

CLARIFICATION No. 2

February 8, 2017

Attention All Bidders and Plan Holders:

Area 5 – Shop Awning Addition Project
FEMA PW 716
F.A. Contract No. TA-5900
County Road Project No. 90-06F7019D

The following clarifications are:

Answers to bidders questions:

(1) What is the desired mounting height for the retractable cords?

Light switch height for reel

(2) Lights are called out as 4-ft triple tube LED. Please clarify what you are requesting. A foot-candle level or lumen output level per fixture is best.

4' LED Striplight that produces 6,000 Lumens minimum, medium diffuse, 40k color temp, 90 CRI color rendering index.

(3) Do you want a switch for light within heated bays at each of the three doors.

Each common lighted area (2 heated bays, 5 common bays) shall have a switch at each walk-in door that enters that area.

(4) Clarify item 5 on the conceptual drawing page 6

We would like a wall mount LED light that provides comparable light to a 100W mercury vapor light.

(5) Clarify Exit lighting.

Exit lighting shall be self-powered Exit/Emergency with double head LED lamps

(6) Appendix D does not include a Power Equipment List.

The Power Equipment List shall be provided by the successful bidder upon request to adequately determine force account work if needed.