

CRP 2121 - MICKELSEN PARKWAY PROJECT

Q & A #1 Date 06/24/2020

Email Bid Questions to geoff.soderquist@lewiscountywa.gov

Question Number	Reference Existing Contract Page # or Addenda	Pre-Bid Question	County Response
1	Special Provisions Page 87	What fertilizer and mulch type and application rates do you require.	The fertilizer will be addressed by addendum. The mulch rates can be found in section 8-023)11)A of the Standard specifications.
2	Plan Sheet 48	My landscaper cannot find a quantity for bid item #28	This will be addressed by addendum.
3	Speical Provisions Pages 13 and 34 Sheet 2	Is the owner providing survey.	See item 37, and the special provisions will be addressed by addendum.
4	Sheets 16-24	What schedule is the conduit and PVC Water Main?	The 2" conduit is schedule 80 and the 12" C900 PVC Water Main is schedule DR 18
5	Addendum 3	Will an updated proposal be provided?	As stated at the bottom of the addendum, "Bidders are instructed to revise pages 1 and 2 of the Proposal as revsied pages have not been prepared for attachment to this addendum. If the bidder fails to make these corrections on the Proposal, the items will be corrected by the County."
6	Special Provisions Page 56	HMA Tolerances and Adjustments under Non-Statistical Evaluation: Is the No. 200 sieve really +/- 1% or is this a miss print?	It is correct, bid in accordance with the Contract
7	Items 37, 111, 205	We have one Question on SHORING OR EXCAVATION CLASS B INCL. HAUL you are showing it as SF is that correct?	The item name will be corrected to the standard item name by addendum, shoring or extra excavation can be found in section 2-09 of the Standard Specifications
8	Sheet 48	Please specify the following plant sizes in the Strom pond planting: Scirpus acutus (hardstem bulrush) & Sparganium emersum (burreed)	Will be addressed by addendum
9	Sheet 48	Are alternate plantings acceptable?	Bid in accordance with the Contract