

ADDENDUM NO. 1

August 5, 2021

Attention All Bidders and Plan Holders:

Cowlitz River Public Access Point Project
CMP 15-1606

The following shall be replaced in the Contract Special Provisions:

(Located in Appendix B, Page 67)

The attached Updated Proposal Form

- The work on this contract is to be performed upon lands whose ownership obligates the Contractor to collect State sales tax from the Contracting Agency. The provisions of Section 1-07.2(2) apply.
- Bid Item 15 – Seeding and Mulching quantity shall be increased to 0.5 Acres total.

The following shall be added to the Contract Special Provisions / Plans:

(Special Provisions Section 8-02.3 *Construction Requirements*, Page 38)

Riparian Hydroseeding Zone area is 0.3 Acres (as depicted in the Contract Plans) and Roadside Hydroseeding area is 0.2 Acres to be applied at the infiltration pond, outlet ditch and all other disturbed areas outside of the finished gravel road and trail surface.

(Plan Sheet 11 of 13, Log Stringer Bridge Section View)

4" x 6" rail posts shall be attached to log stringers with a 5/8" diameter x 12" galvanized lag bolt and washer 3" from the bottom of each rail post.

All bidders will be required to furnish evidence of the receipt of this addendum. This addendum will be incorporated in and made a part of the contract when awarded, and when formally executed.

**END OF
ADDENDUM NO. 1**



Rod Lakey P.E.
Project Engineer

Attachment: Proposal Sheet
(Special Provisions Page 67 Revised 5-Aug-21)

PROPOSAL

TO: LEWIS COUNTY BOARD OF COUNTY COMMISSIONERS
CHEHALIS, WASHINGTON 98532

This certifies that the undersigned has examined the location of the COWLITZ RIVER PUBLIC ACCESS POINT PROJECT, in Lewis County, Washington, and that the plans, specifications and contract governing the work embraced in these improvements, and the method by which payment will be made for said work is understood. The undersigned hereby proposes to undertake and complete the work embraced in this improvement, or as much thereof as can be completed with the money available in accordance with the said plans, specifications and contract, and the following schedules of rates and prices:

NOTE Unit prices for all items, all extensions, and total amount of bid shall be shown:
All entries must be typed or entered in ink.

| ITEM NO. | PLAN QUANTITY | ITEM DESCRIPTION | UNIT PRICE DOLLARS CENTS | AMOUNT DOLLARS CENTS |
|----------------------------|---------------|--|--------------------------|----------------------|
| 1 | 1 L.S. | MOBILIZATION | LUMP SUM | \$ |
| 2 | 1 L.S. | CLEARING AND GRUBBING | LUMP SUM | \$ |
| 3 | 1 L.S. | REMOVAL OF STRUCTURES AND OBSTRUCTIONS | LUMP SUM | \$ |
| 4 | 2,550 C.Y. | ROADWAY EXCAVATION INCL. HAUL | \$ | \$ |
| 5 | 175 C.Y. | GRAVEL BORROW FOR STRUCTURAL EARTH WALL INCL. HAUL | \$ | \$ |
| 6 | 35 L.F. | SCHEDULE A CULV. PIPE 12 IN. DIAM. | \$ | \$ |
| 7 | 60 L.F. | SCHEDULE A CULV. PIPE 18 IN. DIAM. | \$ | \$ |
| 8 | 1 L.S. | LOG STRINGER FOOT BRIDGE | LUMP SUM | \$ |
| 9 | 1 L.S. | PRECAST CONCRETE DOUBLE VAULT TOILET | LUMP SUM | \$ |
| 10 | 1,416 S.F. | GRAVITY BLOCK WALL | \$ | \$ |
| 11 | 1 L.S. | OIL/WATER SEPARATOR | LUMP SUM | \$ |
| 12 | 2,500 TON | CRUSHED SURFACING BASE COURSE | \$ | \$ |
| 13 | 1,110 TON | CRUSHED SURFACING TOP COURSE | \$ | \$ |
| 14 | 7 DAYS | ESC LEAD | \$ | \$ |
| 15 | 0.5 ACRE | SEEDING AND MULCHING | \$ | \$ |
| 16 | 1 L.S. | MITIGATION PLANTING | LUMP SUM | \$ |
| 17 | 1,065 L.F. | HIGH VISIBILITY FENCE | \$ | \$ |
| 18 | 300 L.F. | WATTLE | \$ | \$ |
| 19 | 1 L.S. | PERMANENT SIGNING | LUMP SUM | \$ |
| 20 | 18 EACH | NESTING BOX INSTALLATION | \$ | \$ |
| 21 | 5 EACH | BOLLARD TYPE I | \$ | \$ |
| 22 | 1 EACH | ACCESS CONTROL GATE | \$ | \$ |
| 23 | 0 EST. | REIMBURSEMENT FOR THIRD PARTY DAMAGE | ESTIMATED | \$0.00 |
| 24 | 1 CALC. | MINOR CHANGE | CALCULATED | \$25,000.00 |
| 25 | 1 L.S. | SPILL PREVENTION CONTROL AND COUNTERMEASURES PLAN | LUMP SUM | \$ |
| | | | SUB-TOTAL | \$ |
| Washington State Sales Tax | | | 7.80% | \$ |
| | | | TOTAL BID | \$ |