

Lewis County Public Works
Chehalis, Washington 98532
June 16, 2022

ATTENTION: All Bidders and Planholders

**Crumb Road MP 0.17
Culvert Replacement Project
SM 20F630050017
FEMA Project No. 4539-DR-WA-PW 121
Addendum No. 2**

The Crumb Road MP 0.17 Culvert Replacement Project Contract Special Provisions Section 8-02.3(8) Plant Installation is supplemented with the following:


Planting Zones

Plant material, type, size and density for Zones A and B shall be as outlined in the following table:

Planting Zone	Scientific Name	Common Name	Type	Size of Plants (Material)	Planting Density (Spacing)	Monitoring Stake Marking Color	Number of Plants
Zone A 2,632 S.F. OHWM to 1-ft Above 100-yr Flood Elev. (Approximately 2-ft to 6-ft above Stream CL)	<i>Cornus serices</i>	Red osier dogwood	Shrub	3-ft live stakes (0.5 to 1.5-inch dia.)	3' centers	N/A	100
	<i>Salix lucida</i>	Pacific Willow	Shrub	3-ft live stakes (0.5 to 1.5-inch dia.)	3' centers	N/A	100
	<i>Salix scouleriana</i>	Scouter's willow	Shrub	3-ft live stakes (0.5 to 1.5-inch dia.)	3' centers	N/A	100
Zone B 6,306 S.F. Riparian Zone No trees shall be planted within 10- ft of HMA.	<i>Acer macrophyllum</i>	Big-Leaf Maple	Tree	2 gallon container	12' centers	Red	44
	<i>Pseudotsuga menziesii</i>	Douglas fir	Tree	2 gallon container	12' centers	Orange	44
	<i>Acer circinatum</i>	Vine Maple	Tree	1 gallon container	6' centers	Blue	22
	<i>Oemleria cerasiformis</i>	Indian Plum	Shrub	1 gallon container	6' centers	Brown	22
	<i>Rosa nutkana</i>	Nootka Rose	Shrub	1 gallon container	6' centers	Purple	22
	<i>Symphoricarpos albus</i>	Common Snowberry	Shrub	1 gallon container	6' centers	Black	22

Live Stakes in Planting Zone A shall be planted per WSDOT Standard Plan H-10.15-00 Live Stake Installations. Trees and shrubs shall be planted per WSDOT Standard Plan H-10.10-00 Tree and Shrub Planting Details.

Bidders shall furnish the County with evidence of receipt of this Addendum on the Proposal Signature Page for this Contract. This Addendum will be incorporated in the contract when awarded and when formally executed.


Rod Lakey, P.E.
Project Engineer

End Addendum No. 2