Lewis County Department of Public Works Engineering Division


# CONTRACT PROVISIONS AND PLANS FOR CONSTRUCTION OF:



# HMA PROJECT

CRP 2200C June, 2023

Lewis County Public Works 57 W. Main Chehalis, WA 98532-2626 **Approved for Construction:** 



05/25/2023

**Project Engineer** 

05/26/2023 Date

Assistant County Engineer

BOARD OF COUNTY COMMISSIONERS Sean Swope, District No. 1

Lindsey R. Pollock, DVM, District No. 2 Scott J. Brummer, District No. 3

## TABLE OF CONTENTS

3	TABLE OF CONTENTS	1
4	1-01, DESCRIPTION OF WORK	1
5	1-01.3 Definitions	
6	1-02, BID PROCEDURES AND CONDITIONS	3
7	1-02.1 Prequalification of Bidders	
8	1-02.6 Preparation Of Proposal	4
9	1-02.9 Delivery of Proposal	
10	1-02.12 Public Opening Of Proposal	
11	Date and Time of Bid Opening	
12	1-02.13 Irregular Proposals	5
13	1-02.14 Disqualification of Bidders	
14	1-02.15 Pre Award Information	
15	1-03, AWARD AND EXECUTION OF CONTRACT	9
16	1-03.3 Execution of Contract	9
17	1-03.4 Contract Bond	
18	1-03.7 Judicial Review	11
19	1-05, CONTROL OF WORK	. 11
20	1-05.7 Removal Of Defective And unauthorized Work	11
21	1-05.13 Superintendents, Labor and Equipment of Contractor	12
22	1-05.14 Cooperation With Other Contractors	12
23	1-05.15 Method of Serving Notices	
24	1-07, LEGAL RELATIONS AND RESPONSIBILITIES TO THE PUBLIC	. 12
25	1-07.1 Laws to be Observed	12
26	1-07.2 State Taxes	13
27	1-07.2(1) State Sales Tax — Rule 171	. 13
28	1-07.2(2) State Sales Tax — Rule 170	. 13
29	1-07.2(3) Services	. 14
30	1-07.7 Load Limits	14
31	1-07.9 Wages	14
32	1-07.11 Requirements For Nondiscrimination	14
33	1-07.17 Utilities And Similar Facilities	20
34	1-07.18 Public Liability and Property Damage Insurance	21
35	1-07.18(1) General Requirements	. 21
36	1-07.18(2) Additional Insured	. 22
37	1-07.18(3) Subcontractors	. 22
38	1-07.18(4) Verification of Coverage	. 22
39	1-07.18(5) Coverages and Limits	
40	1-08, PROSECUTION AND PROGRESS	. 24
41	1-08.0 Preliminary Matters	
42	1-08.0(1) Preconstruction Conference	
43	1-08.0(2) Hours of Work	. 24
44	1-08.1 Subcontracting	25
45	1-08.3(2)A Type A Progress Schedule	. 26

Contractor's W	eekly Activities	
1-08.4 Prose	ecution of Work	
1-08.5 Time	for Completion	
1-08.9 Liquidat	ed Damages	
1-09, MEASURE	MENT AND PAYMENT	
1-09.9 Paym	nents	
1-09.11 Dispute	es and Claims	
1-09.11(3) T	ime Limitation and Jurisdiction	
1-09.13 Claims	Resolution	
	enue for Litigation	
1-10, TEMPORA	ARY TRAFFIC CONTROL	
1-10.2 Traffic C	Control Management	
1-10.2(1) Ger	neral	
1-10.2(2) Tra	ffic Control Plans	
1-10.2(3) Cor	formance to Established Standards	
4-04, BALLAST	AND CRUSHED SURFACING	
	ction Requirements	
4-04.3(5) Sha	ping and Compacting	
4-04.4 Measure	ment	
•	ASPHALT	
,	tion	
*	ls	
5-04.2(1) Ho	w to Get a HMA Mix Design on the QPL	
	x Design – Obtaining Project Approval	
· · ·	ction Requirements	
	eather Limitations	
• •	ving Under Traffic	
. ,	uipment	
· / 1	paration of Existing Paved Surfaces	
	oducing/Stockpiling Aggregates and RAP	
. ,	xing	
	reading and Finishing	
	gregate Acceptance Prior to Incorporation in HMA	
· · · •	IA Mixture Acceptance	
	MA Compaction Acceptance	
	eject Work	
	pints	
	urface Smoothness	
· ,	laning (Milling) Bituminous Pavement	
. ,	ealing Pavement Surfaces	
· · ·	MA Road Approaches	
	ement	
	t	
•	ality Assurance Price Adjustment	
	MENT	
-		
	Y ESTIMATES AND PAYMENT POLICY	
Pigeon Springs Road HMA		
CRP 2200C		

1	APPENDICES	
2	APPENDIX A	72
3	WASHINGTON STATE PREVAILING WAGE RATES	
4	APPENDIX B	74
5	BID PROPOSAL DOCUMENTS	
6	APPENDIX C	84
7	CONTRACT DOCUMENTS	
8	CONTRACT BOND FOR Bond No	
9	POWER EQUIPMENT LIST	
10	APPENDIX D	
11	CONTRACT PLANS	
12		
13		
14		

## INTRODUCTION

3 (LCPW GSP)

The following Special Provisions are made a part of this contract and supersede any conflicting provisions of the 2023 Standard Specifications for Road, Bridge, and Municipal Construction.

The said Standard Specifications, the WSDOT Standard Plans, and WSDOT Construction Manual, together with the Special Provisions and the attached plans hereinafter contained, covering all work specified under this contract are incorporated and hereby made a part of this contract. The Special Provisions hereinafter contained shall supersede any conflicting provisions of the Standard Specifications, the WSDOT Standard Plans, and WSDOT Construction Manual.

12 13 **S** 

1

2

6

7

8

9

10

11

14

21

31

38

39 40

41

Several types of Special Provisions are included in this contract; General, Region, Bridges and Structures, and Project Specific. Special Provisions types are differentiated as follows:

1516(date)General Special Provision17(LCPW GSP)Lewis County General Special Provision18(\*\*\*\*\*)Notes a revision to a General Special Provision19and also notes a Project Specific Special Provision.20(APWA GSP)American Public Works Association General Special Provision

General Special Provisions are similar to Standard Specifications in that they typically apply to many
 projects, usually in more than one Region. Usually, the only difference from one project to another is
 the inclusion of variable project data, inserted as a "fill-in".

Project Specific Special Provisions normally appear only in the contract for which they were
 developed.

The following paragraph pertaining to the Standard Specifications shall obtain and be made a part of
 this contract:

Wherever the word "State" or "Contracting Agency" is used it shall mean Lewis County; that wherever the words "Secretary (Secretary of Transportation)" are used they shall mean Lewis County Engineer; that wherever the words "State Treasurer" are used they shall mean Lewis County Treasurer; that wherever the words "State Auditor" are used they shall mean Lewis County Auditor; that wherever the words "Motor Vehicle Fund" are used they shall mean Lewis County Road Fund.

## SPECIAL PROVISIONS

#### DIVISION 1 GENERAL REQUIREMENTS

42 43

## <sup>44</sup> **1-01, DESCRIPTION OF WORK**

45 (March 13, 1995)

This contract provides for the improvement of \*\*\* Pigeon Springs Road by planning bituminous pavement, paving roadway with HMA, and providing shoulder rock and finishing\*\*\* and other related work, all in accordance with the attached Contract Plans, these Contract Provisions, and the Standard Specifications.

## 1-01.3 Definitions

2 3	(January 19, 2022 APWA GSP)
4 5 6	Delete the heading <b>Completion Dates</b> and the three paragraphs that follow it, and replace them with the following:
7	Dates
8 9	<b>Bid Opening Date</b> The date on which the Contracting Agency publicly opens and reads the Bids.
10 11 12	Award Date The date of the formal decision of the Contracting Agency to accept the lowest responsible and responsive Bidder for the Work.
13 14	Contract Execution Date The date the Contracting Agency officially binds the Agency to the Contract.
15 16	<i>Notice to Proceed Date</i> The date stated in the Notice to Proceed on which the Contract time begins.
17	Substantial Completion Date
18 19 20	The day the Engineer determines the Contracting Agency has full and unrestricted use and benefit of the facilities, both from the operational and safety standpoint, any remaining traffic disruptions will be rare and brief, and only minor incidental work, replacement of temporary
21 22	substitute facilities, plant establishment periods, or correction or repair remains for the Physical Completion of the total Contract.
23 24 25 26	<b>Physical Completion Date</b> The day all of the Work is physically completed on the project. All documentation required by the Contract and required by law does not necessarily need to be furnished by the Contractor by this date.
27 28 29 30 31	<b>Completion Date</b> The day all the Work specified in the Contract is completed and all the obligations of the Contractor under the contract are fulfilled by the Contractor. All documentation required by the Contract and required by law must be furnished by the Contractor before establishment of this date.
32 33 34	<i>Final Acceptance Date</i> The date on which the Contracting Agency accepts the Work as complete.
35 36	Supplement this Section with the following:
37 38 39 40 41	All references in the Standard Specifications or WSDOT General Special Provisions, to the terms "Department of Transportation", "Washington State Transportation Commission", "Commission", "Secretary of Transportation", "Secretary", "Headquarters", and "State Treasurer" shall be revised to read "Contracting Agency".
42 43 44	All references to the terms "State" or "state" shall be revised to read "Contracting Agency" unless the reference is to an administrative agency of the State of Washington, a State statute or regulation, or the context reasonably indicates otherwise.
45 46 47	All references to "State Materials Laboratory" shall be revised to read "Contracting Agency designated location".
48 49 50 51	All references to "final contract voucher certification" shall be interpreted to mean the Contracting Agency form(s) by which final payment is authorized, and final completion and acceptance granted.

#### Additive

1

2

3

4 5

6

7

8

9 10

11

12

14

15

16

17

19

20 21

23

24

27

28

- A supplemental unit of work or group of bid items, identified separately in the Bid Proposal, which
- may, at the discretion of the Contracting Agency, be awarded in addition to the base bid.

#### Alternate

One of two or more units of work or groups of bid items, identified separately in the Bid Proposal. from which the Contracting Agency may make a choice between different methods or material of construction for performing the same work.

#### **Business Day**

A business day is any day from Monday through Friday except holidays as listed in Section 1-08.5.

#### 13 **Contract Bond**

The definition in the Standard Specifications for "Contract Bond" applies to whatever bond form(s) are required by the Contract Documents, which may be a combination of a Payment Bond and a Performance Bond.

#### 18 **Contract Documents**

See definition for "Contract".

#### **Contract Time**

22 The period of time established by the terms and conditions of the Contract within which the Work must be physically completed.

#### 25 Notice of Award

26 The written notice from the Contracting Agency to the successful Bidder signifying the Contracting Agency's acceptance of the Bid Proposal.

#### 29 Notice to Proceed

- 30 The written notice from the Contracting Agency or Engineer to the Contractor authorizing and
- 31 directing the Contractor to proceed with the Work and establishing the date on which the Contract 32 time begins.

#### 33 Traffic 34

- Both vehicular and non-vehicular traffic, such as pedestrians, bicyclists, wheelchairs, and 35 equestrian traffic. 36
- 37

#### **1-02, BID PROCEDURES AND CONDITIONS** 38

39 40

41

42 43 44

#### **1-02.1 Pregualification of Bidders**

Delete this Section and replace it with the following:

#### 1-02.1 Qualifications of Bidder

- (January 24, 2011 APWA GSP)
- 45 46 47

48

49 50

Before award of a public works contract, a bidder must meet at least the minimum qualifications of RCW 39.04.350(1) to be considered a responsible bidder and gualified to be awarded a public works project.

#### 1-02.2 Plans and Specifications 51

- (Lewis County) 52
- 53
- The first paragraph of section 1-02.2 is revised to read: 54 Pigeon Springs Road HMA Project 3 CRP 2200C

1 2	Copies of the plans and specifications are on file in the office of:
3	Lowie County Public Works Department
4 5	Lewis County Public Works Department 57 W. Main St.
	Chehalis, Washington 98532
6	(360) 740-1123 Ext. 7
7 8	(000) 740-1123 EXI. 7
9	The second paragraph of section 1-02.2 is revised to read:
10	
11 12 13	Prospective bidders may obtain plans and specifications from Lewis County Public Works Department in Chehalis, Washington or download from Lewis County Website at <a href="http://www.lewiscountywa.gov">www.lewiscountywa.gov</a> .
14 15 16	<b>1-02.6 Preparation Of Proposal</b> (August 2, 2004)
17 18 19	The fifth and sixth paragraphs of Section 1-02.6 are deleted.
20	1-02.9 Delivery of Proposal
21	(January 19, 2022 APWA GSP, Option A)
22	
23 24	Delete this section and replace it with the following:
25	Each Proposal shall be submitted in a sealed envelope, with the Project Name and Project Number
26	as stated in the Call for Bids clearly marked on the outside of the envelope, or as otherwise required
27	in the Bid Documents, to ensure proper handling and delivery.
28 29	To be considered responsive on a FHWA-funded project, the Bidder may be required to submit the
30	following items, as required by Section 1-02.6:
31	
32	<ul> <li>DBE Utilization Certification (WSDOT 272-056)</li> </ul>
33	DBE Written Confirmation Document (WSDOT 422-031) from each DBE firm listed on the
34	Bidder's completed DBE Utilization Certification
35	Good Faith Effort (GFE) Documentation
36	DBE Bid Item Breakdown (WSDOT 272-054)
37	<ul> <li>DBE Trucking Credit Form (WSDOT 272-058)</li> </ul>
38	
39	DBE Utilization Certification
40	The DBE Utilization Certification shall be received at the same location and no later than the time
41	required for delivery of the Proposal. The Contracting Agency will not open or consider any Proposal
42	when the DBE Utilization Certification is received after the time specified for receipt of Proposals or
43	received in a location other than that specified for receipt of Proposals. The DBE Utilization
44	Certification may be submitted in the same envelope as the Bid deposit.
45	
46	DBE Written Confirmation and/or GFE Documentation
47	The DBE Written Confirmation Documents and/or GFE Documents are not required to be submitted
48	with the Proposal. The DBE Written Confirmation Document(s) and/or GFE (if any) shall be received
49	either with the Bid Proposal or as a Supplement to the Bid. The documents shall be received no later
50	than 48 hours (not including Saturdays, Sundays and Holidays) after the time for delivery of the
51	Proposal. To be considered responsive, Bidder's shall submit Written Confirmation Documentation from each DRE firm listed on the Bidder's completed DRE Utilization Cortification and/or the GEE as
52	from each DBE firm listed on the Bidder's completed DBE Utilization Certification and/or the GFE as required by Section 1-02.6
53	required by Section 1-02.6.
54	

#### DBE Bid Item Breakdown and DBE Trucking Credit Form

The DBE Bid Item Breakdown and the DBE Trucking Credit Forms (if applicable) shall be received 2 either with the Bid Proposal or as a Supplement to the Bid. The documents shall be received no later 3 than 48 hours (not including Saturdays, Sundays and Holidays) after the time for delivery of the 4 Proposal. To be considered responsive, Bidders shall submit a completed DBE Bid Item Breakdown 5 and a DBE Trucking Credit Form for each DBE Trucking firm listed on the DBE Utilization Certification, 6 however, minor errors and corrections to DBE Bid Item Breakdown or DBE Trucking Credit Forms 7 will be returned for correction for a period up to five calendar days (not including Saturdays, Sundays 8 and Holidays) after the time for delivery of the Proposal. A DBE Bid Item Breakdown or DBE Trucking 9 Credit Forms that are still incorrect after the correction period will be determined to be non-responsive. 10

11

12

13

14

15

16

17 18

1

Proposals that are received as required will be publicly opened and read as specified in Section 1-02.12. The Contracting Agency will not open or consider any Bid Proposal that is received after the time specified in the Call for Bids for receipt of Bid Proposals, or received in a location other than that specified in the Call for Bids. The Contracting Agency will not open or consider any "Supplemental Information" (DBE confirmations, or GFE documentation) that is received after the time specified above, or received in a location other than that specified in the Call for Bids.

- If an emergency or unanticipated event interrupts normal work processes of the Contracting Agency
   so that Proposals cannot be received at the office designated for receipt of bids as specified in Section
   1-02.12 the time specified for receipt of the Proposal will be deemed to be extended to the same time
   of day specified in the solicitation on the first work day on which the normal work processes of the
   Contracting Agency resume.
- 24 25

26

29

30

31

32

33 34

35

36

37

38 39

40

49

51

52

53

## 1-02.12 Public Opening Of Proposal

27 (\*\*\*\*\*)

#### <sup>28</sup> Section 1-02.12 is supplemented with the following:

#### Date and Time of Bid Opening

The Board of County Commissioners of Lewis County or designee, will open sealed proposals and publicly read them aloud at or after 12:15 p.m. on **June 22, 2023**, at the Lewis County Courthouse, Chehalis, Washington, for the Pigeon Springs Road HMA Project, CRP 2200C.

## SEALED BIDS MUST BE DELIVERED BY OR BEFORE

#### 12:15 P.M. on Thursday, June 22, 2023

(Lewis County official time is displayed on Axxess Intertel phones in the office of the Board of County Commissioners. Bids submitted after 12:15 PM will not be considered for this project.)

#### Delivery and Marking of Sealed Bid Proposals

Sealed proposals must be delivered to the Clerk of the Board of Lewis County Commissioners
 (351 N.W. North Street, Room 210, CMS-01, Chehalis, Washington 98532) by or before 12:15
 p.m. on the date specified for opening, and in an envelope clearly marked: *"SEALED BID FOR THE PIGEON SPRINGS ROAD HMA PROJECT, CRP 2200C, TO BE OPENED AT OR AFTER* 12:15 P.M. ON JUNE 22, 2023".

#### <sup>46</sup> 47 **1-02.13 Irregular Proposals**

(December 30, 2022 APWA GSP)

<sup>50</sup> Delete this section and replace it with the following:

- 1. A Proposal will be considered irregular and will be rejected if:
  - a. The Bidder is not prequalified when so required;
- <sup>54</sup> b. The authorized Proposal form furnished by the Contracting Agency is not used or is <sup>55</sup> altered;

1	С.	The completed Proposal form contains any unauthorized additions, deletions, alternate
2 3	d.	Bids, or conditions; The Bidder adds provisions reserving the right to reject or accept the award, or enter into
4		the Contract;
5	e.	A price per unit cannot be determined from the Bid Proposal;
6	f.	The Proposal form is not properly executed;
7	g.	The Bidder fails to submit or properly complete a subcontractor list (WSDOT Form 271-
8		015), if applicable, as required in Section 1-02.6;
9	h.	The Bidder fails to submit or properly complete a Disadvantaged Business Enterprise
10	:	Certification (WSDOT Form 272-056), if applicable, as required in Section 1-02.6;
11	i.	The Bidder fails to submit Written Confirmations (WSDOT Form 422-031) from each DBE firm listed on the Bidder's completed DBE Utilization Certification that they are in
12		agreement with the bidder's DBE participation commitment, if applicable, as required in
13		Section 1-02.6, or if the written confirmation that is submitted fails to meet the
14		requirements of the Special Provisions;
15 16	j.	The Bidder fails to submit DBE Good Faith Effort documentation, if applicable, as
17	J.	required in Section 1-02.6, or if the documentation that is submitted fails to demonstrate
18		that a Good Faith Effort to meet the Condition of Award was made;
19	k.	The Bidder fails to submit a DBE Bid Item Breakdown (WSDOT Form 272-054), if
20		applicable, as required in Section 1-02.6, or if the documentation that is submitted fails
21		to meet the requirements of the Special Provisions;
22	Ι.	The Bidder fails to submit DBE Trucking Credit Forms (WSDOT Form 272-058), if
23		applicable, as required in Section 1-02.6, or if the documentation that is submitted fails
24		to meet the requirements of the Special Provisions;
25	m.	The Bid Proposal does not constitute a definite and unqualified offer to meet the material
26	-	terms of the Bid invitation; or
27	n.	More than one Proposal is submitted for the same project from a Bidder under the same or different names.
28		or unrerent names.
29 30	2. A Pror	posal may be considered irregular and may be rejected if:
31	a.	The Proposal does not include a unit price for every Bid item;
32	b.	Any of the unit prices are excessively unbalanced (either above or below the amount of
33		a reasonable Bid) to the potential detriment of the Contracting Agency;
34	С.	Receipt of Addenda is not acknowledged;
35	d.	A member of a joint venture or partnership and the joint venture or partnership submit
36		Proposals for the same project (in such an instance, both Bids may be rejected); or
37	e.	If Proposal form entries are not made in ink.
38	1 02 14 Dice	ualification of Bidders
39 40	-	8 APWA GSP, Option B)
41	(1010) 11,2010	
42	Delete this se	ction and replace it with the following:
43		
44	A Bidde	r will be deemed not responsible if the Bidder does not meet the mandatory bidder
45	•	ibility criteria in RCW 39.04.350(1), as amended; or does not meet Supplemental Criteria
46	1-7 liste	d in this Section.
47	-	
48		ntracting Agency will verify that the Bidder meets the mandatory bidder responsibility
49		n RCW 39.04.350(1), and Supplemental Criteria 1-2. Evidence that the Bidder meets
50	Suppien	nental Criteria 3-7 shall be provided by the Bidder as stated later in this Section.
51		
52 53	1. De	elinguent State Taxes
54		

Department of Revenue without a payment plan approved by the Department of 2 Revenue. 3 B. Documentation: The Bidder, if and when required as detailed below, shall sign a 5 statement (on a form to be provided by the Contracting Agency) that the Bidder does not 6 owe delinquent taxes to the Washington State Department of Revenue, or if delinquent 7 taxes are owed to the Washington State Department of Revenue, the Bidder must 8 submit a written payment plan approved by the Department of Revenue, to the 9 Contracting Agency by the deadline listed below. 10 11 2. **Federal Debarment** 12 13 A Criterion: The Bidder shall not currently be debarred or suspended by the Federal 14 government. 15 16 B. Documentation: The Bidder shall not be listed as having an "active exclusion" on the 17 U.S. government's "System for Award Management" database (www.sam.gov). 18 19 3. Subcontractor Responsibility 20 21 A Criterion: The Bidder's standard subcontract form shall include the subcontractor 22 responsibility language required by RCW 39.06.020, and the Bidder shall have an 23 established procedure which it utilizes to validate the responsibility of each of its 24 subcontractors. The Bidder's subcontract form shall also include a requirement that 25 each of its subcontractors shall have and document a similar procedure to determine 26 whether the sub-tier subcontractors with whom it contracts are also "responsible" 27 subcontractors as defined by RCW 39.06.020. 28 29 B. Documentation: The Bidder, if and when required as detailed below, shall submit a copy 30 of its standard subcontract form for review by the Contracting Agency, and a written 31 description of its procedure for validating the responsibility of subcontractors with which 32 it contracts. 33 34 4. **Claims Against Retainage and Bonds** 35 36 A Criterion: The Bidder shall not have a record of excessive claims filed against the 37 retainage or payment bonds for public works projects in the three years prior to the bid 38 submittal date, that demonstrate a lack of effective management by the Bidder of making 39 timely and appropriate payments to its subcontractors, suppliers, and workers, unless 40 there are extenuating circumstances and such circumstances are deemed acceptable to 41 the Contracting Agency. 42 43 B. Documentation: The Bidder, if and when required as detailed below, shall submit a list of 44 the public works projects completed in the three years prior to the bid submittal date that 45 have had claims against retainage and bonds and include for each project the following 46 information: 47 48 Name of project 49 The owner and contact information for the owner; . 50 A list of claims filed against the retainage and/or payment bond for any of the . 51 projects listed; 52 A written explanation of the circumstances surrounding each claim and the ultimate 53 resolution of the claim. 54 55

A Criterion: The Bidder shall not owe delinquent taxes to the Washington State

## 5. **Public Bidding Crime**

- A <u>Criterion</u>: The Bidder and/or its owners shall not have been convicted of a crime involving bidding on a public works contract in the five years prior to the bid submittal date.
- B. <u>Documentation</u>: The Bidder, if and when required as detailed below, shall sign a statement (on a form to be provided by the Contracting Agency) that the Bidder and/or its owners have not been convicted of a crime involving bidding on a public works contract.

#### 6. <u>Termination for Cause / Termination for Default</u>

- A <u>Criterion</u>: The Bidder shall not have had any public works contract terminated for cause or terminated for default by a government agency in the five years prior to the bid submittal date, unless there are extenuating circumstances and such circumstances are deemed acceptable to the Contracting Agency.
- B. <u>Documentation</u>: The Bidder, if and when required as detailed below, shall sign a statement (on a form to be provided by the Contracting Agency) that the Bidder has not had any public works contract terminated for cause or terminated for default by a government agency in the five years prior to the bid submittal date; or if Bidder was terminated, describe the circumstances.

## 7. Lawsuits

- A <u>Criterion</u>: The Bidder shall not have lawsuits with judgments entered against the Bidder in the five years prior to the bid submittal date that demonstrate a pattern of failing to meet the terms of contracts, unless there are extenuating circumstances and such circumstances are deemed acceptable to the Contracting Agency
- B. <u>Documentation</u>: The Bidder, if and when required as detailed below, shall sign a statement (on a form to be provided by the Contracting Agency) that the Bidder has not had any lawsuits with judgments entered against the Bidder in the five years prior to the bid submittal date that demonstrate a pattern of failing to meet the terms of contracts, or shall submit a list of all lawsuits with judgments entered against the Bidder in the five years prior to the bid submittal date, along with a written explanation of the circumstances surrounding each such lawsuit. The Contracting Agency shall evaluate these explanations to determine whether the lawsuits demonstrate a pattern of failing to meet of terms of construction related contracts
- As evidence that the Bidder meets the Supplemental Criteria stated above, the apparent low Bidder must submit to the Contracting Agency by 12:00 P.M. (noon) of the second business day following the bid submittal deadline, a written statement verifying that the Bidder meets the supplemental criteria together with supporting documentation (sufficient in the sole judgment of the Contracting Agency) demonstrating compliance with the Supplemental Criteria. The Contracting Agency reserves the right to request further documentation as needed from the low Bidder and documentation from other Bidders as well to assess Bidder responsibility and compliance with all bidder responsibility criteria. The Contracting Agency also reserves the right to obtain information from third-parties and independent sources of information concerning a Bidder's compliance with the mandatory and supplemental criteria, and to use that information in their evaluation. The Contracting Agency may consider mitigating factors in determining whether the Bidder complies with the requirements of the supplemental criteria.

- The basis for evaluation of Bidder compliance with these mandatory and supplemental criteria shall include any documents or facts obtained by Contracting Agency (whether from the Bidder or third parties) including but not limited to: (i) financial, historical, or operational data from the Bidder; (ii) information obtained directly by the Contracting Agency from others for whom the Bidder has worked, or other public agencies or private enterprises; and (iii) any additional information obtained by the Contracting Agency which is believed to be relevant to the matter.
- If the Contracting Agency determines the Bidder does not meet the bidder responsibility criteria 8 above and is therefore not a responsible Bidder, the Contracting Agency shall notify the Bidder in 9 writing, with the reasons for its determination. If the Bidder disagrees with this determination, it 10 may appeal the determination within two (2) business days of the Contracting Agency's 11 determination by presenting its appeal and any additional information to the Contracting Agency. 12 The Contracting Agency will consider the appeal and any additional information before issuing its 13 final determination. If the final determination affirms that the Bidder is not responsible, the 14 Contracting Agency will not execute a contract with any other Bidder until at least two business 15 days after the Bidder determined to be not responsible has received the Contracting Agency's 16 final determination. 17
- Request to Change Supplemental Bidder Responsibility Criteria Prior To Bid: Bidders with
   concerns about the relevancy or restrictiveness of the Supplemental Bidder Responsibility Criteria
   may make or submit requests to the Contracting Agency to modify the criteria. Such requests
   shall be in writing, describe the nature of the concerns, and propose specific modifications to the
   criteria. Bidders shall submit such requests to the Contracting Agency no later than five (5)
   business days prior to the bid submittal deadline and address the request to the Project Engineer
   or such other person designated by the Contracting Agency in the Bid Documents.
  - 1-02.15 Pre Award Information
- 28 (December 30, 2022 APWA GSP)
  - Revise this section to read:
  - Before awarding any contract, the Contracting Agency may require one or more of these items or actions of the apparent lowest responsible bidder:
    - 1. A complete statement of the origin, composition, and manufacture of any or all materials to be used,
    - 2. Samples of these materials for quality and fitness tests,
    - 3. A progress schedule (in a form the Contracting Agency requires) showing the order of and time required for the various phases of the work,
- <sup>39</sup> 4. A breakdown of costs assigned to any bid item,
  - 5. Attendance at a conference with the Engineer or representatives of the Engineer,
- 6. Obtain, and furnish a copy of, a business license to do business in the city or county where the work is located.
  - 7. Any other information or action taken that is deemed necessary to ensure that the bidder is the lowest responsible bidder.
- 44 45

43

1

2

3

4

5

6 7

18

26

27

29

30 31

32

33

34

35

36

37

38

- <sup>46</sup> **1-03, AWARD AND EXECUTION OF CONTRACT**
- <sup>47</sup> 48 **1-03.3 Execution of Contract**
- <sup>49</sup> (January 19, 2022 APWA GSP) <sup>50</sup>
- <sup>51</sup> Revise this section to read:

2 successful Bidder shall provide the information necessary to execute the Contract to the 3 Contracting Agency. The Bidder shall send the contact information, including the full name, email 4 address, and phone number, for the authorized signer and bonding agent to the Contracting 5 Agency. 6 7 Copies of the Contract Provisions, including the unsigned Form of Contract, will be available for 8 signature by the successful bidder on the first business day following award. The number of copies 9 to be executed by the Contractor will be determined by the Contracting Agency. 10 Within 15 calendar days after the award date, the successful bidder shall return the signed 11 Contracting Agency-prepared contract, an insurance certification as required by Section 1-07.18, a 12 satisfactory bond as required by law and Section 1-03.4, the Transfer of Coverage form for the 13 Construction Stormwater General Permit with sections I, III, and VIII completed when provided. 14 Before execution of the contract by the Contracting Agency, the successful bidder shall provide any 15 pre-award information the Contracting Agency may require under Section 1-02.15. 16 17 Until the Contracting Agency executes a contract, no proposal shall bind the Contracting Agency nor 18 shall any work begin within the project limits or within Contracting Agency-furnished sites. The 19 Contractor shall bear all risks for any work begun outside such areas and for any materials ordered 20 before the contract is executed by the Contracting Agency. 21 22 If the bidder experiences circumstances beyond their control that prevents return of the contract 23 documents within the calendar days after the award date stated above, the Contracting Agency 24 may grant up to a maximum of 5 additional calendar days for return of the documents, provided the 25 Contracting Agency deems the circumstances warrant it. 26 27 1-03.4 Contract Bond 28 (July 23, 2015 APWA GSP) 29 30 Delete the first paragraph and replace it with the following: 31 32 The successful bidder shall provide executed payment and performance bond(s) for the full contract 33 amount. The bond may be a combined payment and performance bond; or be separate payment 34 and performance bonds. In the case of separate payment and performance bonds, each shall be 35 for the full contract amount. The bond(s) shall: 36 1. Be on Contracting Agency-furnished form(s); 37 2. Be signed by an approved surety (or sureties) that: 38 a. Is registered with the Washington State Insurance Commissioner, and 39 b. Appears on the current Authorized Insurance List in the State of Washington published by 40 the Office of the Insurance Commissioner, 41 Guarantee that the Contractor will perform and comply with all obligations, duties, and 42 conditions under the Contract, including but not limited to the duty and obligation to indemnify, 43 defend, and protect the Contracting Agency against all losses and claims related directly or 44 indirectly from any failure: 45 a. Of the Contractor (or any of the employees, subcontractors, or lower tier subcontractors of 46 the Contractor) to faithfully perform and comply with all contract obligations, conditions, and 47 duties, or 48 b. Of the Contractor (or the subcontractors or lower tier subcontractors of the Contractor) to 49 pay all laborers, mechanics, subcontractors, lower tier subcontractors, material person, or 50 any other person who provides supplies or provisions for carrying out the work: 51 4. Be conditioned upon the payment of taxes, increases, and penalties incurred on the project 52 under titles 50, 51, and 82 RCW; and 53

Within 3 calendar days of Award date (not including Saturdays, Sundays and Holidays), the

- Be accompanied by a power of attorney for the Surety's officer empowered to sign the bond; and
  - 6. Be signed by an officer of the Contractor empowered to sign official statements (sole proprietor or partner). If the Contractor is a corporation, the bond(s) must be signed by the president or vice president, unless accompanied by written proof of the authority of the individual signing the bond(s) to bind the corporation (i.e., corporate resolution, power of attorney, or a letter to such effect signed by the president or vice president).

#### 1-03.7 Judicial Review

1

2

3

4

5

6

7 8

9 10

11

12 13

14

15

16

17

18 19

20 21

24

26

31

38

46

54

(December 30, 2022 APWA GSP)

Revise this section to read:

All decision made by the Contracting Agency regarding the Award and execution of the Contract or Bid rejection shall be conclusive subject to the scope of judicial review permitted under Washington Law. Such review, if any, shall be timely filed in the Superior Court of <u>the county where the Contracting</u> <u>Agency headquarters is located</u>, provided that where an action is asserted against a county, RCW <u>36.01.050 shall control venue and jurisdiction</u>.

1-05, CONTROL OF WORK

#### 22 1-05.7 Removal Of Defective And unauthorized Work

- 23 (October 1, 2005 APWA GSP)
- <sup>25</sup> Supplement this section with the following:

If the Contractor fails to remedy defective or unauthorized work within the time specified in a written
 notice from the Engineer, or fails to perform any part of the work required by the Contract Documents,
 the Engineer may correct and remedy such work as may be identified in the written notice, with
 Contracting Agency forces or by such other means as the Contracting Agency may deem necessary.

- If the Contractor fails to comply with a written order to remedy what the Engineer determines to be
   an emergency situation, the Engineer may have the defective and unauthorized work corrected
   immediately, have the rejected work removed and replaced, or have work the Contractor refuses to
   perform completed by using Contracting Agency or other forces. An emergency situation is any
   situation when, in the opinion of the Engineer, a delay in its remedy could be potentially unsafe, or
   might cause serious risk of loss or damage to the public.
- <sup>39</sup>Direct or indirect costs incurred by the Contracting Agency attributable to correcting and remedying <sup>40</sup>defective or unauthorized work, or work the Contractor failed or refused to perform, shall be paid by <sup>41</sup>the Contractor. Payment will be deducted by the Engineer from monies due, or to become due, the <sup>42</sup>Contractor. Such direct and indirect costs shall include in particular, but without limitation, <sup>43</sup>compensation for additional professional services required, and costs for repair and replacement of <sup>44</sup>work of others destroyed or damaged by correction, removal, or replacement of the Contractor's <sup>45</sup>unauthorized work.
- <sup>47</sup> No adjustment in contract time or compensation will be allowed because of the delay in the
   <sup>48</sup> performance of the work attributable to the exercise of the Contracting Agency's rights provided by
   <sup>49</sup> this Section.
- The rights exercised under the provisions of this section shall not diminish the Contracting Agency's right to pursue any other avenue for additional remedy or damages with respect to the Contractor's failure to perform the work as required.

1-05.13 Superintendents, Labor and Equipment of Contractor 1 (August 14, 2013 APWA GSP) 2 3 Delete the sixth and seventh paragraphs of this section. 4 5 1-05.14 Cooperation With Other Contractors 6 Section 1-05.14 is supplemented with the following: 7 (March 13, 1995) 8 9 Other Contracts Or Other Work 10 It is anticipated that the following work adjacent to or within the limits of this project will be performed 11 by others during the course of this project and will require coordination of the work: 12 13 \$\$ Utilities and/or Utility Contractors. The contractor's attention is directed to Section 1-07.17 14 these Special Provisions. \$\$ 15 16 1-05.15 Method of Serving Notices 17 (December 30, 2022 APWA GSP) 18 Revise the second paragraph to read: 19 20 All correspondence from the Contractor shall be directed to the Project Engineer. All 21 correspondence from the Contractor constituting any notification, notice of protest, notice of dispute, 22 or other correspondence constituting notification required to be furnished under the Contract, must 23 be in paper format, hand delivered or sent via mail delivery service to the Project Engineer's office. 24 Electronic copies such as e-mails or electronically delivered copies of correspondence will not 25 constitute such notice and will not comply with the requirements of the Contract. 26 27 1-07, LEGAL RELATIONS AND RESPONSIBILITIES TO THE PUBLIC 28 29 1-07.1 Laws to be Observed 30 (October 1, 2005 APWA GSP) 31 32 Supplement this section with the following: 33 34 In cases of conflict between different safety regulations, the more stringent regulation shall apply. 35 36 The Washington State Department of Labor and Industries shall be the sole and paramount 37 administrative agency responsible for the administration of the provisions of the Washington Industrial 38 Safety and Health Act of 1973 (WISHA). 39 40 The Contractor shall maintain at the project site office, or other well-known place at the project site, 41 all articles necessary for providing first aid to the injured. The Contractor shall establish, publish, and 42 make known to all employees, procedures for ensuring immediate removal to a hospital, or doctor's 43 care, persons, including employees, who may have been injured on the project site. Employees 44 should not be permitted to work on the project site before the Contractor has established and made 45 known procedures for removal of injured persons to a hospital or a doctor's care. 46 47 The Contractor shall have sole responsibility for the safety, efficiency, and adequacy of the 48 Contractor's plant, appliances, and methods, and for any damage or injury resulting from their failure, 49 or improper maintenance, use, or operation. The Contractor shall be solely and completely 50 responsible for the conditions of the project site, including safety for all persons and property in the 51 performance of the work. This requirement shall apply continuously, and not be limited to normal 52 working hours. The required or implied duty of the Engineer to conduct construction review of the 53

Contractor's performance does not, and shall not, be intended to include review and adequacy of the Contractor's safety measures in, on, or near the project site.

#### 1-07.2 State Taxes

Delete this section, including its sub-sections, in its entirety and replace it with the following:

#### 1-07.2 State Sales Tax

(June 27, 2011 APWA GSP)

The Washington State Department of Revenue has issued special rules on the State sales tax. Sections 1-07.2(1) through 1-07.2(3) are meant to clarify those rules. The Contractor should contact the Washington State Department of Revenue for answers to questions in this area. The Contracting Agency will not adjust its payment if the Contractor bases a bid on a misunderstood tax liability.

15 16

1

2 3

> 4 5

> 6 7

8

9 10

11

12

13

14

17

18

19

The Contractor shall include all Contractor-paid taxes in the unit bid prices or other contract amounts. In some cases, however, state retail sales tax will not be included. Section 1-07.2(2) describes this exception.

The Contracting Agency will pay the retained percentage (or release the Contract Bond if a FHWA funded Project) only if the Contractor has obtained from the Washington State Department of
 Revenue a certificate showing that all contract-related taxes have been paid (RCW 60.28.051).
 The Contracting Agency may deduct from its payments to the Contractor any amount the
 Contractor may owe the Washington State Department of Revenue, whether the amount owed
 relates to this contract or not. Any amount so deducted will be paid into the proper State fund.

27 28

29

#### 1-07.2(1) State Sales Tax — Rule 171

WAC 458-20-171, and its related rules, apply to building, repairing, or improving streets, roads, etc., 30 which are owned by a municipal corporation, or political subdivision of the state, or by the United 31 States, and which are used primarily for foot or vehicular traffic. This includes storm or combined 32 sewer systems within and included as a part of the street or road drainage system and power lines 33 when such are part of the roadway lighting system. For work performed in such cases, the 34 Contractor shall include Washington State Retail Sales Taxes in the various unit bid item prices, or 35 other contract amounts, including those that the Contractor pays on the purchase of the materials. 36 equipment, or supplies used or consumed in doing the work. 37

38 39

50

1-07.2(2) State Sales Tax — Rule 170

- 40 WAC 458-20-170, and its related rules, apply to the constructing and repairing of new or existing 41 buildings, or other structures, upon real property. This includes, but is not limited to, the 42 construction of streets, roads, highways, etc., owned by the state of Washington; water mains and 43 their appurtenances; sanitary sewers and sewage disposal systems unless such sewers and 44 disposal systems are within, and a part of, a street or road drainage system; telephone, telegraph, 45 electrical power distribution lines, or other conduits or lines in or above streets or roads, unless 46 such power lines become a part of a street or road lighting system; and installing or attaching of any 47 article of tangible personal property in or to real property, whether or not such personal property 48 becomes a part of the realty by virtue of installation. 49
- For work performed in such cases, the Contractor shall collect from the Contracting Agency, retail sales tax on the full contract price. The Contracting Agency will automatically add this sales tax to each payment to the Contractor. For this reason, the Contractor shall not include the retail sales tax in the unit bid item prices, or in any other contract amount subject to Rule 170, with the following exception.

1	
2	Exception: The Contracting Agency will not add in sales tax for a payment the Contractor or a
3	subcontractor makes on the purchase or rental of tools, machinery, equipment, or consumable
4	supplies not integrated into the project. Such sales taxes shall be included in the unit bid item
5	prices or in any other contract amount.
6	
7	1-07.2(3) Services
8	
	The Contractor shall not collect retail sales tax from the Contracting Agency on any contract wholly
9	
10	for professional or other services (as defined in Washington State Department of Revenue Rules
11	138 and 244).
12	
13	1-07.7 Load Limits
14	Section 1-07.7 is supplemented with the following:
15	
16	(Lewis County)
17	If the source of materials provided by the Contractor necessitates hauling over roads other than
18	Lewis County roads, the Contractor shall, at the Contractor's expense, make all arrangements for
19	the use of the haul routes.
20	
21	Any vehicle providing material paid for by the ton, on the project, will provide licensed tonnage for
22	that vehicle.
23	1-07.9 Wages
24	1-07.5 Wages
25	General
26	
27	Section 1-07.9(1) is supplemented with the following:
28	(*****)
29	(*****) The Oracle sector is a surger to drive the sector of any surger list has the sector of its sector is it is a
30	The State rates incorporated in this contract are applicable to all construction activities
31	associated with this contract.
32	
33	1-07.11 Requirements For Nondiscrimination
34	Section 1-07.11 is supplemented with the following:
35	
36	(October 3, 2022)
37	Requirement for Affirmative Action to Ensure Equal Employment Opportunity (Executive Order
38	<u>11246)</u>
39	
40	1. The Contractor's attention is called to the Equal Opportunity Clause and the Standard Federal
41	Equal Employment Opportunity Construction Contract Specifications set forth herein.
42	
42	2. The goals and timetables for minority and female participation set by the Office of Federal
	Contract Compliance Programs, expressed in percentage terms for the Contractor's aggregate
44	work force in each construction craft and in each trade on all construction work in the covered
45	area, are as follows:
46	
47	Warran Statewide
48	Women - Statewide
49	
50	<u>Timetable</u> <u>Goal</u>
51	
52	Until further notice 6.9%
53	Minorities - by Standard Metropolitan Statistical Area (SMSA)
54	

1	Spokane, WA:
2	SMSA Counties:
3	Spokane, WA 2.8
4	WA Spokane.
5	Non-SMSA Counties 3.0
6	WA Adams; WA Asotin; WA Columbia; WA Ferry; WA Garfield; WA Lincoln, WA
	Pend Oreille; WA Stevens; WA Whitman.
7	
8	Dichland WA
9	Richland, WA
10	SMSA Counties:
11	Richland Kennewick, WA 5.4
12	WA Benton; WA Franklin.
13	Non-SMSA Counties 3.6
14	WA Walla Walla.
15	
16	Yakima, WA:
17	SMSA Counties:
18	Yakima, WA 9.7
	WA Yakima.
19	Non-SMSA Counties 7.2
20	
21	WA Chelan; WA Douglas; WA Grant; WA Kittitas; WA Okanogan.
22	
23	Seattle, WA:
24	SMSA Counties:
25	Seattle Everett, WA 7.2
26	WA King; WA Snohomish.
27	Tacoma, WA 6.2
28	WA Pierce.
	Non-SMSA Counties 6.1
29	WA Clallam; WA Grays Harbor; WA Island; WA Jefferson; WA Kitsap; WA Lewis;
30	WA Clainant, WA Clays Habor, WA Island, WA Senerson, WA Risap, WA Lewis, WA Mason; WA Pacific; WA San Juan; WA Skagit; WA Thurston; WA Whatcom.
31	WA Mason, WA Facilic, WA San Juan, WA Skayii, WA Muision, WA Whatcom.
32	
33	Portland, OR:
34	SMSA Counties:
35	Portland, OR-WA 4.5
36	WA Clark.
37	Non-SMSA Counties 3.8
38	WA Cowlitz; WA Klickitat; WA Skamania; WA Wahkiakum.
39	
40	These goals are applicable to each nonexempt Contractor's total on-site construction workforce,
41	regardless of whether or not part of that workforce is performing work on a Federal, or federally
41	assisted project, contract, or subcontract until further notice. Compliance with these goals and
	time tables is enforced by the Office of Federal Contract compliance Programs.
43	
44	The Contractor's compliance with the Executive Order and the regulations in 41 CEP Part 60.4
45	The Contractor's compliance with the Executive Order and the regulations in 41 CFR Part 60-4
46	shall be based on its implementation of the Equal Opportunity Clause, specific affirmative action
47	obligations required by the specifications set forth in 41 CFR 60-4.3(a), and its efforts to meet
48	the goals. The hours of minority and female employment and training must be substantially
49	uniform throughout the length of the contract, in each construction craft and in each trade, and
50	the Contractor shall make a good faith effort to employ minorities and women evenly on each
51	of its projects. The transfer of minority or female employees or trainees from Contractor to
52	Contractor or from project to project for the sole purpose of meeting the Contractor's goal shall
	be a violation of the contract, the Executive Order and the regulations in 41 CFR Part 60-4.
53	Compliance with the goals will be measured against the total work hours performed.
54	Compliance with the years will be measured against the total work nours performed.
55	

1 2 3 4 5 6 7 8 9	3.	Program of \$10,0 resulting number dollar at	ns (OFCC 00 or mor g from thi of the su mount of	hall provide written notification to the Office of Federal Contract Compliance (P) within 10 working days of award of any construction subcontract in excess re that are Federally funded, at any tier for construction work under the contract is solicitation. The notification shall list the name, address and telephone ubcontractor; employer identification number of the subcontractor; estimated the subcontract; estimated starting and completion dates of the subcontract; inical area in which the contract is to be performed. The notification shall be
10 11 12 13 14 15 16 17		Offi Attr Sar 90 Sar (41	ice of Fed n: Regiona n Francisc – 7 <sup>th</sup> Stree n Francisc 5) 625-77	
18 19 20	4.	designa	ted hereir	
21 22 23	<u>Orc</u>	ler 11246	<u>5)</u>	al Employment Opportunity Construction Contract Specifications (Executive
24	1.	As used	l in these	specifications:
25 26 27		a.		Area means the geographical area described in the solicitation from which tract resulted;
28 29 30		b.		means Director, Office of Federal Contract Compliance Programs, United Department of Labor, or any person to whom the Director delegates authority;
31 32 33		С.	• •	er Identification Number means the Federal Social Security number used on loyer's Quarterly Federal Tax Return, U. S. Treasury Department Form 941;
34 35 36		d.	Minority	includes:
37 38			(1)	Black, a person having origins in any of the Black Racial Groups of Africa.
39 40 41 42			(2)	Hispanic, a fluent Spanish speaking, Spanish surnamed person of Mexican, Puerto Rican, Cuban, Central American, South American, or other Spanish origin.
43 44 45			(3)	Asian or Pacific Islander, a person having origins in any of the original peoples of the Pacific rim or the Pacific Islands, the Hawaiian Islands and Samoa.
46 47 48 49			(4)	American Indian or Alaskan Native, a person having origins in any of the original peoples of North America, and who maintain cultural identification through tribal affiliation or community recognition.
50 51 52 53 54 55	2.	involving \$10,000 goals fo	g any cor ) the prov	ontractor, or any subcontractor at any tier, subcontracts a portion of the work instruction trade, it shall physically include in each subcontract in excess of risions of these specifications and the Notice which contains the applicable and female participation and which is set forth in the solicitations from which lted.

- 3. If the Contractor is participating (pursuant to 41 CFR 60-4.5) in a Hometown Plan approved by the U.S. Department of Labor in the covered area either individually or through an association, its affirmative action obligations on all work in the Plan area (including goals and timetables) shall be in accordance with that Plan for those trades which have unions participating in the Plan. Contractors must be able to demonstrate their participation in and compliance with the provisions of any such Hometown Plan. Each Contractor or subcontractor participating in an approved Plan is individually required to comply with its obligations under the EEO clause, and to make a good faith effort to achieve each goal under the Plan in each trade in which it has employees. The overall good faith performance by other Contractor's or subcontractor's failure to take good faith effort to achieve the Plan goals and timetables.
- 4. The Contractor shall implement the specific affirmative action standards provided in paragraphs 7a through 7p of this Special Provision. The goals set forth in the solicitation from which this contract resulted are expressed as percentages of the total hours of employment and training of minority and female utilization the Contractor should reasonably be able to achieve in each construction trade in which it has employees in the covered area. Covered construction contractors performing construction work in geographical areas where they do not have a Federal or federally assisted construction contract shall apply the minority and female goals established for the geographical area where the work is being performed. The Contractor is expected to make substantially uniform progress in meeting its goals in each craft during the period specified.
- 5. Neither the provisions of any collective bargaining agreement, nor the failure by a union with whom the Contractor has a collective bargaining agreement, to refer either minorities or women shall excuse the Contractor's obligations under these specifications, Executive Order 11246, or the regulations promulgated pursuant thereto.
- 6. In order for the nonworking training hours of apprentices and trainees to be counted in meeting the goals, such apprentices and trainees must be employed by the Contractor during the training period, and the Contractor must have made a commitment to employ the apprentices and trainees at the completion of their training, subject to the availability of employment opportunities. Trainees must be trained pursuant to training programs approved by the U.S. Department of Labor.
- 7. The Contractor shall take specific affirmative actions to ensure equal employment opportunity. The evaluation of the Contractor's compliance with these specifications shall be based upon its effort to achieve maximum results from its action. The Contractor shall document these efforts fully, and shall implement affirmative action steps at least as extensive as the following:
  - a. Ensure and maintain a working environment free of harassment, intimidation, and coercion at all sites, and in all facilities at which the Contractor's employees are assigned to work. The Contractor, where possible, will assign two or more women to each construction project. The Contractor shall specifically ensure that all foremen, superintendents, and other on-site supervisory personnel are aware of and carry out the Contractor's obligation to maintain such a working environment, with specific attention to minority or female individuals working at such sites or in such facilities.
- b. Establish and maintain a current list of minority and female recruitment sources, provide written notification to minority and female recruitment sources and to community organizations when the Contractor or its unions have employment opportunities available, and maintain a record of the organizations' responses.

- c. Maintain a current file of the names, addresses and telephone numbers of each minority and female off-the-street applicant and minority or female referral from a union, a recruitment source or community organization and of what action was taken with respect to each such individual. If such individual was sent to the union hiring hall for referral and was not referred back to the Contractor by the union or, if referred, not employed by the Contractor, this shall be documented in the file with the reason therefor, along with whatever additional actions the Contractor may have taken.
- d. Provide immediate written notification to the Director when the union or unions with which the Contractor has a collective bargaining agreement has not referred to the Contractor a minority person or woman sent by the Contractor, or when the Contractor has other information that the union referral process has impeded the Contractor's efforts to meet its obligations.
- e. Develop on-the-job training opportunity and/or participate in training programs for the area which expressly include minorities and women, including upgrading programs and apprenticeship and trainee programs relevant to the Contractor's employment needs, especially those programs funded or approved by the U.S. Department of Labor. The Contractor shall provide notice of these programs to the sources compiled under 7b above.
- f. Disseminate the Contractor's EEO policy by providing notice of the policy to unions and training programs and requesting their cooperation in assisting the Contractor in meeting its EEO obligations; by including it in any policy manual and collective bargaining agreement; by publicizing it in the company newspaper, annual report, etc.; by specific review of the policy with all management personnel and with all minority and female employees at least once a year; and by posting the company EEO policy on bulletin boards accessible to all employees at each location where construction work is performed.
  - g. Review, at least annually, the company's EEO policy and affirmative action obligations under these specifications with all employees having any responsibility for hiring, assignment, layoff, termination or other employment decisions including specific review of these items with on-site supervisory personnel such as Superintendents, General Foremen, etc., prior to the initiation of construction work at any job site. A written record shall be made and maintained identifying the time and place of these meetings, persons attending, subject matter discussed, and disposition of the subject matter.
    - h. Disseminate the Contractor's EEO policy externally by including it in any advertising in the news media, specifically including minority and female news media, and providing written notification to and discussing the Contractor's EEO policy with other Contractors and Subcontractors with whom the Contractor does or anticipates doing business.
- i. Direct its recruitment efforts, both oral and written to minority, female and community organizations, to schools with minority and female students and to minority and female recruitment and training organizations serving the Contractor's recruitment area and employment needs. Not later than one month prior to the date for the acceptance of applications for apprenticeship or other training by any recruitment source, the Contractor shall send written notification to organizations such as the above, describing the openings, screening procedures, and tests to be used in the selection process.

2

3

5

6

7 8

9

10

11

12

13 14

15

16

17

18

19

20 21

22

23

24

25

26

27

28

29 30

31

32

33

34

35

36

37

38 39

40

41

42

43

44 45

46

47

48

49

50

51

52

- j. Encourage present minority and female employees to recruit other minority persons and women and where reasonable, provide after school, summer and vacation employment to minority and female youth both on the site and in other areas of a Contractor's work force.
  - k. Validate all tests and other selection requirements where there is an obligation to do so under 41 CFR Part 60-3.
  - I. Conduct, at least annually, an inventory and evaluation of all minority and female personnel for promotional opportunities and encourage these employees to seek or to prepare for, through appropriate training, etc., such opportunities.
  - m. Ensure that seniority practices, job classifications, work assignments and other personnel practices, do not have a discriminatory effect by continually monitoring all personnel and employment related activities to ensure that the EEO policy and the Contractor's obligations under these specifications are being carried out.
    - n. Ensure that all facilities and company activities are nonsegregated except that separate or single-user toilet and necessary changing facilities shall be provided to assure privacy between the sexes.
    - Document and maintain a record of all solicitations of offers for subcontracts from minority and female construction contractors and suppliers, including circulation of solicitations to minority and female contractor associations and other business associations.
      - p. Conduct a review, at least annually, of all supervisors' adherence to and performance under the Contractor's EEO policies and affirmative action obligations.
- 8. Contractors are encouraged to participate in voluntary associations which assist in fulfilling one or more of their affirmative action obligations (7a through 7p). The efforts of a contractor association, joint contractor-union, contractor-community, or other similar group of which the Contractor is a member and participant, may be asserted as fulfilling any one or more of the obligations under 7a through 7p of this Special Provision provided that the Contractor actively participates in the group, makes every effort to assure that the group has a positive impact on the employment of minorities and women in the industry, ensure that the concrete benefits of the program are reflected in the Contractor's minority and female work-force participation, makes a good faith effort to meet its individual goals and timetables, and can provide access to documentation which demonstrate the effectiveness of actions taken on behalf of the Contractor. The obligation to comply, however, is the Contractor's noncompliance.
  - 9. A single goal for minorities and a separate single goal for women have been established. The Contractor, however, is required to provide equal employment opportunity and to take affirmative action for all minority groups, both male and female, and all women, both minority and non-minority. Consequently, the Contractor may be in violation of the Executive Order if a particular group is employed in substantially disparate manner (for example, even though the Contractor has achieved its goals for women generally, the Contractor may be in violation of the Executive Order if a specific minority group of women is underutilized).
    - 10. The Contractor shall not use the goals and timetables or affirmative action standards to discriminate against any person because of race, color, religion, sex, or national origin.

11. The Contractor shall not enter into any subcontract with any person or firm debarred from Government contracts pursuant to Executive Order 11246.

- 12. The Contractor shall carry out such sanctions and penalties for violation of these specifications and of the Equal Opportunity Clause, including suspensions, terminations and cancellations of existing subcontracts as may be imposed or ordered pursuant to Executive Order 11246, as amended, and its implementing regulations by the Office of Federal Contract Compliance Programs. Any Contractor who fails to carry out such sanctions and penalties shall be in violation of these specifications and Executive Order 11246, as amended.
- 13. The Contractor, in fulfilling its obligations under these specifications, shall implement specific affirmative action steps, at least as extensive as those standards prescribed in paragraph 7 of this Special Provision, so as to achieve maximum results from its efforts to ensure equal employment opportunity. If the Contractor fails to comply with the requirements of the Executive Order, the implementing regulations, or these specifications, the Director shall proceed in accordance with 41 CFR 60-4.8.
- 14. The Contractor shall designate a responsible official to monitor all employment related activity to ensure that the company EEO policy is being carried out, to submit reports relating to the provisions hereof as may be required by the government and to keep records. Records shall at least include, for each employee, their name, address, telephone numbers, construction trade, union affiliation if any, employee identification number when assigned, social security number, race, sex, status (e.g., mechanic, apprentice, trainee, helper, or laborer), dates of changes in status, hours worked per week in the indicated trade, rate of pay, and locations at which the work was performed. Records shall be maintained in an easily understandable and retrievable form; however, to the degree that existing records satisfy this requirement, the Contractors will not be required to maintain separate records.
- 15. Nothing herein provided shall be construed as a limitation upon the application of other laws which establish different standards of compliance or upon the application of requirements for the hiring of local or other area residents (e.g., those under the Public Works Employment Act of 1977 and the Community Development Block Grant Program).
- 16. Additional assistance for Federal Construction Contractors on contracts administered by Washington State Department of Transportation or by Local Agencies may be found at:
- <sup>35</sup> Washington State Dept. of Transportation
  - Office of Equal Opportunity
  - PO Box 47314
  - 310 Maple Park Ave. SE
  - Olympia WA
  - 98504-7314 Db: 260 705
  - Ph: 360-705-7090
  - Fax: 360-705-6801 http://www.wsdot.wa.gov/equalopportunity/default.htm
- 43 <u>http://www.wsdot.wa.gov/equalopportur</u>

## 45 1-07.17 Utilities And Similar Facilities

- 46 (April 2, 2007)
- <sup>47</sup> Section 1-07.17 is supplemented with the following:
- Locations and dimensions shown in the Plan for existing facilities are in accordance with available information obtained without uncovering, measuring, or other verification.
  - The following addresses and telephone numbers of utility companies known or suspected of having facilities within the project limits are supplied for the Contractor's convenience:

1	Lewis County P.U.D. No. 1
2	321 NW Pacific
3	Chehalis, WA 98532
4	Telephone: (360) 748-9261
5	
6	TDS Telecom
7	Neil Schwartz
8	Network Specialist 1
9	Tel: 208-835-2222 / cell: 208-790-0189
10	Neil.schwartz@tdstelcom.com
11	
12	LUMEN
13	Dioni Cariaga
14	Network Implementation Engineer II
15	411 S Kaiser Rd, Olympia, WA 98502
16	tel: 206-733-5261 / cell: 360-250-2596
17	dioni.cariaga@lumen.com
18	-
19	The Contractor shall call the Underground locate
20	construction at each project site. The Contractor sh
21	within two feet of the planned construction. The abo
00	ner RCW 19 122 it shall be the Contractors respon

construction at each project site. The Contractor shall notify the Utility Owner of any utilities that are
 within two feet of the planned construction. The above list of Utility Owners may not be complete. As
 per RCW 19.122 it shall be the Contractors responsibility to contact the owners of utilities known or
 suspected of having services close to the project site.

service (800-424-5555) two to ten days prior to

#### 25 1-07.18 Public Liability and Property Damage Insurance

- <sup>27</sup> Delete this section in its entirety, and replace it with the following:
- <sup>29</sup> **1-07.18** Insurance
- <sup>30</sup> (January 4, 2016 APWA GSP)

#### <sup>32</sup> 1-07.18(1) General Requirements

- A. The Contractor shall procure and maintain the insurance described in all subsections of section 1 07.18 of these Special Provisions, from insurers with a current A. M. Best rating of not less than A-:
   VII and licensed to do business in the State of Washington. The Contracting Agency reserves the
   right to approve or reject the insurance provided, based on the insurer's financial condition.
- B. The Contractor shall keep this insurance in force without interruption from the commencement of
   the Contractor's Work through the term of the Contract and for thirty (30) days after the Physical
   Completion date, unless otherwise indicated below.
- 41

51

37

24

26

28

- C. If any insurance policy is written on a claims made form, its retroactive date, and that of all 42 subsequent renewals, shall be no later than the effective date of this Contract. The policy shall 43 state that coverage is claims made, and state the retroactive date. Claims-made form coverage 44 shall be maintained by the Contractor for a minimum of 36 months following the Completion Date or 45 earlier termination of this Contract, and the Contractor shall annually provide the Contracting 46 Agency with proof of renewal. If renewal of the claims made form of coverage becomes 47 unavailable, or economically prohibitive, the Contractor shall purchase an extended reporting period 48 ("tail") or execute another form of guarantee acceptable to the Contracting Agency to assure 49 financial responsibility for liability for services performed. 50
- D. The Contractor's Automobile Liability, Commercial General Liability and Excess or Umbrella Liability
   insurance policies shall be primary and non-contributory insurance as respects the Contracting
   Agency's insurance, self-insurance, or self-insured pool coverage. Any insurance, self-insurance, or

- self-insured pool coverage maintained by the Contracting Agency shall be excess of the Contractor's insurance and shall not contribute with it.
- E. The Contractor shall provide the Contracting Agency and all additional insureds with written notice of any policy cancellation, within two business days of their receipt of such notice.
- G. The Contractor shall not begin work under the Contract until the required insurance has been obtained and approved by the Contracting Agency

H. Failure on the part of the Contractor to maintain the insurance as required shall constitute a material
 breach of contract, upon which the Contracting Agency may, after giving five business days' notice
 to the Contractor to correct the breach, immediately terminate the Contract or, at its discretion,
 procure or renew such insurance and pay any and all premiums in connection therewith, with any
 sums so expended to be repaid to the Contracting Agency on demand, or at the sole discretion of
 the Contracting Agency, offset against funds due the Contractor from the Contracting Agency.

<sup>16</sup>
 <sup>17</sup> I. All costs for insurance shall be incidental to and included in the unit or lump sum prices of the
 <sup>18</sup> Contract and no additional payment will be made.

# <sup>19</sup> **1-07.18(2)** Additional Insured

All insurance policies, with the exception of Workers Compensation, and of Professional Liability and Builder's Risk (if required by this Contract) shall name the following listed entities as additional insured(s) using the forms or endorsements required herein:

24 25

1

2

4

5 6

7

8 9

- the Contracting Agency and its officers, elected officials, employees, agents, and volunteers
- The above-listed entities shall be additional insured(s) for the full available limits of liability maintained by the Contractor, irrespective of whether such limits maintained by the Contractor are greater than those required by this Contract, and irrespective of whether the Certificate of Insurance provided by the Contractor pursuant to 1-07.18(4) describes limits lower than those maintained by the Contractor.
- 30

For Commercial General Liability insurance coverage, the required additional insured endorsements shall be at least as broad as ISO forms CG 20 10 10 01 for ongoing operations and CG 20 37 10 01 for completed operations.

34 35

## 1-07.18(3) Subcontractors

The Contractor shall cause each Subcontractor of every tier to provide insurance coverage that complies with all applicable requirements of the Contractor-provided insurance as set forth herein, except the Contractor shall have sole responsibility for determining the limits of coverage required to be obtained by Subcontractors.

40

The Contractor shall ensure that all Subcontractors of every tier add all entities listed in 1-07.18(2) as additional insureds, and provide proof of such on the policies as required by that section as detailed in 1-07.18(2) using an endorsement as least as broad as ISO CG 20 10 10 01 for ongoing operations and CG 20 37 10 01 for completed operations.

45

<sup>46</sup> Upon request by the Contracting Agency, the Contractor shall forward to the Contracting Agency
 <sup>47</sup> evidence of insurance and copies of the additional insured endorsements of each Subcontractor of
 <sup>48</sup> every tier as required in 1-07.18(4) Verification of Coverage.

49

#### <sup>50</sup> 1-07.18(4) Verification of Coverage

<sup>51</sup> The Contractor shall deliver to the Contracting Agency a Certificate(s) of Insurance and endorsements

- <sup>52</sup> for each policy of insurance meeting the requirements set forth herein when the Contractor delivers the <sup>53</sup> signed Contract for the work. Failure of Contracting Agency to demand such verification of coverage
- signed Contract for the work. Failure of Contracting Agency to demand such verification of coverage
   with these insurance requirements or failure of Contracting Agency to identify a deficiency from the

- insurance documentation provided shall not be construed as a waiver of Contractor's obligation to
- <sup>2</sup> maintain such insurance.
- 3 4
- Verification of coverage shall include:
- 5 1. An ACORD certificate or a form determined by the Contracting Agency to be equivalent.
- Copies of all endorsements naming Contracting Agency and all other entities listed in 1-07.18(2) as
   additional insured(s), showing the policy number. The Contractor may submit a copy of any blanket
   additional insured clause from its policies instead of a separate endorsement.
- <sup>9</sup> 3. Any other amendatory endorsements to show the coverage required herein.
- 4. A notation of coverage enhancements on the Certificate of Insurance shall <u>not</u> satisfy these
   requirements actual endorsements must be submitted.
- <sup>13</sup> Upon request by the Contracting Agency, the Contractor shall forward to the Contracting Agency a full <sup>14</sup> and certified copy of the insurance policy(s). If Builders Risk insurance is required on this Project, a full <sup>15</sup> and certified copy of that policy is required when the Contractor delivers the signed Contract for the <sup>16</sup> work.
- 17

#### 18 1-07.18(5) Coverages and Limits

- <sup>19</sup> The insurance shall provide the minimum coverages and limits set forth below. Contractor's
- <sup>20</sup> maintenance of insurance, its scope of coverage, and limits as required herein shall not be construed to
- limit the liability of the Contractor to the coverage provided by such insurance, or otherwise limit the
- <sup>22</sup> Contracting Agency's recourse to any remedy available at law or in equity.
- 23
- All deductibles and self-insured retentions must be disclosed and are subject to approval by the
- <sup>25</sup> Contracting Agency. The cost of any claim payments falling within the deductible or self-insured
- retention shall be the responsibility of the Contractor. In the event an additional insured incurs a liability
- <sup>27</sup> subject to any policy's deductibles or self-insured retention, said deductibles or self-insured retention
- <sup>28</sup> shall be the responsibility of the Contractor.
- 29

## <sup>30</sup> 1-07.18(5)A Commercial General Liability

- Commercial General Liability insurance shall be written on coverage forms at least as broad as ISO
   occurrence form CG 00 01, including but not limited to liability arising from premises, operations, stop
   gap liability, independent contractors, products-completed operations, personal and advertising injury,
- and liability assumed under an insured contract. There shall be no exclusion for liability arising from
- explosion, collapse or underground property damage.
- 36
- The Commercial General Liability insurance shall be endorsed to provide a per project general aggregate limit, using ISO form CG 25 03 05 09 or an equivalent endorsement.
- 39
- Contractor shall maintain Commercial General Liability Insurance arising out of the Contractor's
   completed operations for at least three years following Substantial Completion of the Work.
- 42
- <sup>43</sup> Such policy must provide the following minimum limits:
- <sup>44</sup> \$1,000,000 Each Occurrence
- 45 \$2,000,000 General Aggregate
- <sup>46</sup> \$2,000,000 Products & Completed Operations Aggregate
- <sup>47</sup> \$1,000,000 Personal & Advertising Injury each offence
- 48 \$1,000,000 Stop Gap / Employers' Liability each accident
- 49
- 50 1-07.18(5)B Automobile Liability

1 2 3	Automobile Liability shall cover owned, non-owned, hired, and leased vehicles; and shall be written on a coverage form at least as broad as ISO form CA 00 01. If the work involves the transport of pollutants, the automobile liability policy shall include MCS 90 and CA 99 48 endorsements.
4 5 6	Such policy must provide the following minimum limit: \$1,000,000 Combined single limit each accident
7 8 9 10 11	<b>1-07.18(5)C Workers' Compensation</b> The Contractor shall comply with Workers' Compensation coverage as required by the Industrial Insurance laws of the State of Washington.
12	1-08, PROSECUTION AND PROGRESS
13 14 15	<b>1-08.0 Preliminary Matters</b> (May 25, 2006 APWA GSP)
16 17 18	Add the following new section:
19 20 21	<b>1-08.0(1) Preconstruction Conference</b> (October 10, 2008 APWA GSP)
22 23 24	Prior to the Contractor beginning the work, a preconstruction conference will be held between the Contractor, the Engineer and such other interested parties as may be invited. The purpose of the preconstruction conference will be:
25 26 27	<ol> <li>To review the initial progress schedule;</li> <li>To establish a working understanding among the various parties associated or affected by the work;</li> </ol>
28 29	<ol> <li>To establish and review procedures for progress payment, notifications, approvals, submittals, etc.;</li> </ol>
30	<ol><li>To establish normal working hours for the work;</li></ol>
31	5. To review safety standards and traffic control; and
32	6. To discuss such other related items as may be pertinent to the work.
33 34	The Contractor shall prepare and submit at the preconstruction conference the following:
35	1. A breakdown of all lump sum items;
36	2. A preliminary schedule of working drawing submittals; and
37	3. A list of material sources for approval if applicable.
38	
39 40	Add the following new section:
41 42	1-08.0(2) Hours of Work (December 8, 2014 APWA GSP)
43	
44 45	Except in the case of emergency or unless otherwise approved by the Engineer, the normal working
46	hours for the Contract shall be any consecutive 8-hour period between 7:00 a.m. and 6:00 p.m. Monday through Friday, exclusive of a lunch break. If the Contractor desires different than the
47	normal working hours stated above, the request must be submitted in writing prior to the
48	preconstruction conference, subject to the provisions below. The working hours for the Contract
49	shall be established at or prior to the preconstruction conference.
50	
51 52	All working hours and days are also subject to local permit and ordinance conditions (such as noise ordinances).

1 2	If the Contractor wishes to deviate from the established working hours, the Contractor shall submit a
2	written request to the Engineer for consideration. This request shall state what hours are being
4	requested, and why. Requests shall be submitted for review no later than 3 working days prior to the
5	day(s) the Contractor is requesting to change the hours.
6	
7	If the Contracting Agency approves such a deviation, such approval may be subject to certain other
8	conditions, which will be detailed in writing. For example:
9	1. On non-Federal aid projects, requiring the Contractor to reimburse the Contracting Agency
10	for the costs in excess of straight-time costs for Contracting Agency representatives who
11	worked during such times. (The Engineer may require designated representatives to be
12	present during the work. Representatives who may be deemed necessary by the Engineer include, but are not limited to: survey crews; personnel from the Contracting Agency's
13	material testing lab; inspectors; and other Contracting Agency employees or third party
14	consultants when, in the opinion of the Engineer, such work necessitates their presence.)
15	
16	2. Considering the work performed on Saturdays, Sundays, and holidays as working days with
17	regard to the contract time.
18	3. Considering multiple work shifts as multiple working days with respect to contract time even
19	though the multiple shifts occur in a single 24-hour period.
10	
20	4. If a 4-10 work schedule is requested and approved the non working day for the week will be
21	charged as a working day.
22	5. If Davis Bacon wage rates apply to this Contract, all requirements must be met and recorded
23	properly on certified payroll
24	
25	1-08.1 Subcontracting
26	(December 30, 2022 APWA GSP, Option A)
27	
28 29	Section 1-08.1 is supplemented with the following:
30	Prior to any subcontractor or lower tier subcontractor beginning work, the Contractor shall submit to
31	the Engineer a certification (WSDOT Form 420-004) that a written agreement between the
32 33	Contractor and the subcontractor or between the subcontractor and any lower tier subcontractor
34	has been executed. This certification shall also guarantee that these subcontract agreements
	include all the documents required by the Special Provision Federal Agency Inspection.
35	
36	A subcontractor or lower tier subcontractor will not be permitted to perform any work under the
37	contract until the following documents have been completed and submitted to the Engineer:
38	
39	1. Request to Sublet Work (WSDOT Form 421-012), and
40	
41	2. Contractor and Subcontractor or Lower Tier Subcontractor Certification for Federal-aid Projects
42	(WSDOT Form 420-004).
43	
44	The Contractor shall submit to the Engineer a completed Monthly Retainage Report (WSDOT Form
45	272-065) within 15 calendar days after receipt of every monthly progress payment until every
46	subcontractor and lower tier subcontractor's retainage has been released.
47	
48	The Contractor's records pertaining to the requirements of this Special Provision shall be open to
49	inspection or audit by representatives of the Contracting Agency during the life of the contract and
50	for a period of not less than three years after the date of acceptance of the contract. The Contractor
	Pigeon Springs Road HMA Project

shall retain these records for that period. The Contractor shall also guarantee that these records of all subcontractors and lower tier subcontractors shall be available and open to similar inspection or audit for the same time period.

1-08.3(2)A Type A Progress Schedule

(December 30, 2022 APWA GSP)

Revise this section to read:

The Contractor shall submit \$\$3\$\$ copies of a Type A Progress Schedule no later than at the
 preconstruction conference, or some other mutually agreed upon submittal time. The schedule may
 be a critical path method (CPM) schedule, bar chart, or other standard schedule format. Regardless
 of which format used, the schedule shall identify the critical path. The Engineer will evaluate the
 Type A Progress Schedule and approve or return the schedule for corrections within 15 calendar
 days of receiving the submittal.

- 1-08.3(2)D Weekly Look-Ahead Schedule
- 18 19 **(\*\*\*\*\*)**

Section 1-08.3(2)D is supplemented with the following:

#### 22 Contractor's Weekly Activities

The Contractor shall submit a weekly schedule to the Engineer (prior to the beginning of each work week). The schedule shall indicate the Contractor's proposed activities for the forthcoming week along with the hours of work. This will permit the Engineer to more effectively provide the contract engineering and inspection for the Contractor's operations.

27

38

45

47

48 49

55

1

2

3

4

5

6 7

8 9

16

17

20 21

The written weekly activity schedule shall be submitted to the Engineer or a designated assistant before the end of the last shift on the next to the last working day of the week preceding the indicated activities, or other mutually agreeable time. The written weekly look ahead shall be discussed at a weekly on-site meeting between the Contractor's representative (PM, Site Foreman, etc.) and the Contracting Agency's staff members (Asst. County Engineer, PM, inspector, Environmental depending on upcoming planned work) at a mutually agreed upon recurring day/time.

If the Contractor proceeds with work not indicated on the weekly activity schedule, or in a sequence
 differing from that which has been shown on the schedule, the Engineer may require the Contractor
 to delay unscheduled activities until they are included on a subsequent weekly activity schedule.

Separately, and in addition to the weekly schedule, the Contractor shall submit weekly a summary of project activities to the Engineer. The summary of activities shall include a report of the nature and progress of each of the major activities that were advanced on the project within the previous week. It shall be sufficiently detailed that a composite history of the project develops. The locations and approximate quantity guardrail and traffic control work shall be reported. Unusual activity, and conditions or events that may affect the course of the project shall also be reported.

<sup>46</sup> 1-08.4 Prosecution of Work

Delete this section and replace it with the following:

- <sup>50</sup> **1-08.4 Notice to Proceed and Prosecution of Work**
- <sup>51</sup> (July 23, 2015 APWA GSP)
- <sup>52</sup> <sup>53</sup> Notice to Proceed will be given after the contract has been executed and the contract bond and
- <sup>54</sup> evidence of insurance have been approved and filed by the Contracting Agency. The Contractor

shall not commence with the work until the Notice to Proceed has been given by the Engineer. The Pigeon Springs Road HMA Project

- Contractor shall commence construction activities on the project site within ten days of the Notice to
   Proceed Date, unless otherwise approved in writing. The Contractor shall diligently pursue the
   work to the physical completion date within the time specified in the contract. Voluntary shutdown
   or slowing of operations by the Contractor shall not relieve the Contractor of the responsibility to
   complete the work within the time(s) specified in the contract.
- 6

17

19

38

40

48

49

50

51

When shown in the Plans, the first order of work shall be the installation of high visibility fencing to delineate all areas for protection or restoration, as described in the Contract. Installation of high visibility fencing adjacent to the roadway shall occur after the placement of all necessary signs and traffic control devices in accordance with 1-10.1(2). Upon construction of the fencing, the Contractor shall request the Engineer to inspect the fence. No other work shall be performed on the site until the Contracting Agency has accepted the installation of high visibility fencing, as described in the Contract.

#### 15 **1-08.5 Time for Completion**

- <sup>16</sup> (December 30, 2022 APWA GSP, Option B)
- <sup>18</sup> Revise the third and fourth paragraphs to read:

Contract time shall begin on the first working day following the \$\$14<sup>th</sup> \$\$ calendar day after the
 Notice to Proceed date. If the Contractor starts work on the project at an earlier date, then contract
 time shall begin on the first working day when onsite work begins.

23 Each working day shall be charged to the contract as it occurs, until the contract work is physically 24 complete. If substantial completion has been granted and all the authorized working days have 25 been used, charging of working days will cease. Each week the Engineer will provide the Contractor 26 a statement that shows the number of working days: (1) charged to the contract the week before; 27 (2) specified for the physical completion of the contract; and (3) remaining for the physical 28 completion of the contract. The statement will also show the nonworking days and all partial or 29 whole days the Engineer declares as unworkable. The statement will be identified as a Written 30 Determination by the Engineer. If the Contractor does not agree with the Written Determination of 31 working days, the Contractor shall pursue the protest procedures in accordance with Section 1-32 04.5. By failing to follow the procedures of Section 1-04.5, the Contractor shall be deemed as 33 having accepted the statement as correct. If the Contractor is approved to work 10 hours a day and 34 4 days a week (a 4-10 schedule) and the fifth day of the week in which a 4-10 shift is worked would 35 ordinarily be charged as a working day, then the fifth day of that week will be charged as a working 36 day whether or not the Contractor works on that day. 37

<sup>39</sup> Revise the sixth paragraph to read:

The Engineer will give the Contractor written notice of the completion date of the contract after all the Contractor's obligations under the contract have been performed by the Contractor. The following events must occur before the Completion Date can be established:

- 1. The physical work on the project must be complete; and
- 45
   A5
   A6
   A6
   A7
   A6
   A7
   A6
   A7
   A6
   A7
   A6
   A7
   A6
   A7
   A
  - a. Certified Payrolls (per Section 1-07.9(5)).
    - b. Material Acceptance Certification Documents
  - Monthly Reports of Amounts Credited as DBE Participation, as required by the Contract Provisions.
- d. Final Contract Voucher Certification

1 2		Copies of the approved "Affidavit of Prevailing Wages Paid" for the Contractor and all subcontractors
3 4 5 6	f.	A copy of the Notice of Termination sent to the Washington State Department of Ecology (Ecology); the elapse of 30 calendar days from the date of receipt of the Notice of Termination by Ecology; and no rejection of the Notice of Termination by Ecology. This requirement will not apply if the Construction Stormwater General Permit is transferred back to the Contracting Agency in accordance with Section 8-01.3(16).
7 8		Property owner releases per Section 1-07.24
9	9.	
10	(*****) 	
11 12	i nis projec	t shall be physically completed within *** <b>6</b> *** working days.
13 14		uidated Damages 2021 APWA GSP, Option B)
15 16	Revise the	second and third paragraphs to read:
17 18	Accordi	ingly, the Contractor agrees:
19 20 21	1.	To pay (according to the following formula) liquidated damages for each working day beyond the number of working days established for Physical Completion, and
22 23 24	2.	To authorize the Engineer to deduct these liquidated damages from any money due or coming due to the Contractor.
25 26	Liq	uidated Damages Formula
27 28	LD=	=0.15C/T
29 30	Whe	ere:
31		
32		LD = liquidated damages per working day (rounded to the nearest dollar)
33 34		C = original Contract amount T = original time for Physical Completion
35 36		he Contract Work has progressed to Substantial Completion as defined in the Contract, the er may determine the Contract Work is Substantially Complete. The Engineer will notify the
37 38	•	ctor in writing of the Substantial Completion Date. For overruns in Contract time occurring
39	after the	e date so established, the formula for liquidated damages shown above will not apply. For
40		is in Contract time occurring after the Substantial Completion Date, liquidated damages shall
41 42		essed on the basis of direct engineering and related costs assignable to the project until the Physical Completion Date of all the Contract Work. The Contractor shall complete the
43		ng Work as promptly as possible. Upon request by the Project Engineer, the Contractor
44	shall fu	rnish a written schedule for completing the physical Work on the Contract.
45		
46 47	1-09. MEA	ASUREMENT AND PAYMENT
48	· •••,/	
49	1-09.9 Pay	rments
50		- 30, 2022 APWA GSP)
51 52	Section 1-0	9.9 is revised to read:
	Pigeon Springs	Road HMA Project
	CRP 2200C	28

The basis of payment will be the actual quantities of Work performed according to the Contract and
 as specified for payment.

The Contractor shall submit a breakdown of the cost of lump sum bid items at the Preconstruction
 Conference, to enable the Project Engineer to determine the Work performed on a monthly basis. A
 breakdown is not required for lump sum items that include a basis for incremental payments as part
 of the respective Specification. Absent a lump sum breakdown, the Project Engineer will make a
 determination based on information available. The Project Engineer's determination of the cost of
 work shall be final.

Progress payments for completed work and material on hand will be based upon progress
 estimates prepared by the Engineer. A progress estimate cutoff date will be established at the
 preconstruction conference.

The initial progress estimate will be made not later than 30 days after the Contractor commences
 the work, and successive progress estimates will be made every month thereafter until the
 Completion Date. Progress estimates made during progress of the work are tentative, and made
 only for the purpose of determining progress payments. The progress estimates are subject to
 change at any time prior to the calculation of the final payment.

- <sup>22</sup> The value of the progress estimate will be the sum of the following:
  - 1. Unit Price Items in the Bid Form the approximate quantity of acceptable units of work completed multiplied by the unit price.
    - Lump Sum Items in the Bid Form based on the approved Contractor's lump sum breakdown for that item, or absent such a breakdown, based on the Engineer's determination.
    - 3. Materials on Hand 100 percent of invoiced cost of material delivered to Job site or other storage area approved by the Engineer.
    - 4. Change Orders entitlement for approved extra cost or completed extra work as determined by the Engineer.

<sup>32</sup> Progress payments will be made in accordance with the progress estimate less:

- 1. Retainage per Section 1-09.9(1), on non FHWA-funded projects;
- 2. The amount of progress payments previously made; and
- 3. Funds withheld by the Contracting Agency for disbursement in accordance with the Contract Documents.
- 36 37 38

39

40

41

1

4

11

23

24

25

26

27

28

29

30 31

33

34

35

Progress payments for work performed shall not be evidence of acceptable performance or an admission by the Contracting Agency that any work has been satisfactorily completed. The determination of payments under the contract will be final in accordance with Section 1-05.1.

Failure to perform obligations under the Contract by the Contractor may be decreed by the
 Contracting Agency to be adequate reason for withholding any payments until compliance is
 achieved.

<sup>45</sup>
 <sup>46</sup> Upon completion of all Work and after final inspection (Section 1-05.11), the amount due the
 <sup>47</sup> Contractor under the Contract will be paid based upon the final estimate made by the Engineer and
 <sup>48</sup> presentation of a Final Contract Voucher Certification to be signed by the Contractor. The
 <sup>49</sup> Contractor's signature on such voucher shall be deemed a release of all claims of the Contractor
 <sup>50</sup> unless a Certified Claim is filed in accordance with the requirements of Section 1-09.11 and is
 <sup>51</sup> expressly excepted from the Contractor's certification on the Final Contract Voucher Certification.

CRP 2200C

The date the Contracting Agency signs the Final Contract Voucher Certification constitutes the final 1 acceptance date (Section 1-05.12). 2

3 If the Contractor fails, refuses, or is unable to sign and return the Final Contract Voucher 4 Certification or any other documentation required for completion and final acceptance of the 5 Contract, the Contracting Agency reserves the right to establish a Completion Date (for the purpose 6 of meeting the requirements of RCW 60.28) and unilaterally accept the Contract. Unilateral final 7 acceptance will occur only after the Contractor has been provided the opportunity, by written 8 request from the Engineer, to voluntarily submit such documents. If voluntary compliance is not 9 achieved, formal notification of the impending establishment of a Completion Date and unilateral 10 final acceptance will be provided by email with delivery confirmation from the Contracting Agency to 11 the Contractor, which will provide 30 calendar days for the Contractor to submit the necessary 12 documents. The 30 calendar day period will begin on the date the email with delivery confirmation is 13 received by the Contractor. The date the Contracting Agency unilaterally signs the Final Contract 14 Voucher Certification shall constitute the Completion Date and the final acceptance date (Section 1-15 05.12). The reservation by the Contracting Agency to unilaterally accept the Contract will apply to 16 Contracts that are Physically Completed in accordance with Section 1-08.5, or for Contracts that 17 are terminated in accordance with Section 1-08.10. Unilateral final acceptance of the Contract by 18 the Contracting Agency does not in any way relieve the Contractor of their responsibility to comply 19 with all Federal, State, tribal, or local laws, ordinances, and regulations that affect the Work under 20 the Contract. 21

Payment to the Contractor of partial estimates, final estimates, and retained percentages shall be subject to controlling laws.

24 25 26

27

22

23

#### 1-09.11 Disputes and Claims

28 29 30

31 32

33

47

48

1-09.11(3) Time Limitation and Jurisdiction

(December 30, 2022 APWA GSP)

Revise this section to read:

For the convenience of the parties to the Contract it is mutually agreed by the parties that all claims 34 or causes of action which the Contractor has against the Contracting Agency arising from the 35 Contract shall be brought within 180 calendar days from the date of final acceptance (Section 1-36 05.12) of the Contract by the Contracting Agency; and it is further agreed that all such claims or 37 causes of action shall be brought only in the Superior Court of the county where the Contracting 38 Agency headquarters is located, provided that where an action is asserted against a county, RCW 39 36.01.050 shall control venue and jurisdiction. The parties understand and agree that the 40 Contractor's failure to bring suit within the time period provided, shall be a complete bar to all such 41 claims or causes of action. It is further mutually agreed by the parties that when claims or causes of 42 action which the Contractor asserts against the Contracting Agency arising from the Contract are 43 filed with the Contracting Agency or initiated in court, the Contractor shall permit the Contracting 44 Agency to have timely access to all records deemed necessary by the Contracting Agency to assist 45 in evaluating the claims or action. 46

1-09.13 Claims Resolution

49	
50	1-09.13(3)A Arbitration General
51	(January 19, 2022 APWA GSP)
52	
53	Revise the third paragraph to read:
54	

The Contracting Agency and the Contractor mutually agree to be bound by the decision of the 1 arbitrator, and judgment upon the award rendered by the arbitrator may be entered in the Superior 2 Court of the county in which the Contracting Agency's headquarters is located, provided that where 3 claims subject to arbitration are asserted against a county, RCW 36.01.050 shall control venue and 4 jurisdiction of the Superior Court. The decision of the arbitrator and the specific basis for the 5 decision shall be in writing. The arbitrator shall use the Contract as a basis for decisions. 6 7 1-09.13(4) Venue for Litigation 8 (December 30, 2022 APWA GSP) 9 10 Revise this section to read: 11 12 Litigation shall be brought in the Superior Court of the county in which the Contracting Agency's 13 headquarters is located, provided that where claims are asserted against a county, RCW 36.01.050 14 shall control venue and jurisdiction of the Superior Court. It is mutually agreed by the parties that 15 when litigation occurs, the Contractor shall permit the Contracting Agency to have timely access to 16 all records deemed necessary by the Contracting Agency to assist in evaluating the claims or 17 action. 18 19 1-10, TEMPORARY TRAFFIC CONTROL 20 21 1-10.2 Traffic Control Management 22 23 1-10.2(1) General 24 Section 1-10.2(1) is supplemented with the following: 25 26 (October 3, 2022) 27 The Traffic Control Supervisor shall be certified by one of the following: 28 29 The Northwest Laborers-Employers Training Trust 30 27055 Ohio Ave. 31 Kingston, WA 98346 32 (360) 297-3035 33 https://www.nwlett.edu 34 35 **Evergreen Safety Council** 36 12545 135<sup>th</sup> Ave. NE 37 Kirkland, WA 98034-8709 38 1-800-521-0778 39 https://www.esc.org 40 41 The American Traffic Safety Services Association 42 15 Riverside Parkway, Suite 100 43 Fredericksburg, Virginia 22406-1022 44 Training Dept. Toll Free (877) 642-4637 45 Phone: (540) 368-1701 46 https://atssa.com/training 47 48 Integrity Safety 49 13912 NE 20th Ave. 50 Vancouver, WA 98686 51 (360) 574-6071 52 https://www.integritysafety.com 53 54

1	US Safety Alliance
2	(904) 705-5660
3	https://www.ussafetyalliance.com
4	
5	K&D Services Inc.
6	2719 Rockefeller Ave.
7	Everett, WA 98201
8	(800) 343-4049
	https://www.kndservices.net
9	https://www.thtdscr/rocs.net
10	1-10.2(2) Traffic Control Plans
11	(*****)
12	
13	Section 1-10.2(2) is supplemented with the following:
14	The Contractor shall submit a traffic control plan for a single lang two way traffic data we discout to
15	The Contractor shall submit a traffic control plan for a single lane two-way traffic detour adjacent to
16	the construction area prior to construction as a Type 2 working drawing. Two-way traffic shall be
17	restored during non-working hours. All signs and traffic control devices required for this project shall
18	be the Contractor's responsibility to furnish, erect, maintain, and remove immediately after
19	construction.
20	
21	If determined by the Engineer that additional signing (not shown on the Traffic Control Plan) is
22	needed, it shall be the Contractor's responsibility to furnish, erect, and maintain these additional
23	signs at no cost to the Contracting Agency.
24	
25	1-10.2(3) Conformance to Established Standards
26	(*****)
27	Section 1-10.2(3) is supplemented with the following:
28	
29	The latest revision of the WSDOT Manual M54-44 "Work Zone Traffic Control Guidelines"
20	
30	(WZTCG) is hereby made a part of this contract by reference as if contained fully herein.
30	
30 31	
30 31 32	(WZTCG) is hereby made a part of this contract by reference as if contained fully herein.
30 31 32 33	(WZTCG) is hereby made a part of this contract by reference as if contained fully herein. DIVISION 4
30 31 32 33 34	(WZTCG) is hereby made a part of this contract by reference as if contained fully herein. DIVISION 4 BASES
30 31 32 33 34	(WZTCG) is hereby made a part of this contract by reference as if contained fully herein. DIVISION 4
30 31 32 33 34 35	(WZTCG) is hereby made a part of this contract by reference as if contained fully herein. DIVISION 4 BASES
30 31 32 33 34 35 36	(WZTCG) is hereby made a part of this contract by reference as if contained fully herein. DIVISION 4 BASES
30 31 32 33 34 35 36 37	(WZTCG) is hereby made a part of this contract by reference as if contained fully herein. DIVISION 4 BASES 4-04, BALLAST AND CRUSHED SURFACING
30 31 32 33 34 35 36 37 38	(WZTCG) is hereby made a part of this contract by reference as if contained fully herein. DIVISION 4 BASES 4-04, BALLAST AND CRUSHED SURFACING 4-04.3 Construction Requirements 4-04.3(5) Shaping and Compacting
30 31 32 33 34 35 36 37 38 39	(WZTCG) is hereby made a part of this contract by reference as if contained fully herein. DIVISION 4 BASES 4-04, BALLAST AND CRUSHED SURFACING 4-04.3 Construction Requirements
30 31 32 33 34 35 36 37 38 39 40 41	(WZTCG) is hereby made a part of this contract by reference as if contained fully herein. DIVISION 4 BASES 4-04, BALLAST AND CRUSHED SURFACING 4-04.3 Construction Requirements 4-04.3(5) Shaping and Compacting (******)
30 31 32 33 34 35 36 37 38 39 40 41 42	(WZTCG) is hereby made a part of this contract by reference as if contained fully herein. DIVISION 4 BASES 4-04, BALLAST AND CRUSHED SURFACING 4-04.3 Construction Requirements 4-04.3(5) Shaping and Compacting
<ol> <li>30</li> <li>31</li> <li>32</li> <li>33</li> <li>34</li> <li>35</li> <li>36</li> <li>37</li> <li>38</li> <li>39</li> <li>40</li> <li>41</li> <li>42</li> <li>43</li> </ol>	(WZTCG) is hereby made a part of this contract by reference as if contained fully herein. DIVISION 4 BASES 4-04, BALLAST AND CRUSHED SURFACING 4-04.3 Construction Requirements 4-04.3(5) Shaping and Compacting (******) Section 4-04.3(5) is supplemented with the following:
<ol> <li>30</li> <li>31</li> <li>32</li> <li>33</li> <li>34</li> <li>35</li> <li>36</li> <li>37</li> <li>38</li> <li>39</li> <li>40</li> <li>41</li> <li>42</li> <li>43</li> <li>44</li> </ol>	(WZTCG) is hereby made a part of this contract by reference as if contained fully herein. DIVISION 4 BASES 4-04, BALLAST AND CRUSHED SURFACING 4-04.3 Construction Requirements 4-04.3(5) Shaping and Compacting (******) Section 4-04.3(5) is supplemented with the following: Shoulder Finishing
<ol> <li>30</li> <li>31</li> <li>32</li> <li>33</li> <li>34</li> <li>35</li> <li>36</li> <li>37</li> <li>38</li> <li>39</li> <li>40</li> <li>41</li> <li>42</li> <li>43</li> <li>44</li> <li>45</li> </ol>	(WZTCG) is hereby made a part of this contract by reference as if contained fully herein. DIVISION 4 BASES 4-04, BALLAST AND CRUSHED SURFACING 4-04.3 (5) Shaping and Compacting (******) Section 4-04.3(5) is supplemented with the following: Shoulder Finishing Shoulder Finishing Shoulder finishing material shall not be placed until the abutting pavement has been completed,
30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46	(WZTCG) is hereby made a part of this contract by reference as if contained fully herein. DIVISION 4 BASES 4-04, BALLAST AND CRUSHED SURFACING 4-04.3 Construction Requirements 4-04.3(5) Shaping and Compacting (******) Section 4-04.3(5) is supplemented with the following: Shoulder Finishing Shoulder Finishing material shall not be placed until the abutting pavement has been completed, unless designated by the Engineer. Shoulder finishing material (Crushed Surfacing Base Course)
30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47	(WZTCG) is hereby made a part of this contract by reference as if contained fully herein. DIVISION 4 BASES 4-04, BALLAST AND CRUSHED SURFACING 4-04.3 Construction Requirements 4-04.3 (5) Shaping and Compacting (******) Section 4-04.3 (5) is supplemented with the following: Shoulder Finishing Shoulder Finishing material shall not be placed until the abutting pavement has been completed, unless designated by the Engineer. Shoulder finishing material (Crushed Surfacing Base Course) shall be placed by a spreader box in one lift. Processing of the shoulder finishing material on the
<ol> <li>30</li> <li>31</li> <li>32</li> <li>33</li> <li>34</li> <li>35</li> <li>36</li> <li>37</li> <li>38</li> <li>39</li> <li>40</li> <li>41</li> <li>42</li> <li>43</li> <li>44</li> <li>45</li> <li>46</li> <li>47</li> <li>48</li> </ol>	(WZTCG) is hereby made a part of this contract by reference as if contained fully herein. DIVISION 4 BASES 4-04, BALLAST AND CRUSHED SURFACING 4-04.3 Construction Requirements 4-04.3(5) Shaping and Compacting (******) Section 4-04.3(5) is supplemented with the following: Shoulder Finishing Shoulder Finishing material shall not be placed until the abutting pavement has been completed, unless designated by the Engineer. Shoulder finishing material (Crushed Surfacing Base Course)
<ul> <li>30</li> <li>31</li> <li>32</li> <li>33</li> <li>34</li> <li>35</li> <li>36</li> <li>37</li> <li>38</li> <li>39</li> <li>40</li> <li>41</li> <li>42</li> <li>43</li> <li>44</li> <li>45</li> <li>46</li> <li>47</li> <li>48</li> <li>49</li> </ul>	(WZTCG) is hereby made a part of this contract by reference as if contained fully herein. DIVISION 4 BASES 4-04, BALLAST AND CRUSHED SURFACING 4-04.3(5) Shaping and Compacting (******) Section 4-04.3(5) is supplemented with the following: Shoulder Finishing Shoulder finishing material shall not be placed until the abutting pavement has been completed, unless designated by the Engineer. Shoulder finishing material (Crushed Surfacing Base Course) shall be placed by a spreader box in one lift. Processing of the shoulder finishing material on the roadway shall not be permitted.
<ol> <li>30</li> <li>31</li> <li>32</li> <li>33</li> <li>34</li> <li>35</li> <li>36</li> <li>37</li> <li>38</li> <li>39</li> <li>40</li> <li>41</li> <li>42</li> <li>43</li> <li>44</li> <li>45</li> <li>46</li> <li>47</li> <li>48</li> <li>49</li> <li>50</li> </ol>	(WZTCG) is hereby made a part of this contract by reference as if contained fully herein. DIVISION 4 BASES 4-04, BALLAST AND CRUSHED SURFACING 4-04.3 Construction Requirements 4-04.3(5) Shaping and Compacting (******) Section 4-04.3(5) is supplemented with the following: Shoulder Finishing Shoulder finishing material shall not be placed until the abutting pavement has been completed, unless designated by the Engineer. Shoulder finishing material (Crushed Surfacing Base Course) shall be placed by a spreader box in one lift. Processing of the shoulder finishing material on the roadway shall not be permitted. The existing shoulder material, as well as any additional crushed surfacing material required shall
<ul> <li>30</li> <li>31</li> <li>32</li> <li>33</li> <li>34</li> <li>35</li> <li>36</li> <li>37</li> <li>38</li> <li>39</li> <li>40</li> <li>41</li> <li>42</li> <li>43</li> <li>44</li> <li>45</li> <li>46</li> <li>47</li> <li>48</li> <li>49</li> <li>50</li> <li>51</li> </ul>	(WZTCG) is hereby made a part of this contract by reference as if contained fully herein. DIVISION 4 BASES 4-04, BALLAST AND CRUSHED SURFACING 4-04.3 Construction Requirements 4-04.3(5) Shaping and Compacting (******) Section 4-04.3(5) is supplemented with the following: Shoulder Finishing Shoulder finishing material shall not be placed until the abutting pavement has been completed, unless designated by the Engineer. Shoulder finishing material (Crushed Surfacing Base Course) shall be placed by a spreader box in one lift. Processing of the shoulder finishing material on the roadway shall not be permitted. The existing shoulder material, as well as any additional crushed surfacing material required shall be placed, watered, and compacted against the vertical edge of the pavement, including road
<ul> <li>30</li> <li>31</li> <li>32</li> <li>33</li> <li>34</li> <li>35</li> <li>36</li> <li>37</li> <li>38</li> <li>39</li> <li>40</li> <li>41</li> <li>42</li> <li>43</li> <li>44</li> <li>45</li> <li>46</li> <li>47</li> <li>48</li> <li>49</li> <li>50</li> <li>51</li> <li>52</li> </ul>	(WZTCG) is hereby made a part of this contract by reference as if contained fully herein. DIVISION 4 BASES 4-04, BALLAST AND CRUSHED SURFACING 4-04.3 Construction Requirements 4-04.3(5) Shaping and Compacting (******) Section 4-04.3(5) is supplemented with the following: Shoulder Finishing Shoulder finishing material shall not be placed until the abutting pavement has been completed, unless designated by the Engineer. Shoulder finishing material (Crushed Surfacing Base Course) shall be placed by a spreader box in one lift. Processing of the shoulder finishing material on the roadway shall not be permitted. The existing shoulder material, as well as any additional crushed surfacing material required shall be placed, watered, and compacted against the vertical edge of the pavement, including road approaches. Hand work may be required in areas of road approaches and guardrail. The Contractor
<ul> <li>30</li> <li>31</li> <li>32</li> <li>33</li> <li>34</li> <li>35</li> <li>36</li> <li>37</li> <li>38</li> <li>39</li> <li>40</li> <li>41</li> <li>42</li> <li>43</li> <li>44</li> <li>45</li> <li>46</li> <li>47</li> <li>48</li> <li>49</li> <li>50</li> <li>51</li> <li>52</li> <li>53</li> </ul>	(WZTCG) is hereby made a part of this contract by reference as if contained fully herein. DIVISION 4 BASES 4-04, BALLAST AND CRUSHED SURFACING 4-04.3 Construction Requirements 4-04.3(5) Shaping and Compacting (*****) Section 4-04.3(5) is supplemented with the following: Shoulder Finishing Shoulder Finishing material shall not be placed until the abutting pavement has been completed, unless designated by the Engineer. Shoulder finishing material (Crushed Surfacing Base Course) shall be placed by a spreader box in one lift. Processing of the shoulder finishing material on the roadway shall not be permitted. The existing shoulder material, as well as any additional crushed surfacing material required shall be placed, watered, and compacted against the vertical edge of the pavement, including road approaches. Hand work may be required in areas of road approaches and guardrail. The Contractor shall grade the shoulder material to a uniform slope, remove all debris (sod, large rocks, etc.) and
30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52	(WZTCG) is hereby made a part of this contract by reference as if contained fully herein. DIVISION 4 BASES 4-04, BALLAST AND CRUSHED SURFACING 4-04.3(5) Shaping and Compacting (******) Section 4-04.3(5) is supplemented with the following: Shoulder Finishing Shoulder Finishing material shall not be placed until the abutting pavement has been completed, unless designated by the Engineer. Shoulder finishing material (Crushed Surfacing Base Course) shall be placed by a spreader box in one lift. Processing of the shoulder finishing material on the roadway shall not be permitted. The existing shoulder material, as well as any additional crushed surfacing material required shall be placed, watered, and compacted against the vertical edge of the pavement, including road approaches. Hand work may be required in areas of road approaches and guardrail. The Contractor shall grade the shoulder material to a uniform slope, remove all debris (sod, large rocks, etc.) and dress all berms resulting from this operation to the satisfaction of the Engineer. The material shall
<ul> <li>30</li> <li>31</li> <li>32</li> <li>33</li> <li>34</li> <li>35</li> <li>36</li> <li>37</li> <li>38</li> <li>39</li> <li>40</li> <li>41</li> <li>42</li> <li>43</li> <li>44</li> <li>45</li> <li>46</li> <li>47</li> <li>48</li> <li>49</li> <li>50</li> <li>51</li> <li>52</li> <li>53</li> </ul>	(WZTCG) is hereby made a part of this contract by reference as if contained fully herein. DIVISION 4 BASES 4-04, BALLAST AND CRUSHED SURFACING 4-04.3 Construction Requirements 4-04.3(5) Shaping and Compacting (*****) Section 4-04.3(5) is supplemented with the following: Shoulder Finishing Shoulder Finishing material shall not be placed until the abutting pavement has been completed, unless designated by the Engineer. Shoulder finishing material (Crushed Surfacing Base Course) shall be placed by a spreader box in one lift. Processing of the shoulder finishing material on the roadway shall not be permitted. The existing shoulder material, as well as any additional crushed surfacing material required shall be placed, watered, and compacted against the vertical edge of the pavement, including road approaches. Hand work may be required in areas of road approaches and guardrail. The Contractor shall grade the shoulder material to a uniform slope, remove all debris (sod, large rocks, etc.) and

1 2 3 4 5 6	be graded into place and compacted by wheel rolling a minimum of two passes with a motor grader or comparable piece of equipment in areas where the shoulder is narrow. All other areas shall be compacted to the satisfaction of the Engineer. In all areas where the shoulder is wide enough, as determined by the Engineer, a steel drum vibratory compactor shall be used. For compaction, water shall be applied as determined by the Engineer. Damage to the HMA mat due to the Contractor's operation shall be repaired at no cost to the Contracting Agency.
7 8 9 10 11	Following the placement of crushed surfacing material each day, the new mainline and shoulder pavement shall be cleaned of all dirt and debris to the satisfaction of the Engineer. Prior to commencing work on the Shoulder Finishing operation the Contractor shall submit the selected method of compaction and equipment to be used to the Engineer for approval.
12 13	4-04.4 Measurement
14 15	(******) Section 4-04.4 is supplemented with the following:
16 17	"Shoulder Finishing" shall be measured per mile.
18 19 20 21	<b>4-04.5 Payment</b> (*****) Section 4-04.5 is supplemented with the following:
22 23 24 25	The unit contract price per mile for "Shoulder Finishing" shall be full pay for furnishing crushed surfacing, hauling, grading existing material, placing additional material, compacting and all other work as specified along both shoulders and driveway approaches as staked in the field
26 27 28	DIVISION 5 SURACE TREATMENTS AND PAVEMENTS
29 30	(LCPW GSP)
31	5-04, HOT MIX ASPHALT
32	Delete Section 5-04 and amendments, Hot Mix Asphalt and replace it with the following:
33 34	5-04.1 Description
35 36 37	This Work shall consist of providing and placing one or more layers of plant-mixed hot mix asphalt (HMA) on a prepared foundation or base in accordance with these Specifications and the lines, grades, thicknesses, and typical cross-sections shown in the Plans.
38 39 40 41	HMA shall be composed of asphalt binder and mineral materials as may be required, mixed in the proportions specified to provide a homogeneous, stable, and workable mixture.
42	The term "Approach" shall include Road approaches, driveways, and extensions.
43 44 45 46	Superintendents, Labor, and Equipment of Contractor The Contractor shall have a sufficient number of qualified personnel on the project to insure the following minimum crew size:
47 48 49 50 51 52	One paving superintendent One paver operator Two screed operators Three roller operators Two rakers

- 1 These workers shall be present and not assigned to dual activities that would stop them from fulfilling
- their assigned task while the paver is in operation. There will be one assigned supervisor who will be in
- <sup>3</sup> charge of paving operations and who will be responsible for work performed.

## Fiber Reinforced HMA:

This work shall consist of providing and placing Fiber Reinforced HMA in accordance with these Specifications and the lines, grades, thicknesses and typical cross-sections shown in the plans.

#### 10 Definitions:

4

5 6

7

8 9

11

12

13

14

15

16

17

18 19

- Reinforcing Fibers: High tensile strength synthetic aramid fiber blend specially formulated to reinforce hot mix asphalt.
- Fiber Reinforced Asphalt Concrete (FRAC): A mixture of hot mix asphalt and reinforcing fibers that has greater resistance to rutting, thermal cracking, fatigue cracking, and reflective cracking as compared to conventional non-fiber asphalt mixes.
- Aramid Dispersion State Ratio (ADSR): A measure of the dispersion efficiency of the Reinforcing Fibers within asphalt mixes. ADSR is calculated by comparing the mass of aramid in the individual state to the total mass of extracted aramid fibers, expressed as a percentage.

#### 20 5-04.2 Materials

<sup>21</sup> Materials shall meet the requirements of the following sections:

23	Asphalt Binder	9-02.1(4)
24	Cationic Emulsified Asphalt	9-02.1(6)
25	Anti-Stripping Additive	9-02.4
26	HMA Additive	9-02.5
27	Aggregates	9-03.8
28	Recycled Asphalt Pavement	9-03.8(3)B
29	Mineral Filler	9-03.8(5)
30	Recycled Material	9-03.21
31	Portland Cement	9-01
32	Sand	9-03.1(2)
33	(As noted in 5-04.3(5)C for crack se	aling)
34	Joint Sealant	9-04.2
35	Foam Backer Rod	9-04.2(3)A

36

The Contract documents may establish that the various mineral materials required for the manufacture of HMA will be furnished in whole or in part by the Contracting Agency. If thE documents do not establish the furnishing of any of these mineral materials by the Contracting Agency, the Contractor shall be required to furnish such materials in the amounts required for the designated mix. Mineral materials include coarse and fine aggregates, and mineral filler.

- 42
- <sup>43</sup> No recycled asphalt pavement (RAP) may be used in the production of HMA for wearing course.

44

The grade of asphalt binder shall be as required by the Contract. Blending of asphalt binder from different
 sources is not permitted.

47

<sup>1</sup> Production of aggregates shall comply with the requirements of Section 3-01. Preparation of stockpile

site, the stockpiling of aggregates, and the removal of aggregates from stockpiles shall comply with the requirements of Section 3-02

requirements of Section 3-02.

## **Reinforcing Fibers:**

1. Provide a reinforcing fiber blend of virgin polyolefins and virgin aramids that meets the requirements in Table 1 and Table 2 below:

Reinfor	cing Fiber Mater	ial Properties	
Property	Standard	Polyolefin	Aramid
Form	Manufacturer Certification	Serrated	Monofilament
Nominal Specific Gravity	ASTM D276	0.91	1.44
Tensile Strength (psi)	ASTM D7269	NA <sup>1</sup>	400,000
Length (in)	Manufacturer Certification	0.75	0.75

<u>Table 1</u>

1. Polyolefin fibers will melt or become plastically deformed during production

## Table 2

Reinforcing Fiber Performance Properties			
Performance Measure	Test Method	Standard	Requirement
Dispersion Efficiency	Aramid Dispersion State Ratio (ADSR)	Modified ASTM D2172	≥ 85%
Field Performance Cracking Resistance	Pavement Condition Index	ASTM D6433	≥ 10 PCI Points increase, Minimum 4 years
Resistance to Permanent Deformation (Rutting)	Flow Number (FN)	AASTHO TP79	≥ 75% increase

2. If an aramid-based fiber blend is proposed that does not meet all of the material properties in Table 1 above, performance test results meeting Table 2 above and complying with Part 2 of Section 5-04.2(2) below a substitute fiber blend shall be submitted at least one week prior to bid date for approval by engineer.

3. Non-aramid fiber blends will not be considered as acceptable alternatives to this specification

# 5-04.2(1) How to Get a HMA Mix Design on the QPL

If the contractor wishes to submit a mix design for inclusion in the Qualified Products List (QPL), please follow the WSDOT process outlined in Standard Specification 5-04.2(1).

## 5-04.2(2) Mix Design – Obtaining Project Approval

No paving shall begin prior to the approval of the mix design by the Engineer.

## ESAL's

 The number of ESAL's for the design and acceptance of the HMA shall be \*\*\* 1.0 \*\*\* million.

**Nonstatistical** evaluation will be used for all HMA not designated as Commercial HMA in the contract documents.

**Commercial** evaluation will be used for Commercial HMA and for other classes of HMA if approved by the Engineer, in the following applications: sidewalks, road approaches, ditches, slopes, paths, trails, gores, prelevel, and pavement repair. Other nonstructural applications of HMA accepted by commercial evaluation shall be as approved by the Project Engineer. Sampling and testing of HMA accepted by commercial evaluation will be at the option of the Project Engineer. The Proposal quantity of HMA that is accepted by commercial evaluation will be excluded from the quantities used in the determination of nonstatistical evaluation.

- **Nonstatistical Mix Design**. Fifteen days prior to the first day of paving the contractor shall provide one of the following mix design verification certifications for Contracting Agency review;
  - The WSDOT Mix Design Evaluation Report from the current WSDOT QPL, or one of the mix design verification certifications listed below.
  - The proposed HMA mix design on WSDOT Form 350-042 with the seal and certification (stamp & sig-nature) of a valid licensed Washington State Professional Engineer.
  - The Mix Design Report for the proposed HMA mix design developed by a qualified City or County laboratory that is within one year of the approval date.\*\*

The mix design shall be performed by a lab accredited by a national authority such as Laboratory Accreditation Bureau, L-A-B for Construction Materials Testing, The Construction Materials Engineering Council (CMEC's) ISO 17025 or AASHTO Accreditation Program (AAP) and shall supply evidence of participation in the AASHTO: resource proficiency sample program.

- Mix designs for HMA accepted by Nonstatistical evaluation shall;
  - Have the aggregate structure and asphalt binder content determined in accordance with WSDOT Standard Operating Procedure 732 and meet the requirements of Sections 9-03.8(2), except that Hamburg testing for ruts and stripping are at the discretion of the Engineer, and 9-03.8(6).
  - Have anti-strip requirements, if any, for the proposed mix design determined in accordance with AASHTO T 283 or T 324, or based on historic anti-strip and aggregate source compatibility from previous WSDOT lab testing.
- <sup>43</sup> At the discretion of the Engineer, agencies may accept verified mix designs older than 12 months <sup>44</sup> from the original verification date with a certification from the Contractor that the materials and <sup>45</sup> sources are the same as those shown on the original mix design.

<sup>47</sup> Commercial Evaluation Approval of a mix design for "Commercial Evaluation" will be based on a
 <sup>48</sup> review of the Contractor's submittal of WSDOT Form 350-042 (For commercial mixes, AASHTO T
 <sup>49</sup> 324 evaluation is not required) or a Mix Design from the current WSDOT QPL or from one of the
 <sup>50</sup> processes allowed by this section. Testing of the HMA by the Contracting Agency for mix design
 <sup>51</sup> approval is not required.

2 For the Bid Item Commercial HMA, the Contractor shall select a class of HMA and design level of 3 Equivalent Single Axle Loads (ESAL's) appropriate for the required use. 4 **Reinforcing Fibers:** 5 6 Submit the following prior to Construction: 7 8 Representative fiber product sample. b. Fiber product data sheet and certification from the Manufacturer that the fiber product 10 supplied meets the requirements of this specification. 11 c. Manufacturer's instructions and general recommendations. 12 d. Performance test results of ADSR testing from a minimum of three separate laboratory 13 trials to validate dispersion efficiency. 14 e. Performance results of PCI testing from a minimum of three separate field trials to validate 15 cracking resistance. 16 f. Performance test results of FN testing from a minimum of three separate laboratory trials 17 to validate rutting resistance. 18 g. A minimum of five unique project examples and references where the reinforcing fiber 19 product was used within 250 miles of the project location 20 \*\*NOTE: Testing is NOT required on samples from the job mix. Submit previously 21 completed lab testing only. 22 23 Performance testing requirements 24 25 All historical test results submitted to validate the fiber's performance in asphalt mixes shall 26 be from previously completed laboratory and field trials using plant-mixed FRAC only. **Testing** 27 is NOT required on samples from the job mix. 28 29 Performance testing must be from laboratory trials at a fiber dosage rate equal to the rate 30 proposed for the project. Tests must be performed by an AASHTO accredited laboratory or 31 nationally recognized university testing lab and must be reviewed and approved by the project 32 engineer. 33 34 a. Aramid Dispersion State Ratio (ADSR) Tests from a minimum of three (3) separate 35 laboratory trials. 36 Perform ADSR test based on modified ASTM D2172 procedures as provided in the 37 document entitled "Extraction of Aramid Fibers from Fiber Reinforced Asphalt 38 Concrete - Special Test Method". A copy of the modified extraction methodology can 39 be obtained by making an inquiry to the Pavement and Materials Laboratory at Arizona 40 State University at NCE@asu.edu. 41 2. To validate ADSR results, average extracted aramid fiber quantity must equal 0.007 42 percent by total sample weight with no individual result less than 0.005 percent of the 43 total sample weight. 44 3. All tested fiber mixes must achieve a minimum ADSR of 85%. 45 46 b. Pavement Condition Index (PCI) side by side comparison from a minimum of three (3) 47 field trails with a minimum in-service pavement age of four years. 48 PCI surveys shall be performed according to ASTM D6433. 49

1

1 2	2.	Tests results shall include a control and a fiber reinforced pavement section. FRAC mix shall be identical to control mix except for the inclusion of fibers added at the same
3 4 5	3.	dosage as proposed on the project. In field performance sections shall be subject to the same environmental and traffic conditions. A minimum surface area of 500 yd <sup>2</sup> per FRAC and control section is
6		required.
7 8	4.	PCI results from fiber sections shall show a minimum 10 PCI points greater than the control section after a minimum of 4 years.
9		
10		ow Number (FN) Tests from a minimum of three (3) separate laboratory trials.
11		Perform FN tests using the protocol from AASHTO TP79.
12	2.	Tests results shall include a control and a fiber reinforced mix. FRAC mix shall be
13		identical to control mix except for the inclusion of fibers added at the same dosage as
14		proposed on the project.
15 16	3.	Results from fiber specimens shall show an average FN increase of at least 75% over control specimens.
17		
18 19	5-04.3 Construc	ction Requirements
20	5-04-3(1) W	eather Limitations
21	• •	HMA for wearing course on any Traveled Way beginning October 1st through March
22		llowing year without written concurrence from the Engineer.
23		ioning your minout minor concernence nem the Engineer.
24	Do not place	HMA on any wet surface, or when the average surface temperatures are less than those
25		bw, or when weather conditions otherwise prevent the proper handling or finishing of the
26	HMA.	,
27		

28

# Minimum Surface Temperature for Paving

Compacted Thickness (Feet)	Wearing Course	Other Courses
Less than 0.10	55°F	45°F
0.10 to .20	45°F	35°F
More than 0.20	35°F	35°F

29 30

# 5-04.3(2) Paving Under Traffic

- <sup>31</sup> When the Roadway being paved is open to traffic, the requirements of this Section shall apply.
- 32

The Contractor shall keep intersections open to traffic at all times except when paving the intersection or paving across the intersection. During such time, and provided that there has been an advance warning to the public, the intersection may be closed for the minimum time required to place and compact the mixture. In hot weather, the Engineer may require the application of water to the pavement to accelerate the finish rolling of the pavement and to shorten the time required before reopening to traffic.

39

<sup>40</sup> Before closing an intersection, advance warning signs shall be placed and signs shall also be placed
 <sup>41</sup> marking the detour or alternate route.

During paving operations, temporary pavement markings shall be maintained throughout the project. Temporary pavement markings shall be installed on the Roadway prior to opening to traffic. Temporary pavement markings shall be in accordance with Section 8-23.

All costs in connection with performing the Work in accordance with these requirements shall be included in the unit Contract prices for the various Bid items involved in the Contract.

5-04.3(3) Equipment

5-04.3(3)A Mixing Plant

Plants used for the preparation of HMA shall conform to the following requirements:

- 1. Equipment for Preparation of Asphalt Binder Tanks for the storage of asphalt binder shall be equipped to heat and hold the material at the required temperatures. The heating shall be accomplished by steam coils, electricity, or other approved means so that no flame shall be in contact with the storage tank. The circulating system for the asphalt binder shall be designed to ensure proper and continuous circulation during the operating period. A valve for the purpose of sampling the asphalt binder shall be placed in either the storage tank or in the supply line to the mixer.
- 2. Thermometric Equipment An armored thermometer, capable of detecting temperature ranges expected in the HMA mix, shall be fixed in the asphalt binder feed line at a location near the charging valve at the mixer unit. The thermometer location shall be convenient and safe for access by Inspectors. The plant shall also be equipped with an approved dial-scale thermometer, a mercury actuated thermometer, an electric pyrometer, or another approved thermometric instrument placed at the discharge chute of the drier to automatically register or indicate the temperature of the heated aggregates. This device shall be in full view of the plant operator.
- Heating of Asphalt Binder The temperature of the asphalt binder shall not exceed the maximum recommended by the asphalt binder manufacturer nor shall it be below the minimum temperature required to maintain the asphalt binder in a homogeneous state. The asphalt binder shall be heated in a manner that will avoid local variations in heating. The heating method shall provide a continuous supply of asphalt binder to the mixer at a uniform average temperature with no individual variations exceeding 25°F. Also, when a WMA additive is included in the asphalt binder, the temperature of the asphalt binder shall not exceed the maximum recommended by the manufacturer of the WMA additive.
  - 4. Sampling and Testing of Mineral Materials The HMA plant shall be equipped with a mechanical sampler for the sampling of the mineral materials. The mechanical sampler shall meet the requirements of Section 1-05.6 for the crushing and screening operation. The Contractor shall provide for the setup and operation of the field testing facilities of the Contracting Agency as provided for in Section 3-01.2(2).
    - 5. **Sampling HMA** The HMA plant shall provide for sampling HMA by one of the following methods:
      - a. A mechanical sampling device attached to the HMA plant.
      - b. Platforms or devices to enable sampling from the hauling vehicle without entering the hauling vehicle.
    - 5-04.3(3)B Hauling Equipment

Pigeon Springs Road HMA Project CRP 2200C Trucks used for hauling HMA shall have tight, clean, smooth metal beds and shall have a cover of canvas or other suitable material of sufficient size to protect the mixture from adverse weather. Whenever the weather conditions during the work shift include, or are forecast to include, precipitation or an air temperature less than 45°F or when time from loading to unloading exceeds 30 minutes, the cover shall be securely attached to protect the HMA.

The contractor shall provide an environmentally benign means to prevent the HMA mixture from adhering to the hauling equipment. Excess release agent shall be drained prior to filling hauling equipment with HMA. Petroleum derivatives or other coating material that contaminate or alter the characteristics of the HMA shall not be used. For live bed trucks, the conveyer shall be in operation during the process of applying the release agent.

# 5-04.3(3)C Pavers

HMA pavers shall be self-contained, power-propelled units, provided with an internally heated vibratory screed and shall be capable of spreading and finishing courses of HMA plant mix material in lane widths required by the paving section shown in the Plans.

The HMA paver shall be in good condition and shall have the most current equipment available from the manufacturer for the prevention of segregation of the HMA mixture installed, in good condition, and in working order. The equipment certification shall list the make, model, and year of the paver and any equipment that has been retrofitted.

The screed shall be operated in accordance with the manufacturer's recommendations and shall effectively produce a finished surface of the required evenness and texture without tearing, shoving, segregating, or gouging the mixture. A copy of the manufacturer's recommendations shall be provided upon request by the Contracting Agency. Extensions will be allowed provided they produce the same results, including ride, density, and surface texture as obtained by the primary screed. Extensions without augers and an internally heated vibratory screed shall not be used in the Traveled Way.

When specified in the Contract, reference lines for vertical control will be required. Lines shall be placed on both outer edges of the Traveled Way of each Roadway. Horizontal control utilizing the reference line will be permitted. The grade and slope for intermediate lanes shall be controlled automatically from reference lines or by means of a mat referencing device and a slope control device. When the finish of the grade prepared for paving is superior to the established tolerances and when, in the opinion of the Engineer, further improvement to the line, grade, cross-section, and smoothness can best be achieved without the use of the reference line, a mat referencing device may be substituted for the reference line. Substitution of the device will be subject to the continued approval of the Engineer. A joint matcher may be used subject to the approval of the Engineer. The reference line may be removed after the completion of the first course of HMA when approved by the Engineer. Whenever the Engineer determines that any of these methods are failing to provide the necessary vertical control, the reference lines will be reinstalled by the Contractor.

The Contractor shall furnish and install all pins, brackets, tensioning devices, wire, and accessories necessary for satisfactory operation of the automatic control equipment.

<sup>48</sup> If the paving machine in use is not providing the required finish, the Engineer may suspend Work
 <sup>49</sup> as allowed by Section 1-08.6. Any cleaning or solvent type liquids spilled on the pavement shall
 <sup>50</sup> be thoroughly removed before paving proceeds.

## 5-04.3(3)D Material Transfer Vehicle

When used, the MTV shall mix the HMA after delivery by the hauling equipment and prior to laydown by the paving machine. Mixing of the HMA shall be sufficient to obtain a uniform temperature throughout the mixture.

- To be approved for use, an MTV:
  - 1. Shall be self-propelled vehicle, separate from the hauling vehicle or paver.
  - 2. Shall not be connected to the hauling vehicle or paver.
  - 3. May accept HMA directly from the haul vehicle.
  - 4. Shall mix the HMA after delivery by the hauling equipment and prior to placement into the paving machine.
  - 5. Shall mix the HMA sufficiently to obtain a uniform temperature throughout the mixture.

Direct transfer of the HMA mixture from the hauling equipment to the paving machine will not be allowed. The Contractor shall use a self-propelled material transfer vehicle (MTV) to deliver the HMA mixture from the hauling equipment to the paving machine when placing HMA pavement on travel lanes and shoulders, when shoulders are paved in conjunction with travel lanes. A material transfer vehicle is not required for small quantities such as driveways and is optional for shoulders that are paved separately from the driving lane(s). A windrow elevator is not acceptable as a transfer device.

The transfer vehicle's holding hopper shall have a minimum capacity of 15 tons. The material transfer vehicle shall mix the HMA after delivery by the hauling equipment but prior to lay down by the paving machine. Mixing of the HMA material shall be sufficient to obtain a consistent temperature throughout the mixture. If a transfer vehicle does not have holding or mixing capabilities, the paving machine shall be fitted with a holding and mixing hopper having a minimum capacity of 15 tons.

Prior to use, the Contractor shall submit the manufacturer and model number of the equipment to the Engineer for review and approval. All costs to incorporate the material transfer device or vehicle into the paving train shall be included in the unit contract price for the HMA.

The Contractor shall deliver the mixture to the paving machine at a rate that provides continuous operation of the paving machine, except for unavoidable delay or breakdown. If excessive stopping of the paving machine occurs during paving operations, the Engineer may suspend paving operations until the mixture deliver rate matches the paving machine operation.

**5-04.3(3)E** Rollers

Rollers shall be of the steel wheel, vibratory, oscillatory, or pneumatic tire type, in good condition and capable of reversing without backlash. Operation of the roller shall be in accordance with the manufacturer's recommendations. When ordered by the Engineer for any roller planned for use on the project, the Contractor shall provide a copy of the manufacturer's recommendation for the use of that roller for compaction of HMA. The number and weight of rollers shall be sufficient to compact the mixture in compliance with the requirements of Section 5-04.3(10). The use of equipment that results in crushing of the aggregate will not be permitted. Rollers producing pickup, washboard, uneven compaction of the surface, displacement of the mixture or other undesirable results shall not be used.

# 5-04.3(4) Preparation of Existing Paved Surfaces

When the surface of the existing pavement or old base is irregular, the Contractor shall bring it to a uniform grade and cross-section as shown on the Plans or approved by the Engineer.

Preleveling of uneven or broken surfaces over which HMA is to be placed may be accomplished by using an asphalt paver, a motor patrol grader, or by hand raking, as approved by the Engineer.

8 Compaction of preleveling HMA shall be to the satisfaction of the Engineer and may require the use 9 of small steel wheel rollers, plate compactors, or pneumatic rollers to avoid bridging across preleveled 10 areas by the compaction equipment. Equipment used for the compaction of preleveling HMA shall be 11 approved by the Engineer.

12

20

1 2

3

4 5

6

7

13 Before construction of HMA on an existing paved surface, the entire surface of the pavement shall 14 be clean. All fatty asphalt patches, grease drippings, and other objectionable matter shall be entirely 15 removed from the existing pavement. All pavements or bituminous surfaces shall be thoroughly 16 cleaned of dust, soil, pavement grindings, and other foreign matter. All holes and small depressions 17 shall be filled with an appropriate class of HMA. The surface of the patched area shall be leveled and 18 compacted thoroughly. Prior to the application of tack coat, or paving, the condition of the surface 19 shall be approved by the Engineer.

21 A tack coat of asphalt shall be applied to all paved surfaces on which any course of HMA is to be 22 placed or abutted; except that tack coat may be omitted from clean, newly paved surfaces at the 23 discretion of the Engineer. Tack coat shall be uniformly applied to cover the existing pavement with 24 a thin film of residual asphalt free of streaks and bare spots at a rate between 0.02 and 0.10 gallons 25 per square yard of retained asphalt. The rate of application shall be approved by the Engineer. A 26 heavy application of tack coat shall be applied to all joints. For Roadways open to traffic, the 27 application of tack coat shall be limited to surfaces that will be paved during the same working shift. 28 The spreading equipment shall be equipped with a thermometer to indicate the temperature of the 29 tack coat material.

30

31

Equipment shall not operate on tacked surfaces until the tack has broken and cured. If the 32 Contractor's operation damages the tack coat it shall be repaired prior to placement of the HMA.

33

34 The tack coat shall be CSS-1, or CSS-1h emulsified asphalt. The CSS-1 and CSS-1h emulsified 35 asphalt may be diluted once with water at a rate not to exceed one part water to one part emulsified 36 asphalt. The tack coat shall have sufficient temperature such that it may be applied uniformly at the 37 specified rate of application and shall not exceed the maximum temperature recommended by the 38 emulsified asphalt manufacturer.

39

40 41

42 43

44

45

46

# 5-04.3(4)A Crack Sealing

# 5-04.3(4)A1 General

When the Proposal includes a pay item for crack sealing, seal all cracks ¼ inch in width and greater. If the Proposal does not include an item for crack sealing or sealed joints it shall be incidental to and included in the unit contract price per ton for the HMA

47 Cleaning: Ensure that cracks are thoroughly clean, dry and free of all loose and foreign 48 material when filling with crack sealant material. Use a hot compressed air lance to dry and 49 warm the pavement surfaces within the crack immediately prior to filling a crack with the 50 sealant material. Do not overheat pavement. Do not use direct flame dryers. Routing cracks 51 is not required.

**Sand Slurry**: For cracks that are to be filled with sand slurry, thoroughly mix the components and pour the mixture into the cracks until full. Add additional CSS-1 cationic emulsified asphalt to the sand slurry as needed for workability to ensure the mixture will completely fill the cracks. Strike off the sand slurry flush with the existing pavement surface and allow the mixture to cure. Top off cracks that were not completely filled with additional sand slurry. Do not place the HMA overlay until the slurry has fully cured.

The sand slurry shall consist of approximately 20 percent CSS-1 emulsified asphalt, approximately 2 percent portland cement, water (if required), and the remainder clean Class 1 or 2 fine aggregate per section 9-03.1(2). The components shall be thoroughly mixed and then poured into the cracks and joints until full. The following day, any cracks or joints that are not completely filled shall be topped off with additional sand slurry. After the sand slurry is placed, the filler shall be struck off flush with the existing pavement surface and allowed to cure. The HMA overlay shall not be placed until the slurry has fully cured. The requirements of Section 1-06 will not apply to the portland cement and sand used in the sand slurry.

- In areas where HMA will be placed, use sand slurry to fill the cracks.
  - In areas where HMA will not be placed, fill the cracks as follows:
    - 1. Cracks ¼ inch to 1 inch in width fill with hot poured sealant.
    - 2. Cracks greater than 1 inch in width fill with sand slurry.

**Hot Poured Sealant**: For cracks that are to be filled with hot poured sealant, apply the material in accordance with these requirements and the manufacturer's recommendations. Furnish a Type 1 Working Drawing of the manufacturer's product information and recommendations to the Engineer prior to the start of work, including the manufacturer's recommended heating time and temperatures, allowable storage time and temperatures after initial heating, allowable reheating criteria, and application temperature range. Confine hot poured sealant material within the crack. Clean any overflow of sealant from the pavement surface. If, in the opinion of the Engineer, the Contractor's method of sealing the cracks with hot poured sealant results in an excessive amount of material on the pavement surface, stop and correct the operation to eliminate the excess material.

## 5-04.3(4)A2 Crack Sealing Areas Prior to Paving

In areas where HMA will be placed, use sand slurry to fill the cracks.

# 5-04.3(4)A3 Crack Sealing Areas Not to be Paved

In areas where HMA will not be placed, fill the cracks as follows:

- 1. Cracks ¼ inch to 1 inch in width fill with hot poured sealant.
- 2. Cracks greater than 1 inch in width fill with sand slurry.
- 5-04.3(4)B Vacant

- **5-04.3(4)C** Pavement Repair
- <sup>48</sup> All planning bituminous pavement shall be complete before performing pavement repair. The <sup>49</sup> Contractor shall excavate pavement repair areas and shall backfill these with HMA in accordance

with the details shown in the Plans and as marked in the field. The Contractor shall conduct the excavation operations in a manner that will protect the pavement that is to remain. Pavement not designated to be removed that is damaged as a result of the Contractor's operations shall be repaired by the Contractor to the satisfaction of the Engineer at no cost to the Contracting Agency. The Contractor shall excavate only within one lane at a time unless approved otherwise by the Engineer. The Contractor shall not excavate more area than can be completely finished during the same shift, unless approved by the Engineer.

Unless otherwise shown in the Plans or determined by the Engineer, excavate to a depth of 1.0 feet. The Engineer will make the final determination of the excavation depth required. The minimum width of any pavement repair area shall be 40 inches unless shown otherwise in the Plans. Before any excavation, the existing pavement shall be sawcut or shall be removed by a pavement grinder. Excavated materials will become the property of the Contractor and shall be disposed of in a Contractor-provided site off the Right of Way or used in accordance with Sections 2-02.3(3) or 9-03.21.

Asphalt for tack coat shall be required as specified in Section 5-04.3(4). A heavy application of tack coat shall be applied to all surfaces of existing pavement in the pavement repair area.

Placement of the HMA backfill shall be accomplished in lifts not to exceed 0.35-foot compacted depth. Lifts that exceed 0.35-foot of compacted depth may be accomplished with the approval of the Engineer. Each lift shall be thoroughly compacted by a mechanical tamper or a roller.

23

1

2

3

4

5

6

7

8 9

10

11

12

13

14

15

16 17

18

19 20

21

22

24

# 5-04.3(5) Producing/Stockpiling Aggregates and RAP

Aggregates and RAP shall be stockpiled according to the requirements of Section 3-02. Sufficient storage space shall be provided for each size of aggregate and RAP. Materials shall be removed from stockpile(s) in a manner to ensure minimal segregation when being moved to the HMA plant for processing into the final mixture. Different aggregate sizes shall be kept separated until they have been delivered to the HMA plant.

30 31

32

33

## 5-04.3(5)A Vacant

## 5-04.3(6) Mixing

After the required amount of mineral materials, asphalt binder, recycling agent and anti-stripping additives have been introduced into the mixer the HMA shall be mixed until complete and uniform coating of the particles and thorough distribution of the asphalt binder throughout the mineral materials is ensured.

38

When discharged, the temperature of the HMA shall not exceed the optimum mixing temperature by more than 25°F as shown on the reference mix design report or as approved by the Engineer. A maximum water content of 2 percent in the mix, at discharge, will be allowed providing the water causes no problems with handling, stripping, or flushing. If the water in the HMA causes any of these problems, the moisture content shall be reduced as directed by the Engineer.

44

Storing or holding of the HMA in approved storage facilities will be permitted with approval of the
 Engineer, but in no event shall the HMA be held for more than 24 hours. HMA held for more than 24
 hours after mixing shall be rejected. Rejected HMA shall be disposed of by the Contractor at no
 expense to the Contracting Agency. The storage facility shall have an accessible device located at
 the top of the cone or about the third point. The device shall indicate the amount of material in storage.
 No HMA shall be accepted from the storage facility when the HMA in storage is below the top of the

cone of the storage facility, except as the storage facility is being emptied at the end of the working shift.

#### Reinforcing Fibers

- 1. Delivery & Storage: Deliver fiber-reinforcement to plant in sealed, undamaged containers with labels intact and legible, indicating material name and lot number. Store materials covered and off the ground. Keep sand and dust out of boxes and do not allow boxes to become wet.
- 2. Add aramid and polyolefin reinforcing fiber blends at a dosage rate of one (1) pound per one (1) ton of asphalt.
- 3. Add alternative aramid fiber blends at a rate proposed by the manufacturer that achieves the ADSR, PCI, and FN results required in Section 5-04.2.
- 4. Have a fiber manufacturer's representative on site during mixing and production. This requirement can be waived if fiber manufacturer and asphalt producer can supply evidence of manufacturer's brand of fiber being successfully produced a minimum of three times at the asphalt plant to be used for the project.
- 5. Batch Plant. When a batch plant is used, add fiber to the aggregate in the weigh hopper and increase both dry and wet mixing times. Ensure that the fiber is uniformly distributed before the injection of asphalt cement into the mixture.
- 6. Drum Plant:
  - a. Inject fibers through the RAP collar by feeding them with a blower tube system. Rate the feeding of fibers with the rate the plant is producing asphalt mix. If there is any evidence of fiber balls at the discharge chute, increase the mixing time and/or temperature or change the angle of the fiber feeder line to increase dry mixing time.
- b. When using a blower tube system, add fibers continuously and in a steady uniform manner. Provide automated proportioning devices and control delivery within ±10% of the mass of the fibers required. Perform an equipment calibration to the satisfaction of the fiber manufacturer's representative to show that the fiber is being accurately metered and uniformly distributed into the mix.
  - Include the following with the blower tube system:
    - Low level indicators
    - No-flow indicators
    - A printout of feed rate status in pounds/minute
    - A section of transparent pipe in the fiber supply line for observing consistency of flow or feed.

0.35 feet

• Manufacturer's representative's approval of fiber addition system

#### 45 5-04.3(7) Spreading and Finishing

The mixture shall be laid upon an approved surface, spread, and struck off to the grade and elevation
 established. HMA pavers complying with Section 5-04.3(3) shall be used to distribute the mixture.
 Unless otherwise directed by the Engineer, the nominal compacted depth of any layer of any course
 shall not exceed the following:

51HMA Class 1"52HMA Class ¾" and HMA Class ½"

1		wearing course	0.30 feet
2		other courses	0.35 feet
3	HMA Class 3/8"		0.20 feet

<sup>5</sup> On areas where irregularities or unavoidable obstacles make the use of mechanical spreading and <sup>6</sup> finishing equipment impractical, the paving may be done with other equipment or by hand.

<sup>8</sup> When more than one JMF is being utilized to produce HMA, the material produced for each JMF shall <sup>9</sup> be placed by separate spreading and compacting equipment. The intermingling of HMA produced <sup>10</sup> from more than one JMF is prohibited. Each strip of HMA placed during a work shift shall conform to <sup>11</sup> a single JMF established for the class of HMA specified unless there is a need to make an adjustment <sup>12</sup> in the JMF.

- <sup>14</sup> 5-04.3(8) Aggregate Acceptance Prior to Incorporation in HMA
- For HMA accepted by nonstatistical evaluation the aggregate properties of sand equivalent, uncompacted void content and fracture will be evaluated in accordance with Section 3-04. Sampling and testing of aggregates for HMA accepted by commercial evaluation will be at the option of the Engineer.
- <sup>20</sup> 5-04.3(9) HMA Mixture Acceptance
- <sup>21</sup> Acceptance of HMA shall be as provided under nonstatistical, or commercial evaluation.
- <sup>23</sup> Nonstatistical evaluation will be used for the acceptance of HMA unless Commercial Evaluation is
   <sup>24</sup> specified.
- 25

4

7

13

19

22

<sup>26</sup> Commercial evaluation will be used for Commercial HMA and for other classes of HMA in the following
 <sup>27</sup> applications: sidewalks, road approaches, ditches, slopes, paths, trails, gores, prelevel, temporary
 <sup>28</sup> pavement, and pavement repair. Other nonstructural applications of HMA accepted by commercial
 <sup>29</sup> evaluation shall be as approved by the Engineer. Sampling and testing of HMA accepted by
 <sup>30</sup> commercial evaluation will be at the option of the Engineer.

31

32

33

34

35

36 37

38

39

40

41

42

43

44

45 46 47

48

The mix design will be the initial JMF for the class of HMA. The Contractor may request a change in the JMF. Any adjustments to the JMF will require the approval of the Engineer and may be made in accordance with this section.

- **Reinforcing Fibers** 
  - 1. Follow manufacturer's representative's recommendations for placement of FRAC.
  - 2. Collect a small sample (10-20kg) of mix from the discharge chute during first 50 tons of production. If there are one or more undistributed fiber clips or bundles, adjust mixing operations per manufacturer's recommendations to eliminate fiber bundles.
  - 3. Visually observe FRAC mix in the back of first three trucks and every tenth truck thereafter to confirm adequate blending of the fiber.
  - 4. Remove any observed fiber bundles from placed mixture and adjust operations per the manufacturer's recommendation to eliminate future fiber bundle development.

# HMA Tolerances and Adjustments

- 1. **Job Mix Formula Tolerances** The constituents of the mixture at the time of acceptance shall be within tolerance. The tolerance limits will be established as follows:
  - For Asphalt Binder and Air Voids (Va), the acceptance limits are determined by adding the tolerances below to the approved JMF values. These values will also be the Upper Specification Limit (USL) and Lower Specification Limit (LSL) required in Section 1-06.2(2)D2

Property	Non-Statistical Evaluation	Commercial Evaluation
Asphalt Binder	+/- 0.5%	+/- 0.7%
Air Voids, Va	2.5% min. and 5.5% max	N/A

- For Aggregates in the mixture:
  - a. First, determine preliminary upper and lower acceptance limits by applying the following tolerances to the approved JMF.

Aggregate Percent Passing	Non- Statistical Evaluation	Commercial Evaluation
1", ¾", ½", and 3/8" sieves	+/- 6%	+/- 8%
No. 4 sieve	+/-5%	+/- 8%
No. 8 Sieve	+/- 4%	+/-8%
No. 200 sieve	+/- 1.0%	+/- 3.0%

- b. Second, adjust the preliminary upper and lower acceptance limits determined from step (a) the minimum amount necessary so that none of the aggregate properties are outside the control points in Section 9-03.8(6). The resulting values will be the upper and lower acceptance limits for aggregates, as well as the USL and LSL required in Section 1-06.2(2)D2.
- Job Mix Formula Adjustments An adjustment to the aggregate gradation or asphalt binder content of the JMF requires approval of the Engineer. Adjustments to the JMF will only be considered if the change produces material of equal or better quality and may require the development of a new mix design if the adjustment exceeds the amounts listed below.
- a. **Aggregates** –2 percent for the aggregate passing the 1½", 1", ¾", ½", ¾", and the No. 4 sieves, 1 percent for aggregate passing the No. 8 sieve, and 0.5 percent for the aggregate passing the No. 200 sieve. The adjusted JMF shall be within the range of the control points in Section 9-03.8(6).
  - Asphalt Binder Content The Engineer may order or approve changes to asphalt binder content. The maximum adjustment from the approved mix design for the asphalt binder content shall be 0.3 percent
  - 5-04.3(9)A Vacant
- 5-04.3(9)B Vacant

- 5-04.3(9)C Mixture Acceptance Nonstatistical Evaluation
- HMA mixture which is accepted by Nonstatistical Evaluation will be evaluated by the Contracting Agency by dividing the HMA tonnage into lots.

# 5-04.3(9)C1 Mixture Nonstatistical Evaluation – Lots and Sublots

A lot is represented by randomly selected samples of the same mix design that will be tested for acceptance. A lot is defined as the total quantity of material or work produced for each Job Mix Formula placed. Only one lot per JMF is expected. A sublot shall be equal to one day's

1 2	production or 800 tons, whichever is less except that the final sublot will be a minimum of 400 tons and may be increased to 1200 tons.
3	
4	All of the test results obtained from the acceptance samples from a given lot shall be evaluated
5	collectively. If the Contractor requests a change to the JMF that is approved, the material
6	produced after the change will be evaluated on the basis of the new JMF for the remaining
7 8	sublots in the current lot and for acceptance of subsequent lots. For a lot in progress with a
9	CPF less than 0.75, a new lot will begin at the Contractor's request after the Engineer is satisfied that material conforming to the Specifications can be produced.
10	
11	Sampling and testing for evaluation shall be performed on the frequency of one sample per
12	sublot.
13	5-04.3(9)C2 Mixture Nonstatistical Evaluation Sampling
15	Samples for acceptance testing shall be obtained by the Contractor when ordered by the
16	Engineer. The Contractor shall sample the HMA mixture in the presence of the Engineer and
17	in accordance with AASH-TO T 168. A minimum of three samples should be taken for each
18	class of HMA placed on a project. If used in a structural application, at least one of the three
19	samples shall to be tested.
20	
21	Sampling and testing HMA in a Structural application where quantities are less than 400 tons
22 23	is at the discretion of the Engineer.
24	
24	For HMA used in a structural application and with a total project quantity less than 800 tons
26	but more than 400 tons, a minimum of one acceptance test shall be performed. In all cases, a minimum of 3 samples will be obtained at the point of acceptance, a minimum of one of the
27	three samples will be tested for conformance to the JMF:
28	
29 30	<ul> <li>If the test results are found to be within specification requirements, additional testing will be at the Engineer's discretion.</li> </ul>
31	If test results are found not to be within specification requirements, additional testing
32	of the remaining samples to determine a Composite Pay Factor (CPF) shall be
33	performed.
34	5.04.2(0)C2. Mixture Nenetatistical Evolution Accontance Testing
35	5-04.3(9)C3 Mixture Nonstatistical Evaluation – Acceptance Testing
36 37	Testing of HMA for compliance of V <sub>a</sub> will be at the option of the Contracting Agency. If tested,
38	compliance of $V_a$ will use WSDOT SOP 731.
39	Testing for compliance of asphalt binder content will be by WSDOT FOP for AASHTO T 308.
40	
41	Testing for compliance of gradation will be by FOP for WAQTC T 27/T 11.
42	
43	5-04.3(9)C4 Mixture Nonstatistical Evaluation – Pay Factors
44	For each lot of material falling outside the tolerance limits in 5-04.3(9), the Contracting Agency
45	will determine a Composite Pay Factor (CPF) using the following price adjustment factors:
46	
47	
48	

Table of Price Adjustment Factor	ors
Constituent	Factor "f"
All aggregate passing: $1\frac{1}{2}$ ", $1$ ", $\frac{3}{4}$ ", $\frac{1}{2}$ ", $\frac{3}{8}$ " and No.4 sieves	2
All aggregate passing No. 8 sieve	15
All aggregate passing No. 200 sieve	20
Asphalt binder	40
Air Voids (Va) (where applicable)	20

Each lot of HMA produced under Nonstatistical Evaluation and having all constituents falling within the tolerance limits of the job mix formula shall be accepted at the unit Contract price with no further evaluation. When one or more constituents fall outside the nonstatistical tolerance limits in the Job Mix Formula shown in Table of Price Adjustment Factors, the lot shall be evaluated in accordance with Section 1-06.2 to determine the appropriate CPF. The nonstatistical tolerance limits will be used in the calculation of the CPF and the maximum CPF shall be 1.00. When less than three sublots exist, backup samples of the existing sublots or samples from the Roadway shall be tested to provide a minimum of three sets of results for evaluation.

## 5-04.3(9)C5 Vacant

## 5-04.3(9)C6 Mixture Nonstatistical Evaluation – Price Adjustments

For each lot of HMA mix produced under Nonstatistical Evaluation when the calculated CPF is less than 1.00, a Nonconforming Mix Factor (NCMF) will be determined. The NCMF equals the algebraic difference of CPF minus 1.00 multiplied by 60 percent. The total job mix compliance price adjustment will be calculated as the product of the NCMF, the quantity of HMA in the lot in tons, and the unit Contract price per ton of mix.

If a constituent is not measured in accordance with these Specifications, its individual pay factor will be considered 1.00 in calculating the Composite Pay Factor (CPF).

## 5-04.3(9)C7 Mixture Nonstatistical Evaluation - Retests

The Contractor may request a sublot be retested. To request a retest, the Contractor shall submit a written request within 7 calendar days after the specific test results have been received. A split of the original acceptance sample will be retested. The split of the sample will not be tested with the same tester that ran the original acceptance test. The sample will be tested for a complete gradation analysis, asphalt binder content, and, at the option of the agency, V<sub>a</sub>. The results of the retest will be used for the acceptance of the HMA in place of the original sublot sample test results. The cost of testing will be deducted from any monies due or that may come due the Contractor under the Contract at the rate of \$500 per sample.

#### 5-04.3 (9)D Mixture Acceptance – Commercial Evaluation

If sampled and tested, HMA produced under Commercial Evaluation and having all constituents
 falling within the tolerance limits of the job mix formula shall be accepted at the unit Contract price
 with no further evaluation. When one or more constituents fall outside the commercial tolerance
 limits in the Job Mix Formula shown in 5-04.3(9), the lot shall be evaluated in accordance with
 Section 1-06.2 to determine the appropriate CPF. The commercial tolerance limits will be used in
 the calculation of the CPF and the maximum CPF shall be 1.00. When less than three sublots

- exist, backup samples of the existing sublots or samples from the street shall be tested to provide a minimum of three sets of results for evaluation.
- For each lot of HMA mix produced and tested under Commercial Evaluation when the calculated CPF is less than 1.00, a Nonconforming Mix Factor (NCMF) will be determined. The NCMF equals the algebraic difference of CPF minus 1.00 multiplied by 60 percent. The Job Mix Compliance Price Adjustment will be calculated as the product of the NCMF, the quantity of HMA in the lot in tons, and the unit Contract price per ton of mix.
  - If a constituent is not measured in accordance with these Specifications, its individual pay factor will be considered 1.00 in calculating the Composite Pay Factor (CPF).

## 5-04.3(10) HMA Compaction Acceptance

14 HMA mixture accepted by nonstatistical evaluation that is used in traffic lanes, including lanes for 15 intersections, ramps, truck climbing, weaving, and speed change, and having a specified compacted 16 course thickness greater than 0.10-foot, shall be compacted to a specified level of relative density. 17 The specified level of relative density shall be a Composite Pay Factor (CPF) of not less than 0.75 18 when evaluated in accordance with Section 1-06.2, using a LSL of 92.0 (minimum of 92 percent of 19 the maximum density). The maximum density shall be determined by WSDOT FOP for AASHTO T 20 729. The specified level of density attained will be determined by the evaluation of the density of the 21 pavement. The density of the pavement shall be determined in accordance with WSDOT FOP for 22 ASSHTO T 355, except that gauge correlation will be at the discretion of the Engineer, when using 23 the nuclear density gauge and WSDOT SOP 736 when using cores to determine density.

24

25

26

27

1

2

3

5 6

7

8

9 10

11

12

13

Tests for the determination of the pavement density will be taken in accordance with the required procedures for measurement by a nuclear density gauge or roadway cores after completion of the finish rolling.

28

If the Contracting Agency uses a nuclear density gauge to determine density the test procedures
 WSDOT FOP for ASSHTO T 355 and WSDOT SOP T 729 will be used on the day the mix is placed and prior to opening to traffic.

32

Roadway cores for density may be obtained by either the Contracting Agency or the Contractor in
 accordance with WSDOT SOP 734. The core diameter shall be 4-inches minimum, unless otherwise
 approved by the Engineer. Roadway cores will be tested by the Contracting Agency in accordance
 with WSDOT FOP for AASHTO T 166.

37

If the Contract includes the Bid item "Roadway Core" the cores shall be obtained by the Contractor
 in the presence of the Engineer on the same day the mix is placed and at locations designated by the
 Engineer. If the Contract does not include the Bid item "Roadway Core" the Contracting Agency will
 obtain the cores.

42

45

For a lot in progress with a CPF less than 0.75, a new lot will begin at the Contractor's request after
 the Engineer is satisfied that material conforming to the Specifications can be produced.

<sup>46</sup> HMA mixture accepted by commercial evaluation and HMA constructed under conditions other than
 <sup>47</sup> those listed above shall be compacted on the basis of a test point evaluation of the compaction train.
 <sup>48</sup> The test point evaluation shall be performed in accordance with instructions from the Engineer. The
 <sup>49</sup> number of passes with an approved compaction train, required to attain the maximum test point
 <sup>50</sup> density, shall be used on all subsequent paving.

<sup>2</sup> HMA for preleveling shall be thoroughly compacted. HMA that is used for preleveling wheel rutting <sup>3</sup> shall be compacted with a pneumatic tire roller unless otherwise approved by the Engineer.

## Test Results

For a sublot that has been tested with a nuclear density gauge that did not meet the minimum of 92 percent of the reference maximum density in a compaction lot with a CPF below 1.00 and thus subject to a price reduction or rejection, the Contractor may request that a core be used for determination of the relative density of the sublot. The relative density of the core will replace the relative density determined by the nuclear density gauge for the sublot and will be used for calculation of the CPF and acceptance of HMA compaction lot.

When cores are taken by the Contracting Agency at the request of the Contractor, they shall be requested by noon of the next workday after the test results for the sublot have been provided or made available to the Contractor. Core locations shall be outside of wheel paths and as determined by the Engineer. Traffic control shall be provided by the Contractor as requested by the Engineer. Failure by the Contractor to provide the requested traffic control will result in forfeiture of the request for cores. When the CPF for the lot based on the results of the HMA cores is less than 1.00, the cost for the coring will be deducted from any monies due or that may become due the Contractor under the Contract at the rate of \$200 per core and the Contractor shall pay for the cost of the traffic control.

## 5-04.3(10)A HMA Compaction – General Compaction Requirements

Compaction shall take place when the mixture is in the proper condition so that no undue displacement, cracking, or shoving occurs. Areas inaccessible to large compaction equipment shall be compacted by other mechanical means. Any HMA that becomes loose, broken, contaminated, shows an excess or deficiency of asphalt, or is in any way defective, shall be removed and replaced with new hot mix that shall be immediately compacted to conform to the surrounding area.

The type of rollers to be used and their relative position in the compaction sequence shall generally be the Contractor's option, provided the specified densities are attained. Unless the Engineer has approved otherwise, rollers shall only be operated in the static mode when the internal temperature of the mix is less than 175°F. Regardless of mix temperature, a roller shall not be operated in a mode that results in checking or cracking of the mat. Rollers shall only be operated in static mode on bridge decks.

## 5-04.3(10)B HMA Compaction – Cyclic Density

Low cyclic density areas are defined as spots or streaks in the pavement that are less than 90 percent of the theoretical maximum density. At the Engineer's discretion, the Engineer may evaluate the HMA pavement for low cyclic density, and when doing so will follow WSDOT SOP 733. A \$500 Cyclic Density Price Adjustment will be assessed for any 500-foot section with two or more density readings below 90 percent of the theoretical maximum density.

- 5-04.3(10)C Vacant
  - 5-04.3(10)D HMA Nonstatistical Compaction

# 5-04.3(10)D1 HMA Nonstatistical Compaction – Lots and Sublots

HMA compaction which is accepted by nonstatistical evaluation will be based on acceptance testing performed by the Contracting Agency dividing the project into compaction lots.

1 A lot is represented by randomly selected samples of the same mix design that will be tested 2 for acceptance. A lot is defined as the total quantity of material or work produced for each Job 3 Mix Formula placed. Only one lot per JMF is expected. A sublot shall be equal to one day's 4 production or 400 tons, whichever is less except that the final sublot will be a minimum of 200 5 tons and may be increased to 800 tons. Testing for compaction will be at the rate of 5 tests 6 per sublot per WSDOT T 738. The compaction test locations will be determined by the Engineer in accordance with WSDOT Test Method T 716. 8 9 The sublot locations within each density lot will be determined by the Engineer. For a lot in 10 progress with a CPF less than 0.75, a new lot will begin at the Contractor's request after the 11 Engineer is satisfied that material conforming to the Specifications can be produced. 12 13 HMA mixture accepted by commercial evaluation and HMA constructed under conditions 14 other than those listed above shall be compacted on the basis of a test point evaluation of the 15 compaction train. The test point evaluation shall be performed in accordance with instructions 16 from the Engineer. The number of passes with an approved compaction train, required to 17 attain the maximum test point density, shall be used on all subsequent paving. 18 19

HMA for preleveling shall be thoroughly compacted. HMA that is used to prelevel wheel ruts shall be compacted with a pneumatic tire roller unless otherwise approved by the Engineer.

# 5-04.3(10)D2 HMA Compaction Nonstatistical Evaluation – Acceptance Testing

The location of the HMA compaction acceptance tests will be randomly selected by the Engineer from within each sublot, with one test per sublot. The Contracting Agency will determine the random sample location using WSDOT Test Method T 716.

5-04.3(10)D3 HMA Nonstatistical Compaction – Price Adjustments

For each compaction lot with one or two sublots, having all sublots attain a relative density that is 92 percent of the reference maximum density the HMA shall be accepted at the unit Contract price with no further evaluation. When a sublot does not attain a relative density that is 92 percent of the reference maximum density, the lot shall be evaluated in accordance with Section 1-06.2 to determine the appropriate CPF. The maximum CPF shall be 1.00, however, lots with a calculated CPF in excess of 1.00 will be used to offset lots with CPF values below 1.00 but greater than 0.90. Lots with CPF lower than 0.90 will be evaluated for compliance per 5-04.3(11). Additional testing by either a nuclear moisture-density gauge or cores will be completed as required to provide a minimum of three tests for evaluation.

For compaction below the required 92% a Non-Conforming Compaction Factor (NCCF) will be determined. The NCCF equals the algebraic difference of CPF minus 1.00 multiplied by 40 percent. The Compaction Price Adjustment will be calculated as the product of CPF, the quantity of HMA in the compaction control lot in tons, and the unit Contract price per ton of mix.

5-04.3(11) Reject Work

7

20

21

22 23

24

25

26

27 28

29

30

31

32

33

34

35

36

37 38

39

40

41

42

43

44 45

46

5-04.3(11)A Reject Work General

47 Work that is defective or does not conform to Contract requirements shall be rejected. The 48 Contractor may propose, in writing, alternatives to removal and replacement of rejected material. 49 Acceptability of such alternative proposals will be determined at the sole discretion of the 50 Engineer. HMA that has been rejected is subject to the requirements in Section 1-06.2(2) and this specification, and the Contractor shall submit a corrective action proposal to the Engineer for approval.

# 5-04.3(11)B Rejection by Contractor

 The Contractor may, prior to sampling, elect to remove any defective material and replace it with new material. Any such new material will be sampled, tested, and evaluated for acceptance.

# 5-04.3(11)C Rejection Without Testing (Mixture or Compaction)

The Engineer may, without sampling, reject any batch, load, or section of Roadway that appears defective. Material rejected before placement shall not be incorporated into the pavement. Any rejected section of Roadway shall be removed.

No payment will be made for the rejected materials or the removal of the materials unless the Contractor requests that the rejected material be tested. If the Contractor elects to have the rejected material tested, a minimum of three representative samples will be obtained and tested. Acceptance of rejected material will be based on conformance with the nonstatistical acceptance Specification. If the CPF for the rejected material is less than 0.75, no payment will be made for the rejected material; in addition, the cost of sampling and testing shall be borne by the Contractor. If the CPF is greater than or equal to 0.75, the cost of sampling and testing will be borne by the Contracting Agency. If the material is rejected material will be at a CPF of 0.75. If rejection occurs after placement and the CPF is greater than or equal to 0.75, compensation for the rejected material will be at the calculated CPF with an addition of 25 percent of the unit Contract price added for the cost of removal and disposal.

## <sup>26</sup> 5-04.3(11)D Rejection - A Partial Sublot

In addition to the random acceptance sampling and testing, the Engineer may also isolate from a normal sublot any material that is suspected of being defective in relative density, gradation or asphalt binder content. Such isolated material will not include an original sample location. A minimum of three random samples of the suspect material will be obtained and tested. The material will then be statistically evaluated as an independent lot in accordance with Section 1-06.2(2).

# 34 5-04.3(11)E Rejection - An Entire Sublot

An entire sublot that is suspected of being defective may be rejected. When a sublot is rejected a minimum of two additional random samples from this sublot will be obtained. These additional samples and the original sublot will be evaluated as an independent lot in accordance with Section 1-06.2(2).

# 5-04.3(11)F Rejection - A Lot in Progress

The Contractor shall shut down operations and shall not resume HMA placement until such time as the Engineer is satisfied that material conforming to the Specifications can be produced:

- 1. When the Composite Pay Factor (CPF) of a lot in progress drops below 1.00 and the Contractor is taking no corrective action, or
- 2. When the Pay Factor (PF) for any constituent of a lot in progress drops below 0.95 and the Contractor is taking no corrective action, or
- 3. When either the PFi for any constituent or the CPF of a lot in progress is less than 0.75.
- 5-04.3(11)G Rejection An Entire Lot (Mixture or Compaction)

An entire lot with a CPF of less than 0.75 will be rejected.

#### 5-04.3(12) Joints

#### 5-04.3(12)A HMA Joints

#### 5-04.3(12)A1 Transverse Joints

The Contractor shall conduct operations such that the placing of the top or wearing course is a continuous operation or as close to continuous as possible. Unscheduled transverse joints will be allowed and the roller may pass over the unprotected end of the freshly laid mixture only when the placement of the course must be discontinued for such a length of time that the mixture will cool below compaction temperature. When the Work is resumed, the previously compacted mixture shall be cut back to produce a slightly beveled edge for the full thickness of the course.

A temporary wedge of HMA constructed on a 20H:1V shall be constructed where a transverse joint as a result of paving or planing is open to traffic. The HMA in the temporary wedge shall be separated from the permanent HMA by strips of heavy wrapping paper or other methods approved by the Engineer. The wrapping paper shall be removed and the joint trimmed to a slightly beveled edge for the full thickness of the course prior to resumption of paving.

The material that is cut away shall be wasted and new mix shall be laid against the cut. Rollers or tamping irons shall be used to seal the joint.

#### <sup>24</sup> 5-04.3(12)A2 Longitudinal Joints

The longitudinal joint in any one course shall be offset from the course immediately below by not more than 6 inches nor less than 2 inches. All longitudinal joints constructed in the wearing course shall be located at a lane line or an edge line of the Traveled Way. A notched wedge joint shall be constructed along all longitudinal joints in the wearing surface of new HMA unless otherwise approved by the Engineer. The notched wedge joint shall have a vertical edge of not less than the maximum aggregate size or more than ½ of the compacted lift thickness and then taper down on a slope not steeper than 4H:1V. The sloped portion of the HMA notched wedge joint shall be uniformly compacted.

5-04.3(12)B Bridge Paving Joint Seals

## 5-04.3(12)B1 HMA Sawcut and Seal

Prior to placing HMA on the bridge deck, establish sawcut alignment points at both ends of the bridge paving joint seals to be placed at the bridge ends, and at interior joints within the bridge deck when and where shown in the Plans. Establish the sawcut alignment points in a manner that they remain functional for use in aligning the sawcut after placing the overlay.

- <sup>42</sup> Submit a Type 1 Working Drawing consisting of the sealant manufacturer's application <sup>43</sup> procedure.
- <sup>45</sup> Construct the bridge paving joint seal as specified ion the Plans and in accordance with the detail shown in the Standard Plans. Construct the sawcut in accordance with the detail shown in the Standard Plan. Construct the sawcut in accordance with Section 5-05.3(8)B and the manufacturer's application procedure.

# 5-04.3(12)B2 Paved Panel Joint Seal

1 2	Construct the paved panel joint seal in accordance with the requirements specified in Section 5.04.2(12)P1 and the following requirement:
3	5-04.3(12)B1 and the following requirement:
4 5	<ol> <li>Clean and seal the existing joint between concrete panels in accordance with Section 5-01.3(8) and the details shown in the Standard Plans.</li> </ol>
6	
7	5-04.3(13) Surface Smoothness
8	The completed surface of all courses shall be of uniform texture, smooth, uniform as to crown and
9	grade, and free from defects of all kinds. The completed surface of the wearing course shall not vary
10 11	more than 1/8 inch from the lower edge of a 10-foot straightedge placed on the surface parallel to the
12	centerline. The transverse slope of the completed surface of the wearing course shall vary not more than ¼ inch in 10 feet from the rate of transverse slope shown in the Plans.
13	
14	When deviations in excess of the above tolerances are found that result from a high place in the HMA,
15	the pavement surface shall be corrected by one of the following methods:
16	4. Demoved of metanicities with allocation with an entropy of animality metabing on
17	1. Removal of material from high places by grinding with an approved grinding machine, or
18	2. Removal and replacement of the wearing course of HMA, or
19	3. By other method approved by the Engineer.
20	
21 22	Correction of defects shall be carried out until there are no deviations anywhere greater than the allowable tolerances.
23	
24	Deviations in excess of the above tolerances that result from a low place in the HMA and deviations
25	resulting from a high place where corrective action, in the opinion of the Engineer, will not produce
26	satisfactory results will be accepted with a price adjustment. The Engineer shall deduct from monies
27	due or that may become due to the Contractor the sum of \$500.00 for each and every section of
28	single traffic lane 100 feet in length in which any excessive deviations described above are found.
29 30	
30	When utility appurtenances such as manhole covers and valve boxes are located in the traveled way, the utility appurtenances shall be adjusted to the finished grade prior to paving. This requirement may
32	be waived when requested by the Contractor, at the discretion of the Engineer or when the adjustment
33	details provided in the project plan or specifications call for utility appurtenance adjustments after the
34	completion of paving.
35	
36	Utility appurtenance adjustment discussions will be included in the Pre-Paving planning (5-
37 38	04.3(14)B3). Submit a written request to waive this requirement to the Engineer prior to the start of
39	paving.
40	5-04.3(14) Planing (Milling) Bituminous Pavement
40	The planing plan must be approved by the Engineer and a pre planing meeting must be held prior to
42	the start of any planing. See Section 5-04.3(14)B2 for information on planing submittals.
43	
44	Existing surfacing to be planed as staked in the field. A tapered grind shall be required at each
45	end of paving. Approximately 30 feet from butt joint and 65 feet from butt joint as stated in
46	the Contract Plans or as directed by the Engineer.
47	
48 49	For mainline planing operations, use equipment with automatic controls and with sensors for either or both sides of equipment. The controls shall be capable of sensing the grade from an outside

or both sides of equipment. The controls shall be capable of sensing the grade from an outside

- reference line, or a mat-referencing device. The automatic controls shall have a transverse slope
   controller capable of maintaining the mandrel at the desired transverse slope (expressed as a percentage) within plus or minus 0.1 percent.
- <sup>5</sup> Where planing an existing pavement is specified in the Contract, the Contractor must remove existing
   <sup>6</sup> surfacing material and to reshape the surface to remove irregularities. The finished product must be
   <sup>7</sup> a prepared surface acceptable for receiving an HMA overlay.
- <sup>9</sup> Use the cold milling method for planing unless otherwise specified in the Contract. Do not use the
   <sup>10</sup> planer on the final wearing course of new HMA.
- <sup>12</sup> Conduct planing operations in a manner that does not tear, break, burn, or otherwise damage the <sup>13</sup> surface which is to remain. The finished planed surface must be slightly grooved or roughened and <sup>14</sup> must be free from gouges, deep grooves, ridges, or other imperfections. The Contractor must repair <sup>15</sup> any damage to the surface by the Contractor's planing equipment, using an Engineer approved <sup>16</sup> method.
- The Contractor where necessary shall plane or grind, and provide any hand work necessary to work
   around utility appurtenances, castings, lids, curbs, gutters, sidewalks, manholes, and catch basins to
   provide smooth transition of pavement to the finished thickness and grade as staked in the field or
   approved by the Engineer.
- Repair or replace any metal castings and other surface improvements damaged by planing, as
   determined by the Engineer.
- A tapered wedge cut must be planed longitudinally along curb lines sufficient to provide a minimum
   of 4 inches of curb reveal after placement and compaction of the final wearing course. The dimensions
   of the wedge must be as shown on the Drawings or as specified by the Engineer.
- 29

33

36

40

45

47

4

8

11

17

22

25

- A tapered wedge cut must also be made at transitions to adjoining pavement surfaces (meet lines)
   where butt joints are shown on the Drawings. Cut butt joints in a straight line with vertical faces 2
   inches or more in height, producing a smooth transition to the existing adjoining pavement.
- <sup>34</sup> After planing is complete, planed surfaces must be swept, cleaned, and if required by the Contract, <sup>35</sup> patched and preleveled.
- The Engineer may direct additional depth planing. Before performing this additional depth planing,
   the Contractor must conduct a hidden metal in pavement detection survey as specified in Section 5 04.3(14)A.
- 41 5-04.3(14)A Pre-Planing Metal Detection Check
- Before starting planing of pavements, and before any additional depth planing required by the
   Engineer, the Contractor must conduct a physical survey of existing pavement to be planed with
   equipment that can identify hidden metal objects.
- <sup>46</sup> Should such metal be identified, promptly notify the Engineer.
- <sup>48</sup> See Section 1-07.16(1) regarding the protection of survey monumentation that may be hidden in <sup>49</sup> pavement.

The Contractor is solely responsible for any damage to equipment resulting from the Contractor's failure to conduct a pre-planing metal detection survey, or from the Contractor's failure to notify the Engineer of any hidden metal that is detected.

#### 5-04.3(14)B Paving and Planing Under Traffic

#### 5-04.3(14)B1 General

In addition the requirements of Section 1-07.23 and the traffic controls required in Section 1-10, and unless the Contract specifies otherwise or the Engineer approves, the Contractor must comply with the following:

- 1. Intersections:
  - a. Keep intersections open to traffic at all times, except when paving or planing operations through an intersection requires closure. Such closure must be kept to the minimum time required to place and compact the HMA mixture, or plane as appropriate. For paving, schedule such closure to individual lanes or portions thereof that allows the traffic volumes and schedule of traffic volumes required in the approved traffic control plan. Schedule work so that adjacent intersections are not impacted at the same time and comply with the traffic control restrictions required by the Traffic Engineer. Each individual intersection closure or partial closure, must be addressed in the traffic control plan, which must be submitted to and accepted by the Engineer, see Section 1-10.2(2).
  - b. When planing or paving and related construction must occur in an intersection, consider scheduling and sequencing such work into quarters of the intersection, or half or more of an intersection with side street detours. Be prepared to sequence the work to individual lanes or portions thereof.
  - c. Should closure of the intersection in its entirety be necessary, and no trolley service is impacted, keep such closure to the minimum time required to place and compact the HMA mixture, plane, remove asphalt, tack coat, and as needed.
  - d. Any work in an intersection requires advance warning in both signage and a number of Working Days advance notice as determined by the Engineer, to alert traffic and emergency services of the intersection closure or partial closure.
  - e. Allow new compacted HMA asphalt to cool to ambient temperature before any traffic is allowed on it. Traffic is not allowed on newly placed asphalt until approval has been obtained from the Engineer.
  - 2. Temporary centerline marking, post-paving temporary marking, temporary stop bars, and maintaining temporary pavement marking must comply with Section 8-23.
  - 3. Permanent pavement marking must comply with Section 8-22.

#### 5-04.3(14)B2 Submittals – Planing Plan and HMA Paving Plan

The Contractor must submit a separate planing plan and a separate paving plan to the Engineer at least 5 Working Days in advance of each operation's activity start date. These plans must show how the moving operation and traffic control are coordinated, as they will be discussed at the pre-planing briefing and pre-paving briefing. When requested by the Engineer, the Contractor must provide each operation's traffic control plan on  $24 \times 36$  inch or larger size Shop Drawings with a scale showing both the area of operation and sufficient detail of traffic beyond the area of operation where detour traffic may be required. The scale on the Shop Drawings is 1 inch = 20 feet, which may be changed if the Engineer agrees sufficient detail is shown.

1 2 3 4	The planing operation and the paving operation include, but are not limited to, metal detection, removal of asphalt and temporary asphalt of any kind, tack coat and drying, staging of supply trucks, paving trains, rolling, scheduling, and as may be discussed at the briefing.		
5 6 7 8 9	When intersections will be partially or totally blocked, provide adequately sized and noticeable signage alerting traffic of closures to come, a minimum 2 Working Days in advance. The traffic control plan must show where police officers will be stationed when signalization is or may be, countermanded, and show areas where flaggers are proposed.		
10 11	At a minimum, the planing and the paving plan must include:		
12 13 14 15 16	<ol> <li>A copy of the accepted traffic control plan, see Section 1-10.2(2), detailing each day's traffic control as it relates to the specific requirements of that day's planing and paving. Briefly describe the sequencing of traffic control consistent with the proposed planing and paving sequence, and scheduling of placement of temporary pavement markings and channelizing devices after each day's planing, and paving.</li> </ol>		
17	2. A copy of each intersection's traffic control plan.		
18 19 20	<ol> <li>Haul routes from Supplier facilities, and locations of temporary parking and staging areas, including return routes. Describe the complete round trip as it relates to the sequencing of paving operations.</li> </ol>		
21	4. Names and locations of HMA Supplier facilities to be used.		
22	5. List of all equipment to be used for paving.		
23 24	<ol> <li>List of personnel and associated job classification assigned to each piece of paving equipment.</li> </ol>		
25 26 27 28 29 30	7. Description (geometric or narrative) of the scheduled sequence of planing and of paving, and intended area of planing and of paving for each day's work, must include the directions of proposed planing and of proposed paving, sequence of adjacent lane paving, sequence of skipped lane paving, intersection planing and paving scheduling and sequencing, and proposed notifications and coordinations to be timely made. The plan must show HMA joints relative to the final pavement marking lane lines.		
31 32	<ol> <li>Names, job titles, and contact information for field, office, and plant supervisory personnel.</li> </ol>		
33	9. A copy of the approved Mix Designs.		
34	10. Tonnage of HMA to be placed each day.		
35	11. Approximate times and days for starting and ending daily operations.		
36			
37	5-04.3(14)B3 Pre-Paving and Pre-Planing Briefing		
38	At least 2 Working Days before the first paving operation and the first planing operation, or as		
39 40	scheduled by the Engineer for future paving and planing operations to ensure the Contractor		
41	has adequately prepared for notifying and coordinating as required in the Contract, the Contractor must be prepared to discuss that day's operations as they relate to other entities		
42	and to public safety and convenience, including driveway and business access, garbage truck		
43	operations, Metro transit operations and working around energized overhead wires, school		
44	and nursing home and hospital and other accesses, other contractors who may be operating		
45 46	in the area, pedestrian and bicycle traffic, and emergency services. The Contractor, and		
46	Subcontractors that may be part of that day's operations, must meet with the Engineer and discuss the proposed operation as it relates to the submitted planing plan and paving plan,		
48	approved traffic control plan, and public convenience and safety. Such discussion includes,		
49	but is not limited to:		
50			

1		1. General for both Paving Plan and for Planing Plan:			
2	a.	The actual times of starting and ending daily operations.			
3 4	b.	In intersections, how to break up the intersection, and address traffic control and signalization for that operation, including use of peace officers.			
5 6 7	С.	The sequencing and scheduling of paving operations and of planing operations, as applicable, as it relates to traffic control, to public convenience and safety, and to other con-tractors who may operate in the Project Site.			
8 9	d.	Notifications required of Contractor activities, and coordinating with other entities and the public as necessary.			
10 11	e.	Description of the sequencing of installation and types of temporary pavement markings as it relates to planning and to paving.			
12 13	f.	Description of the sequencing of installation of, and the removal of, temporary pavement patch material around exposed castings and as may be needed			
14 15 16	g.	Description of procedures and equipment to identify hidden metal in the pavement, such as survey monumentation, monitoring wells, street car rail, and castings, before planning, see Section 5-04.3(14)B2.			
17 18	h.	Description of how flaggers will be coordinated with the planing, paving, and related operations.			
19 20	i.	Description of sequencing of traffic controls for the process of rigid pavement base repairs.			
21	j.	Other items the Engineer deems necessary to address.			
22		2. Paving – additional topics:			
23	a.	When to start applying tack and coordinating with paving.			
24 25 26 27	b.	Types of equipment and numbers of each type equipment to be used. If more pieces of equipment than personnel are proposed, describe the sequencing of the personnel operating the types of equipment. Discuss the continuance of operator personnel for each type equipment as it relates to meeting Specification			
28		requirements.			
29 30 31 32	C.	Number of JMFs to be placed, and if more than one JMF how the Contractor will ensure different JMFs are distinguished, how pavers and MTVs are distinguished if more than one JMF is being placed at the time, and how pavers and MTVs are cleaned so that one JMF does not adversely influence the other JMF.			
33 34	d.	Description of contingency plans for that day's operations such as equipment breakdown, rain out, and Supplier shutdown of operations.			
35 36	e.	Number of sublots to be placed, sequencing of density testing, and other sampling and testing.			
37	5-01 3(15) Seal	ing Pavement Surfaces			
38 39	ι,	where shown in the plans. Construct the fog seal in accordance with Section 5-02.3.			
40 41	Unless otherwise approved by the Engineer, apply the fog seal prior to opening to traffic.				
42	5-04.3(16) HMA	Road Approaches			
43					
44 45	Engineer. The Work shall be performed in accordance with Section 5-04.				
46 47	5-04.4 Measuremen	t			
48 49	"HMA for Prelevel CL. 3/8 In. PG 58H-22 Fiber Reinforced" per Ton.				
50	"HMA CL. 3/8 In. PG 58H-22 Fiber Reinforced" per Ton.				

Pigeon Springs Road HMA Project CRP 2200C

## 5-04.5 Payment

Payment will be made for each of the following Bid items that are included in the Proposal:

"HMA for Prelevel CL. 3/8 In. PG 58H-22 Fiber Reinforced" per Ton.

The unit contract price per ton for "HMA for Prelevel CL. 3/8 In. PG 58H-22 Fiber Reinforced" shall be full compensation for all costs, including paving reinforcing fiber, anti-stripping additive, incurred to carry out the requirements of Section 5-04 except for those costs included in other items which are included in this Subsection and which are included in the Proposal. Finish surface preparation and minor grade adjustments for HMA preparation shall be considered incidental to this bid item.

"HMA Cl. 3/8 In. PG 58H-22 Fiber Reinforced" per Ton.

The unit contract price per ton for "HMA CL. 3/8 In. PG 58H-22 Fiber Reinforced" shall be full compensation for all costs, including paving reinforcing fiber, anti-stripping additive, incurred to carry out the requirements of Section 5-04 except for those costs included in other items which are included in this Subsection and which are included in the Proposal. Finish surface preparation and minor grade adjustments for HMA preparation shall be considered incidental to this bid item.

## 5-04.5(1) Quality Assurance Price Adjustment

In the event that test results indicate the HMA does not meet specifications, a change order will be issued for the price adjustments for Quality of HMA Mixture and Quality of HMA Compaction based upon these specifications.

## 5-04.5(1)B Price Adjustments for Quality of HMA Compaction

The maximum CPF of a compaction lot is 1.00. 

For each compaction lot of HMA when the CPF is less than 1.00, a Nonconforming Compaction Factor (NCCF) will be determined. THE NCCF equals the algebraic difference of CPF minus 1.00 multiplied by 40 percent. The Compaction Price Adjustment will be calculated as the product of the NCCF, the quantity of HMA in the lot in tons and the unit contract price per ton of the mix.

The CPF shall be as follows:

38		
39	Compaction	CPF
40	91.0% to 91.9%	95%
41	90.0% to 90.9%	90%
42	89.0% to 89.9%	80%
43	88.0% to 88.9%	75%
44	At or below 87.9%	Mix is removed

#### POWER EQUIPMENT

(\*\*\*\*\*) 

The successful bidder will be required to furnish the County a list of all equipment that they anticipate utilizing on this project. 

The bidder's attention is directed to the attached Power Equipment Form, which the successful bidder will be required to complete and return with the contract documents. This information will enable hourly rental rates to be computed by the County, utilizing the "Rental Rate Blue Book for Construction 

Equipment". No payment for any force account work will be allowed until this form has been returned

<sup>2</sup> and accepted by the County.

# 4 E-VERIFY

## 5 **(\*\*\*\*\*)**

"Effective June 21st, 2010, all contracts with a value of  $\geq$  \$100,000 shall require that the awarded 6 contractor register with the Department of Homeland Security E-Verify program. Contractors shall have 7 sixty days after the execution of the contract to register and enter into a Memorandum of Understanding 8 (MOU) with the Department of Homeland Security (DHS) E-Verify program. After completing the MOU 9 the contractor shall have an additional sixty days to provide a written record on the authorized 10 employment status of their employees and those of any sub-contractor(s) currently assigned to the 11 contract. Employees hired during the execution of the contract and after submission of the initial 12 verification will be verified to the county within 30 days of hire, as reported from the E-Verify program. 13 The contractor will continue to update the County on all corrective actions required and changes made 14 during the performance of the contract." 15

# 17 BOND

16

18 **(\*\*\*\*\*)** 

<sup>19</sup> The Bidder's special attention is directed to the attached bond form, which the successful bidder will be <sup>20</sup> required to execute and furnish the County. <u>NO OTHER BOND FORMS WILL BE ACCEPTED</u>. The <sup>21</sup> bond shall be for the full amount of the contract

<sup>21</sup> bond shall be for the full amount of the contract.

# 23 LEWIS COUNTY ESTIMATES AND PAYMENT POLICY

24 (\*\*\*\*\*)

Payment cutoff shall be the last day of each month, inclusive of that day. On or before the 5th day of 25 each calendar month during the term of this contract, the Contracting Agency shall prepare monthly 26 Progress Payments for work completed and material furnished. If the Contractor agrees, the 27 Contractor will approve the Progress Payment and return the estimate to the Contracting Agency by the 28 15<sup>th</sup> day of that same calendar month. The Contracting Agency shall prepare a voucher based upon 29 the approved Progress Payment and payment based thereon shall be due the Contractor near the 10<sup>th</sup> 30 day of the next calendar month. Material Supply contracts involving delivery of prefabricated material 31 or stockpile material only (no physical work on Contracting Agency property) may be reimbursed via 32 Contractor generated invoices upon written approval by the Engineer. Reimbursement by invoice shall 33 not be subject to late charges listed on the Contractor's standard invoice form. 34 35 When the Contractor reports the work is completed he/she shall then notify the Contracting Agency. 36 The Contracting Agency shall inspect the work and report any deficiencies to the Contractor. When the 37 Contracting Agency is satisfied the work has been completed in accordance with all plans and 38 specifications, the Contracting Agency shall then accept the work. 39 40 Upon completion of all work described in this Contract, the Contracting Agency shall prepare a Final 41 Progress Payment and Final Contract Voucher for approval by the Contractor and processing for final 42 payment. Release of the Contract Bond will be 60 days following Contracting Agency Final Acceptance 43 of Contract, provided the conditions of Section 1-03.4 and Section1-07.2 of these Special Provisions 44 have been satisfied. 45 46 **APPENDICES** 47 (July 12, 1999) 48

- <sup>49</sup> The following appendices are attached and made a part of this contract:
- 50 51 \*\*\*\*\*\* APPENDIX A:

52

Washington State Prevailing Wage Rates

Pigeon Springs Road HMA Project CRP 2200C

1	Wage Rate Supplement
2	Wage Rate Benefit Code Key
3	
4	APPENDIX B:
5	Bid Proposal Documents
6	
7	APPENDIX C:
8	Contract Documents
9	
10	APPENDIX D:
11	Contract Plans *****
12	

#### (January 9, 2023) Standard Plans

The State of Washington Standard Plans for Road, Bridge and Municipal Construction M21-01, effective September 30, 2022, is made a part of this contract.

The Standard Plans are revised as follows:

<u>A-10.30</u>

RISER RING detail (Including SECTION view and RISER RING DIMENSIONS table): The RISER RING detail is deleted from the plan.

INSTALLATION detail, SECTION A: The "1/4" callout is revised to read "+/- 1/4" (SEE CONTRACT ~ Note: The + 1/4" installation is shown in the Section A view)"

<u>B-90.40</u> Valve Detail – DELETED

<u>C-8</u> DELETED

<u>C-8A</u> DELETED

<u>C-20.42</u>

Plan View (Case 22A-31), callout, was; "BEAM GUARDRAIL ANCHOR TYPE 10 PAY LIMIT" is revised to read; "BEAM GUARDRAIL ANCHOR TYPE 11 PAY LIMIT"

<u>C-23.60</u> DELETED

<u>C-23.70</u>

Sheet 1, Detail A, callout, was – "EIGHT 5/8" x 1/2" (IN) BOLTS W/ HEX NUTS AND WASHERS (SEE NOTE 5)" revised to read: "EIGHT 5/8" x 1-1/2" (IN) BOLTS W/ HEX NUTS AND WASHERS (SEE NOTE 5)".

Sheet 2, ANCHOR RAIL ELEMENT DETAIL and associated Enlarged Detail, 3/4" Diameter hole pattern (8 holes), callout, "3/4" DIAMETER HOLE (TYP.)" is revised to read: "29/32" x 1 1/8" (IN) SLOT (TYP.)"

<u>D-2.04</u> DELETED

<u>D-2.06</u> DELETED

<u>D-2.08</u> DELETED

<u>D-2.32</u> DELETED

D-2.34

Pigeon Springs Road HMA Project CRP 2200C

DELETED
<u>D-2.60</u> DELETED
<u>D-2.62</u> DELETED
<u>D-2.64</u> DELETED
<u>D-2.66</u> DELETED
<u>D-2.68</u> DELETED
<u>D-2.80</u> DELETED
<u>D-2.88</u> DELETED
<u>D-3.15</u> DELETED
<u>D-3.16</u> DELETED
D-3.17

D-3.17 DELETED

## <u>D-3.10</u>

Sheet 1, Typical Section, callout – "FOR WALLS WITH SINGLE SLOPE TRAFFIC BARRIER. USE THE DETAILS ABOVE THE MATCH LINE ON STANDARD PLAN D-3.15" is revised to read; "FOR WALLS WITH SINGLE SLOPE TRAFFIC BARRIER, SEE CONTRACT PLANS" Sheet 1, Typical Section, callout – "FOR WALLS WITH F-SHAPE TRAFFIC BARRIER. USE THE DETAILS ABOVE THE MATCH LINE ON STANDARD PLAN D-3.16" is revised to read; "FOR WALLS WITH F-SHAPE TRAFFIC BARRIER, SEE CONTRACT PLANS"

#### <u>D-3.11</u>

Sheet 1, Typical Section, callout – ""B" BRIDGE APPROACH SLAB (SEE BRIDGE PLANS) OR PERMANENT GEOSYNTHETIC WALL BARRIER ~ SEE STANDARD PLANS D-3.15 OR D-3.16" is revised to read; "B" BRIDGE APPROACH SLAB OR MOMENT SLAB (SEE CONTRACT PLANS)

Sheet 1, Typical Section, callout – "TYPICAL BARRIER ON BRIDGE APPROACH SLAB (SEE BRIDGE PLANS) OR PERMANENT GEOSYNTHETIC WALL BARRIER ~ SEE STANDARD PLANS D-3.15 OR D-3.16" is revised to read; "TYPICAL BARRIER ON BRIDGE APPROACH SLAB OR MOMENT SLAB (SEE CONTRACT PLANS)

## <u>D-10.10</u>

Wall Type 1 may be used if no traffic barrier is attached on top of the wall. Walls with traffic barriers attached on top of the wall are considered non-standard and shall be designed in accordance with the current WSDOT Bridge Design Manual (BDM) and the revisions stated in the 11/3/15 Bridge Design memorandum.

#### <u>D-10.15</u>

Wall Type 2 may be used if no traffic barrier is attached on top of the wall. Walls with traffic barriers attached on top of the wall are considered non-standard and shall be designed in accordance with the current WSDOT BDM and the revisions stated in the 11/3/15 Bridge Design memorandum.

#### <u>D-10.30</u>

Wall Type 5 may be used in all cases.

#### <u>D-10.35</u>

Wall Type 6 may be used in all cases.

#### <u>D-10.40</u>

Wall Type 7 may be used if no traffic barrier is attached on top of the wall. Walls with traffic barriers attached on top of the wall are considered non-standard and shall be designed in accordance with the current WSDOT BDM and the revisions stated in the 11/3/15 Bridge Design memorandum.

#### <u>D-10.45</u>

Wall Type 8 may be used if no traffic barrier is attached on top of the wall. Walls with traffic barriers attached on top of the wall are considered non-standard and shall be designed in accordance with the current WSDOT BDM and the revisions stated in the revisions stated in the 11/3/15 Bridge Design memorandum.

#### <u>D-15.10</u>

STD Plans D-15 series "Traffic Barrier Details for Reinforced Concrete Retaining Walls" are withdrawn. Special designs in accordance with the current WSDOT BDM are required in place of these STD Plans.

#### <u>D-15.20</u>

STD Plans D-15 series "Traffic Barrier Details for Reinforced Concrete Retaining Walls" are withdrawn. Special designs in accordance with the current WSDOT BDM are required in place of these STD Plans.

#### <u>D-15.30</u>

STD Plans D-15 series "Traffic Barrier Details for Reinforced Concrete Retaining Walls" are withdrawn. Special designs in accordance with the current WSDOT BDM are required in place of these STD Plans.

#### <u>F-10.18</u>

Note 2, "Region Traffic engineer approval is needed to install a truck apron lower than 3"." - DELETED

#### <u>J-10.10</u>

Sheet 4 of 6, "Foundation Size Reference Table", PAD WIDTH column, Type 33xD=6' - 3" is revised to read: 7' - 3". Type 342LX / NEMA P44=5' - 10" is revised to read: 6' - 10"

Sheet 5 of 6, Plan View, "FOR EXAMPLE PAD SHOWN HERE:, "first bullet" item, "-SPACE BETWEEN TYPE B MOD. CABINET AND 33x CABINET IS 6" (IN)" IS REVISED TO READ: "SPACE BETWEEN TYPE B MOD. CABINET (BACK OF ALL CHANNEL STEEL) AND 33x CABINET IS 6" (IN) (CHANNEL STEEL ADDS ABOUT 5" (IN)"

#### <u>J-10.16</u>

Key Note 1, Standard Plan J-10.30 revised to Standard Plan J-10.14

#### <u>J-10.17</u>

Key Note 1, Standard Plan J-10.30 revised to Standard Plan J-10.14

#### <u>J-10.18</u>

Key Note 1, Standard Plan J-10.30 revised to Standard Plan J-10.14

<u>J-20.10</u>

Elevation View, horizontal dimension to edge of sidewalk 10" (IN) OR LESS DESIRABLE ~ 18" (IN) MAXIMUM is revised to read: "10" (IN) MAXIMUM"

<u>J-20.26</u>

Add Note 1, "1. One accessible pedestrian pushbutton station per pedestrian pushbutton post."

<u>J-20.16</u>

View A, callout, was – LOCK NIPPLE, is revised to read; CHASE NIPPLE

<u>J-21.10</u>

Sheet 1, Elevation View, Round Concrete Foundation Detail, callout – "ANCHOR BOLTS ~ 3/4" (IN) x 30" (IN) FULL THREAD ~ THREE REQ'D. PER ASSEMBLY" IS REVISED TO READ: "ANCHOR BOLTS ~ 3/4" (IN) x 30" (IN) FULL THREAD ~ FOUR REQ'D. PER ASSEMBLY"

Sheet 1 of 2, Elevation view (Round), add dimension depicting the distance from the top of the foundation to find 2 #4 reinforcing bar shown, to read; 3" CLR.. Delete "(TYP.)" from the 2  $\frac{1}{2}$ " CLR. dimension, depicting the distance from the bottom of the foundation to find 2 # 4 reinf. Bar.

Sheet 1 of 2, Elevation view (Square), add dimension depicting the distance from the top of the foundation to find 1 #4 reinforcing bar shown, to read; 3" CLR. Delete "(TYP.)" from the 2  $\frac{1}{2}$ " CLR. dimension, depicting the distance from the bottom of the foundation to find 1 # 4 reinf. Bar.

Sheet 2 of 2, Elevation view (Round), add dimension depicting the distance from the top of the foundation to find 2 #4 reinforcing bar shown, to read; 3" CLR. Delete "(TYP.)" from the 2  $\frac{1}{2}$ " CLR. dimension, depicting the distance from the bottom of the foundation to find 2 # 4 reinf. Bar.

Sheet 2 of 2, Elevation view (Square), add dimension depicting the distance from the top of the foundation to find 1 #4 reinforcing bar shown, to read; 3" CLR. Delete "(TYP.)" from the 2  $\frac{1}{2}$ " CLR. dimension, depicting the distance from the bottom of the foundation to find 1 # 4 reinf. Bar.

Detail F, callout, "Heavy Hex Clamping Bolt (TYP.) ~ 3/4" (IN) Diam. Torque Clamping Bolts (see Note 3)" is revised to read; "Heavy Hex Clamping Bolt (TYP.) ~ 3/4" (IN) Diam. Torque Clamping Bolts (see Note 1)"

Detail F, callout, "3/4" (IN) x 2' - 6" Anchor Bolt (TYP.) ~ Four Required (See Note 4)" is revised to read; "3/4" (IN) x 2' - 6" Anchor Bolt (TYP.) ~ Three Required (See Note 2)"

<u>J-21.15</u>

Partial View, callout, was – LOCK NIPPLE ~ 1  $\frac{1}{2}$ " DIAM., is revised to read; CHASE NIPPLE ~ 1  $\frac{1}{2}$ " (IN) DIAM.

#### <u>J-21.16</u>

Detail A, callout, was – LOCKNIPPLE, is revised to read; CHASE NIPPLE

#### <u>J-22.15</u>

Ramp Meter Signal Standard, elevation, dimension 4' - 6" is revised to read; 6'-0" (2x) Detail A, callout, was – LOCK NIPPLE ~ 1 ½" DIAM. is revised to read; CHASE NIPPLE ~ 1 ½" (IN) DIAM.

#### <u>J-40.10</u>

Sheet 2 of 2, Detail F, callout, " $12 - 13 \times 1 \frac{1}{2}$ " S.S. PENTA HEAD BOLT AND 12" S. S. FLAT WASHER" is revised to read; " $12 - 13 \times 1 \frac{1}{2}$ " S.S. PENTA HEAD BOLT AND 1/2" (IN) S. S. FLAT WASHER"

#### <u>J-40.36</u>

Note 1, second sentence; "Finish shall be # 2B for backbox and # 4 for the cover." Is revised to read; "Finish shall be # 2B for barrier box and HRAP (Hot Rolled Annealed and Pickled) for the cover.

#### <u>J-40.37</u>

Note 1, second sentence; "Finish shall be # 2B for backbox and # 4 for the cover." Is revised to read; "Finish shall be # 2B for barrier box and HRAP (Hot Rolled Annealed and Pickled) for the cover.

#### <u>J-75.20</u>

Key Notes, note 16, second bullet point, was: "1/2" (IN) x 0.45" (IN) Stainless Steel Bands", add the following to the end of the note: "Alternate: Stainless steel cable with stainless steel ends, nuts, bolts, and washers may be used in place of stainless steel bands and associated hardware."

#### J-75.41 DELETED

<u>J-75.55</u> Notes, Note A1, Revise reference, was – G-90.29, should be – G-90.20.

#### <u>K-80.20</u> DELETED

#### <u>L-5.10</u>

Sheet 2, Typical Elevation, callout - "2' – 0" MIN. LAP SPLICE BETWEEN (mark) A #3 BAR AND WALL REINFORCEMENT ~ TYPICAL" is revised to read: "2' – 0" MIN. LAP SPLICE BETWEEN (MARK) A #4 BAR AND WALL REINFORCEMENT ~ TYPICAL"

Section C, callout; "(mark) A #3" is revised to read: "(mark) A #4", callout - "(mark) B #3" is revised to read: "(mark) B #4", callout - "(mark) C #3 TIE" is revised to read: "(mark) C #4 TIE" Reinforcing Steel Bending Diagram, (mark) B detail, callout – "128 deg." is revised to read: "123 deg.", callout – "51 deg." is revised to read: "57 deg."

The following are the Standard Plan numbers applicable at the time this project was advertised. The date shown with each plan number is the publication approval date shown in the lower righthand corner of that plan. Standard Plans showing different dates shall not be used in this contract.

A-10.10-008/7/07	A-30.35-0010/12/07	A-50.10-018/17/21
A-10.20-0010/5/07	A-40.00-017/6/22	A-50.40-018/17/21
A-10.30-0010/5/07	A-40.10-047/31/19	A-60.10-0312/23/14
A-20.10-008/31/07	A-40.15-008/11/09	A-60.20-0312/23/14
A-30.10-0011/8/07	A-40.20-041/18/17	A-60.30-016/28/18
A-30.30-016/16/11	A-40.50-0212/23/14	A-60.40-008/31/07
B-5.20-039/9/20	B-30.50-032/27/18	B-75.20-038/17/21
B-5.40-021/26/17	B-30.60-009/9/20	B-75.50-023/15/22
B-5.60-021/26/17	B-30.70-042/27/18	B-75.60-00
B-10.20-023/2/18	B-30.80-012/27/18	B-80.20-006/8/06
B-10.40-028/17/21	B-30.90-021/26/17	B-80.40-006/1/06
B-10.70-028/17/21	B-35.20-006/8/06	B-85.10-016/10/08
B-10.70-02	B-35.40-006/8/06	B-85.20-006/1/06
B-15.20-012/7/12 B-15.40-012/7/12	B-35.40-006/8/06 B-40.20-006/1/06	B-85.30-006/1/06
B-15.60-021/26/17	B-40.40-021/26/17	B-85.40-006/8/06
B-20.20-023/16/12	B-45.20-017/11/17	B-85.50-016/10/08
B-20.40-042/27/18	B-45.40-017/21/17	B-90.10-006/8/06
B-20.60-033/15/12	B-50.20-006/1/06	B-90.20-006/8/06
B-25.20-022/27/18	B-55.20-038/17/21	B-90.30-006/8/06
B-25.60-022/27/18	B-60.20-029/9/20	B-90.40-011/26/17
B-30.05-009/9/20	B-60.40-012/27/18	B-90.50-006/8/06
B-30.10-032/27/18	B-65.20-014/26/12	B-95.20-028/17/21
B-30.15-002/27/18	B-65.40-006/1/06	B-95.40-016/28/18
B-30.20-042/27/18	B-70.20-013/15/22	
B-30.30-032/27/18	B-70.60-011/26/17	
B-30.40-032/27/18		
C-19/8/22	C-22.40-099/8/22	
C-1b9/8/22	C-22.45-069/8/22	
C-1d10/31/03	C-23.70-008/22/	
C-2c8/12/19	C.24.10-037/24/2	
C-4f8/12/19	C-24.15-003/15/2	
C-6a9/8/22	C-25.20-078/20/2	
C-79/8/22	C-25.22-068/20/2	C-75.30-038/20/21
C-7a9/8/22	C-25.26-058/20/2	
C-20.10-089/8/22	C-25.30-018/20/2	21 C-80.20-016/11/14
C-20.14-059/8/22	C-25.80-058/12/1	
C-20.15-026/11/14	C-60.10-029/8/22	
C-20.18-049/8/22	C-60.15-008/17/	
C-20.40-099/8/22	C-60.20-019/8/22	
C-20.41-048/22/22	C-60.30-018/17/2	
C-20.42-057/14/15	C-60.40-008/17/	
C-20.43-008/22/22		
C-20.45.039/8/22	C-60.50-008/17/	

Pigeon Springs Road HMA Project CRP 2200C

D-2.36-036/11/14 D-2.46-028/13/21 D-2.84-0011/10/05 D-2.92-014/26/22 D-3.09-005/17/12 D-3.10-015/29/13 D-3.11-036/11/14	D-412/11/98 D-66/19/98 D-10.10-0112/2/08 D-10.15-0112/2/08 D-10.20-018/7/19 D-10.25-018/7/19 D-10.30-007/8/08	D-10.35-007/8/08 D-10.40-0112/2/08 D-10.45-0112/2/08
E-12/21/07 E-25/29/98	E-48/27/03 E-4a8/27/03	
F-10.12-049/24/20 F-10.16-0012/20/06 F-10.18-033/28/22 F-10.40-049/24/20 F-10.42-001/23/07	F-10.62-024/22/14 F-10.64-034/22/14 F-30.10-049/25/20 F-40.12-036/29/16 F-40.14-036/29/16	F-40.15-049/25/20 F-40.16-036/29/16 F-45.10-038/13/21 F-80.10-047/15/16
$\begin{array}{l} G-10.10\mathcal{0}0\mathcal{0}\mathcal{0}9/20/07\\ G-20.10\mathcal{0}0\mathcal{0}\mathcal{0}8/20/21\\ G-22.10\mathcal{0}0\mathcal{0}\mathcal{0}6/28/18\\ G-24.10\mathcal{0}0\mathcal{0}\mathcal{0}7/12\\ G-24.20\mathcal{0}0\mathcal{0}\mathcal{0}6/28/18\\ G-24.30\mathcal{0}0\mathcal{0}\mathcal{0}6/28/18\\ G-24.40\mathcal{0}0\mathcal{0}\mathcal{0}6/28/18\\ G-24.50\mathcal{0}0\mathcal{0}\mathcal{0}6/28/18\\ G-24.60\mathcal{0}0\mathcal{0}\mathcal{0}6/28/18\\ G-25.10\mathcal{0}0\mathcal{0}\mathcal{0}6/28/18\\ G-25.10\mathcal{0}0\mathcal{0}\mathcal{0}6/28/18\\ G-25.10\mathcal{0}0\mathcal{0}\mathcal{0}6/28/18\\ G-25.10\mathcal{0}0\mathcal{0}\mathcal{0}6/28/18\\ G-25.10\mathcal{0}0\mathcal{0}\mathcal{0}6/28/18\\ G-25.10\mathcal{0}0\mathcal{0}\mathcal{0}6/28/18\\ G-25.10\mathcal{0}0\mathcal{0}\mathcal{0}6/28/18\\ G-25.10\mathcal{0}0\mathcal{0}0\mathcal{0}\mathcal{0}6/28/18\\ G-25.10\mathcal{0}0\$	G-26.10-007/31/19 G-30.10-046/23/15 G-50.10-036/28/18 G-90.10-037/11/17 G-90.20-057/11/17 G-90.30-047/11/17 G-95.10-026/28/18 G-95.20-036/28/18 G-95.30-036/28/18	
H-10.10-007/3/08 H-10.15-007/3/08 H-30.10-0010/12/07	H-32.10-009/20/07 H-60.10-017/3/08 H-60.20-017/3/08	H-70.10-028/17/21 H-70.20-028/17/21
I-10.10-018/11/09 I-30.10-023/22/13 I-30.15-023/22/13 I-30.16-017/11/19 I-30.17-016/12/19	I-30.20-009/20/07 I-30.30-026/12/19 I-30.40-026/12/19 I-30.60-026/12/19 I-40.10-009/20/07	I-40.20-009/20/07 I-50.20-027/6/22 I-60.10-016/10/13 I-60.20-016/10/13 I-80.10-027/15/16
J-05.50-008/30/22 J-107/18/97 J-10.10-049/16/20 J-10.12-009/16/20 J-10.14-009/16/20 J-10.15-016/11/14 J-10.16-028/18/21 J-10.17-028/18/21 J-10.20-048/18/21	J-28.10-028/7/19 J-28.22-008/07/07 J-28.24-029/16/20 J-28.26-0112/02/0 J-28.30-036/11/14 J-28.40-026/11/14 J-28.42-016/28/18 J-28.43-016/28/18 J-28.45-037/21/16	J-60.05-017/21/16         J-60.11-005/20/13         J-60.12-005/20/13         J-60.13-006/16/10         J-60.14-017/31/19         J-75.10-027/10/15         J-75.20-017/10/15

Pigeon Springs Road HMA Project CRP 2200C

$\begin{array}{c} J-10.21-028/18/21\\ J-10.22-028/18/21\\ J-10.25-007/11/17\\ J-10.26-008/30/22\\ J-12.15-006/28/18\\ J-12.16-006/28/18\\ J-12.16-006/28/18\\ J-15.10-016/11/14\\ J-15.15-027/10/15\\ J-20.01-008/30/22\\ J-20.10-047/31/19\\ J-20.15-036/30/14\\ J-20.15-036/30/14\\ J-20.16-026/30/14\\ J-20.20-025/20/13\\ J-20.26-017/12/12\\ J-21.10-046/10/13\\ J-21.15-016/10/13\\ J-21.15-016/10/13\\ J-21.20-016/10/13\\ J-21.20-016/10/13\\ J-22.15-027/10/15\\ J-26.10-037/21/16\\ J-26.15-015/17/12\\ J-26.20-016/28/18\\ J-27.10-017/21/16\\ J-27.15-003/15/12\\ J-28.01-008/30/22\\ \end{array}$	$\begin{array}{c} J-28.60-038/27/2\\ J-28.70-048/30/2\\ J-29.10-028/26/2\\ J-29.15-017/21/1\\ J-29.16-027/21/1\\ J-30.10-018/26/2\\ J-40.01-008/30/2\\ J-40.05-007/21/1\\ J-40.05-007/21/1\\ J-40.20-034/28/1\\ J-40.30-044/28/1\\ J-40.30-044/28/1\\ J-40.30-044/28/1\\ J-40.30-044/28/1\\ J-40.35-015/29/1\\ J-40.36-027/21/1\\ J-40.36-027/21/1\\ J-40.38-015/20/1\\ J-40.39-005/20/1\\ J-40.39-005/20/1\\ J-40.39-007/21/1\\ J-50.05-007/21/1\\ J-50.10-017/31/1\\ J-50.12-028/7/19\\ J-50.15-013/22/1\\ J-50.18-008/7/19\\ J-50.19-008/7/19\\ J-50.20-006/3/1\\ \end{array}$	2       J-75.55-008/30/22         2       J-80.05-008/30/22         6       J-80.10-018/18/21         6       J-80.12-008/18/21         2       J-80.15-006/28/18         2       J-81.10-028/18/21         6       J-81.12-009/3/21         6       J-81.12-009/3/21         6       J-84.05-008/30/22         6       J-86.10-006/28/18         6       J-90.20-036/28/18         7       J-90.21-026/28/18         7       J-90.50-006/28/18         3       J-90.50-006/28/18         7       J-90.50-006/28/18         3       J-90.50-006/28/18         3
K-70.20-016/1/16	K-80.32-008/17/21	K-80.35-019/16/20
K-80.10-029/25/20	K-80.34-008/17/21	K-80.37-019/16/20
		L-40.20-026/21/12 L-70.10-015/21/08
L-10.10-026/21/12	L-40.15-016/16/11	L-70.20-015/21/08
M-1.20-049/25/20 M-1.40-039/25/20 M-1.60-039/25/20 M-1.80-036/3/11 M-2.20-037/10/15 M-2.21-007/10/15 M-3.10-049/25/20 M-3.20-048/2/22 M-3.30-049/25/20 M-3.40-049/25/20 M-3.50-039/25/20 M-5.10-039/25/20 M-5.10-039/25/20 M-5.0011/30/07 M-9.50-026/24/14 M-9.60-002/10/09	M-11.10-048/2/22 M-12.10-038/2/22 M-15.10-012/6/07 M-17.10-027/3/08 M-20.10-048/2/22 M-20.20-024/20/15 M-20.30-042/29/16 M-20.40-036/24/14 M-20.50-026/3/11 M-24.20-024/20/15 M-24.40-024/20/15 M-24.60-046/24/14 M-24.65-007/11/17 M-24.66-007/11/17 M-40.10-036/24/14	M-40.20-0010/12/07 M-40.30-017/11/17 M-40.40-009/20/07 M-40.50-009/20/07 M-40.60-009/20/07 M-60.10-016/3/11 M-60.20-038/17/21 M-65.10-038/17/21 M-80.10-016/3/11 M-80.20-006/10/08 M-80.30-006/10/08

Pigeon Springs Road HMA Project CRP 2200C

# **APPENDIX** A

## WASHINGTON STATE PREVAILING WAGE RATES

INCLUDING:

State Wage Rates

Wage Rate Supplements

Wage Rate Benefit Codes

# State of Washington Department of Labor & Industries Prevailing Wage Section - Telephone 360-902-5335 PO Box 44540, Olympia, WA 98504-4540

Washington State Prevailing Wage

The PREVAILING WAGES listed here include both the hourly wage rate and the hourly rate of fringe benefits. On public works projects, worker's wage and benefit rates must add to not less than this total. A brief description of overtime calculation requirements are provided on the Benefit Code Key.

Journey Level Prevailing Wage Rates for the Effective Date: 5/25/2023

<u>County</u>	Trade	<u>Job</u> <u>Classification</u>	<u>Wage</u>	Holiday	Overtime	Note	*Risk Class
Lewis	<u>Asbestos Abatement</u> <u>Workers</u>	Journey Level	\$56.80	<u>5D</u>	<u>1H</u>		<u>View</u>
Lewis	<u>Boilermakers</u>	Journey Level	\$74.29	<u>5N</u>	<u>1C</u>		<u>View</u>
Lewis	Brick Mason	Journey Level	\$66.32	<u>7E</u>	<u>1N</u>		<u>View</u>
Lewis	Brick Mason	Pointer-Caulker-Cleaner	\$66.32	<u>7E</u>	<u>1N</u>		<u>View</u>
Lewis	Building Service Employees	Janitor	\$15.74		<u>1</u>		<u>View</u>
Lewis	Building Service Employees	Shampooer	\$15.74		<u>1</u>		<u>View</u>
Lewis	Building Service Employees	Waxer	\$15.74		<u>1</u>		<u>View</u>
Lewis	Building Service Employees	Window Cleaner	\$15.74		<u>1</u>		<u>View</u>
Lewis	<u>Cabinet Makers (In Shop)</u>	Journey Level	\$23.17		<u>1</u>		<u>View</u>
Lewis	<u>Carpenters</u>	Acoustical Worker	\$71.53	<u>15J</u>	<u>4C</u>		<u>View</u>
Lewis	<u>Carpenters</u>	Bridge, Dock And Wharf Carpenters	\$71.53	<u>15J</u>	<u>4C</u>		<u>View</u>
Lewis	<u>Carpenters</u>	Floor Layer & Floor Finisher	\$71.53	<u>15J</u>	<u>4C</u>		<u>View</u>
Lewis	<u>Carpenters</u>	Journey Level	\$71.53	<u>15J</u>	<u>4C</u>		<u>View</u>
Lewis	<u>Carpenters</u>	Scaffold Erector	\$71.53	<u>15J</u>	<u>4C</u>		<u>View</u>
Lewis	<u>Cement Masons</u>	Application of all Composition Mastic	\$70.09	<u>15J</u>	<u>4U</u>		<u>View</u>
Lewis	<u>Cement Masons</u>	Application of all Epoxy Material	\$69.59	<u>15J</u>	<u>4U</u>		<u>View</u>
Lewis	<u>Cement Masons</u>	Application of all Plastic Material	\$70.09	<u>15J</u>	<u>4U</u>		<u>View</u>
Lewis	<u>Cement Masons</u>	Application of Sealing Compound	\$69.59	<u>15J</u>	<u>4U</u>		<u>View</u>
Lewis	<u>Cement Masons</u>	Application of Underlayment	\$70.09	<u>15J</u>	<u>4U</u>		<u>View</u>
Lewis	<u>Cement Masons</u>	Building General	\$69.59	<u>15J</u>	<u>4U</u>		<u>View</u>
Lewis	<u>Cement Masons</u>	Composition or Kalman Floors	\$70.09	<u>15J</u>	<u>4U</u>		<u>View</u>

Lewis	Cement Masons	Concrete Paving	\$69.59	<u>15J</u>	<u>4U</u>		View
Lewis	Cement Masons	Curb & Gutter Machine	\$70.09	<u>153</u> 15J	<u>4U</u>		View
Lewis	Cement Masons	Curb & Gutter, Sidewalks	\$69.59	<u>15J</u>	<u>4U</u>		View
Lewis	Cement Masons	Curing Concrete	\$69.59	<u>15J</u>	<u>4U</u>		View
Lewis	Cement Masons	Finish Colored Concrete	\$70.09	<u>15J</u>	<u>4U</u>		View
Lewis	Cement Masons	Floor Grinding	\$70.09	<u>15J</u>	<u>4U</u>		View
Lewis	Cement Masons	Floor Grinding/Polisher	\$69.59	<u>15J</u>	<u>4U</u>		View
Lewis	Cement Masons	Green Concrete Saw, self- powered	\$70.09	<u>15J</u>	<u>4U</u>		View
Lewis	Cement Masons	Grouting of all Plates	\$69.59	<u>15J</u>	<u>4U</u>	_	<u>View</u>
Lewis	Cement Masons	Grouting of all Tilt-up Panels	\$69.59	<u>15J</u>	<u>4U</u>		<u>View</u>
Lewis	Cement Masons	Gunite Nozzleman	\$70.09	<u>15J</u>	<u>4U</u>		<u>View</u>
Lewis	Cement Masons	Hand Powered Grinder	\$70.09	<u>15J</u>	<u>4U</u>		<u>View</u>
Lewis	Cement Masons	Journey Level	\$69.59	<u>15J</u>	<u>4U</u>		<u>View</u>
Lewis	Cement Masons	Patching Concrete	\$69.59	<u>15J</u>	<u>4U</u>		<u>View</u>
Lewis	Cement Masons	Pneumatic Power Tools	\$70.09	<u>15J</u>	<u>4U</u>		<u>View</u>
Lewis	Cement Masons	Power Chipping & Brushing	\$70.09	<u>15J</u>	<u>4U</u>		<u>View</u>
Lewis	<u>Cement Masons</u>	Sand Blasting Architectural Finish	\$70.09	<u>15J</u>	<u>4U</u>		<u>View</u>
Lewis	Cement Masons	Screed & Rodding Machine	\$70.09	<u>15J</u>	<u>4U</u>		<u>View</u>
Lewis	<u>Cement Masons</u>	Spackling or Skim Coat Concrete	\$69.59	<u>15J</u>	<u>4U</u>		<u>View</u>
Lewis	<u>Cement Masons</u>	Troweling Machine Operator	\$70.09	<u>15J</u>	<u>4U</u>		<u>View</u>
Lewis	<u>Cement Masons</u>	Troweling Machine Operator on Colored Slabs	\$70.09	<u>15J</u>	<u>4U</u>		<u>View</u>
Lewis	Cement Masons	Tunnel Workers	\$70.09	<u>15J</u>	<u>4U</u>		<u>View</u>
Lewis	Divers & Tenders	Bell/Vehicle or Submersible Operator (Not Under Pressure)	\$126.05	<u>15J</u>	<u>4C</u>		<u>View</u>
Lewis	Divers & Tenders	Dive Supervisor/Master	\$89.94	<u>15J</u>	<u>4C</u>		<u>View</u>
Lewis	Divers & Tenders	Diver	\$126.05	<u>15J</u>	<u>4C</u>	<u>8V</u>	<u>View</u>
Lewis	Divers & Tenders	Diver On Standby	\$84.94	<u>15J</u>	<u>4C</u>		<u>View</u>
Lewis	Divers & Tenders	Diver Tender	\$77.16	<u>15J</u>	<u>4C</u>		<u>View</u>
Lewis	Divers & Tenders	Hyperbaric Worker - Compressed Air Worker 0- 30.00 PSI	\$89.09	<u>15J</u>	<u>4C</u>		<u>View</u>
Lewis	Divers & Tenders	Hyperbaric Worker - Compressed Air Worker 30.01 - 44.00 PSI	\$94.09	<u>15J</u>	<u>4C</u>		<u>View</u>
Lewis	Divers & Tenders	Hyperbaric Worker - Compressed Air Worker 44.01 - 54.00 PSI	\$107.09	<u>15J</u>	<u>4C</u>		<u>View</u>
Lewis	Divers & Tenders	Hyperbaric Worker - Compressed Air Worker 54.01 - 60.00 PSI	\$103.09	<u>15J</u>	<u>4C</u>		<u>View</u>
Lewis	Divers & Tenders	Hyperbaric Worker - Compressed Air Worker 60.01 - 64.00 PSI	\$105.59	<u>15J</u>	<u>4C</u>		<u>View</u>

Lewis	Divers & Tenders	Hyperbaric Worker - Compressed Air Worker 64.01 - 68.00 PSI	\$110.59	<u>15J</u>	<u>4C</u>		<u>View</u>
Lewis	Divers & Tenders	Hyperbaric Worker - Compressed Air Worker 68.01 - 70.00 PSI	\$112.59	<u>15J</u>	<u>4C</u>		<u>View</u>
Lewis	Divers & Tenders	Hyperbaric Worker - Compressed Air Worker 70.01 - 72.00 PSI	\$114.59	<u>15J</u>	<u>4C</u>		<u>View</u>
Lewis	Divers & Tenders	Hyperbaric Worker - Compressed Air Worker 72.01 - 74.00 PSI	\$116.59	<u>15J</u>	<u>4C</u>		<u>View</u>
Lewis	Divers & Tenders	Manifold Operator	\$77.16	<u>15J</u>	<u>4C</u>		<u>View</u>
Lewis	Divers & Tenders	Manifold Operator Mixed Gas	\$82.16	<u>15J</u>	<u>4C</u>		<u>View</u>
Lewis	Divers & Tenders	Remote Operated Vehicle Operator/Technician	\$77.16	<u>15J</u>	<u>4C</u>		<u>View</u>
Lewis	Divers & Tenders	Remote Operated Vehicle Tender	\$71.98	<u>15J</u>	<u>4C</u>		<u>View</u>
Lewis	Dredge Workers	Assistant Engineer	\$76.56	<u>5D</u>	<u>3F</u>		<u>View</u>
Lewis	Dredge Workers	Assistant Mate (Deckhand)	\$75.97	<u>5D</u>	<u>3F</u>		<u>View</u>
Lewis	Dredge Workers	Boatmen	\$76.56	<u>5D</u>	<u>3F</u>		<u>View</u>
Lewis	Dredge Workers	Engineer Welder	\$78.03	<u>5D</u>	<u>3F</u>		<u>View</u>
Lewis	Dredge Workers	Leverman, Hydraulic	\$79.59	<u>5D</u>	<u>3F</u>		<u>View</u>
Lewis	Dredge Workers	Mates	\$76.56	<u>5D</u>	<u>3F</u>		<u>View</u>
Lewis	Dredge Workers	Oiler	\$75.97	<u>5D</u>	<u>3F</u>		<u>View</u>
Lewis	Drywall Applicator	Journey Level	\$71.53	<u>15J</u>	<u>4C</u>		<u>View</u>
Lewis	<u>Drywall Tapers</u>	Journey Level	\$70.61	<u>5P</u>	<u>1E</u>		<u>View</u>
Lewis	<u>Electrical Fixture</u> <u>Maintenance Workers</u>	Journey Level	\$15.74		<u>1</u>		<u>View</u>
Lewis	<u>Electricians - Inside</u>	Cable Splicer	\$86.25	<u>5C</u>	<u>1G</u>		<u>View</u>
Lewis	<u>Electricians - Inside</u>	Journey Level	\$80.57	<u>5C</u>	<u>1G</u>		<u>View</u>
Lewis	<u>Electricians - Inside</u>	Lead Covered Cable Splicer	\$91.94	<u>5C</u>	<u>1G</u>		<u>View</u>
Lewis	<u>Electricians - Inside</u>	Welder	\$86.25	<u>5C</u>	<u>1G</u>		<u>View</u>
Lewis	Electricians - Motor Shop	Craftsman	\$15.74		<u>1</u>		<u>View</u>
Lewis	Electricians - Motor Shop	Journey Level	\$15.74		<u>1</u>		<u>View</u>
Lewis	Electricians - Powerline Construction	Cable Splicer	\$93.00	<u>5A</u>	<u>4D</u>		<u>View</u>
Lewis	Electricians - Powerline Construction	Certified Line Welder	\$85.42	<u>5A</u>	<u>4D</u>		<u>View</u>
Lewis	<u>Electricians - Powerline</u> <u>Construction</u>	Groundperson	\$55.27	<u>5A</u>	<u>4D</u>		<u>View</u>
Lewis	<u>Electricians - Powerline</u> <u>Construction</u>	Heavy Line Equipment Operator	\$85.42	<u>5A</u>	<u>4D</u>		<u>View</u>
Lewis	<u>Electricians - Powerline</u> <u>Construction</u>	Journey Level Lineperson	\$85.42	<u>5A</u>	<u>4D</u>		<u>View</u>
Lewis	<u>Electricians - Powerline</u> <u>Construction</u>	Line Equipment Operator	\$73.35	<u>5A</u>	<u>4D</u>		<u>View</u>
Lewis	Electricians - Powerline Construction	Meter Installer	\$55.27	<u>5A</u>	<u>4D</u>	<u>8W</u>	<u>View</u>

Lewis	Electricians - Powerline Construction	Pole Sprayer	\$85.42	<u>5A</u>	<u>4D</u>		<u>View</u>
Lewis	<u>Electricians - Powerline</u> <u>Construction</u>	Powderperson	\$63.50	<u>5A</u>	<u>4D</u>		<u>View</u>
Lewis	<u>Electronic Technicians</u>	Journey Level	\$51.14	<u>6Z</u>	<u>1B</u>		View
Lewis	Elevator Constructors	Mechanic	\$107.49	<u>7D</u>	<u>4A</u>		View
Lewis	Elevator Constructors	Mechanic In Charge	\$116.13	<u>7D</u>	<u>4A</u>		<u>View</u>
Lewis	Fabricated Precast Concrete Products	Journey Level	\$15.74		<u>1</u>		<u>View</u>
Lewis	Fabricated Precast Concrete Products	Journey Level - In-Factory Work Only	\$15.74		<u>1</u>		<u>View</u>
Lewis	Fence Erectors	Fence Erector	\$48.14	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	Fence Erectors	Fence Laborer	\$48.14	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	<u>Flaggers</u>	Journey Level	\$48.14	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	<u>Glaziers</u>	Journey Level	\$75.91	<u>7L</u>	<u>1Y</u>		<u>View</u>
Lewis	Heat & Frost Insulators And Asbestos Workers	Journey Level	\$84.84	<u>15H</u>	<u>11C</u>		<u>View</u>
Lewis	<u>Heating Equipment</u> <u>Mechanics</u>	Journey Level	\$94.11	<u>7F</u>	<u>1E</u>		<u>View</u>
Lewis	Hod Carriers & Mason Tenders	Journey Level	\$59.85	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	Industrial Power Vacuum Cleaner	Journey Level	\$15.74		1		<u>View</u>
Lewis	Inland Boatmen	Boat Operator	\$61.41	<u>5B</u>	<u>1K</u>		<u>View</u>
Lewis	Inland Boatmen	Cook	\$56.48	<u>5B</u>	<u>1K</u>		<u>View</u>
Lewis	Inland Boatmen	Deckhand	\$57.48	<u>5B</u>	<u>1K</u>		<u>View</u>
Lewis	Inland Boatmen	Deckhand Engineer	\$58.81	<u>5B</u>	<u>1K</u>		<u>View</u>
Lewis	Inland Boatmen	Launch Operator	\$58.89	<u>5B</u>	<u>1K</u>		<u>View</u>
Lewis	Inland Boatmen	Mate	\$57.31	<u>5B</u>	<u>1K</u>		<u>View</u>
Lewis	Inspection/Cleaning/Sealing Of Sewer & Water Systems By Remote Control	Cleaner Operator, Foamer Operator	\$15.74		<u>1</u>		<u>View</u>
Lewis	Inspection/Cleaning/Sealing Of Sewer & Water Systems By Remote Control	Grout Truck Operator	\$15.74		1		<u>View</u>
Lewis	Inspection/Cleaning/Sealing Of Sewer & Water Systems By Remote Control	Head Operator	\$15.74		1		<u>View</u>
Lewis	Inspection/Cleaning/Sealing Of Sewer & Water Systems By Remote Control	Technician	\$15.74		1		<u>View</u>
Lewis	Inspection/Cleaning/Sealing Of Sewer & Water Systems By Remote Control	Tv Truck Operator	\$15.74		1		<u>View</u>
Lewis	Insulation Applicators	Journey Level	\$71.53	<u>15J</u>	<u>4C</u>		<u>View</u>
Lewis	Ironworkers	Journeyman	\$83.79	<u>15K</u>	<u>11N</u>		<u>View</u>
Lewis	Laborers	Air, Gas Or Electric Vibrating Screed	\$56.80	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	Laborers	Airtrac Drill Operator	\$58.56	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	Laborers	Ballast Regular Machine	\$56.80	<u>15J</u>	<u>4V</u>	<u>8Y</u>	View
Lewis	Laborers	Batch Weighman	\$48.14	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>

Lewis	Laborers	Brick Pavers	\$56.80	<u>15J</u>	<u>4V</u>	<u>8Y</u>	View
Lewis	Laborers	Brush Cutter	\$56.80	<u>15J</u>	<u>4V</u>	<u>8Y</u>	View
Lewis	<u>Laborers</u>	Brush Hog Feeder	\$56.80	<u>15J</u>	<u>4V</u>	<u>8Y</u>	View
Lewis	Laborers	Burner	\$56.80	<u>15J</u>	<u>4V</u>	<u>8Y</u>	View
Lewis	Laborers	Caisson Worker	\$58.56	<u>15J</u>	<u>4V</u>	<u>8Y</u>	View
Lewis	Laborers	Carpenter Tender	\$56.80	<u>15J</u>	<u>4V</u>	<u>8Y</u>	View
Lewis	Laborers	Cement Dumper-paving	\$57.84	<u>15J</u>	<u>4V</u>	<u>8Y</u>	View
Lewis	Laborers	Cement Finisher Tender	\$56.80	<u>15J</u>	<u>4V</u>	<u>8Y</u>	View
Lewis	Laborers	Change House Or Dry Shack	\$56.80	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	Laborers	Chipping Gun (30 Lbs. And Over)	\$57.84	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	<u>Laborers</u>	Chipping Gun (Under 30 Lbs.)	\$56.80	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	Laborers	Choker Setter	\$56.80	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	Laborers	Chuck Tender	\$56.80	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	Laborers	Clary Power Spreader	\$57.84	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	Laborers	Clean-up Laborer	\$56.80	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	<u>Laborers</u>	Concrete Dumper/Chute Operator	\$57.84	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	Laborers	Concrete Form Stripper	\$56.80	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	Laborers	Concrete Placement Crew	\$57.84	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	Laborers	Concrete Saw Operator/Core Driller	\$57.84	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	Laborers	Crusher Feeder	\$48.14	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	Laborers	Curing Laborer	\$56.80	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	Laborers	Demolition: Wrecking & Moving (Incl. Charred Material)	\$56.80	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	Laborers	Ditch Digger	\$56.80	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	Laborers	Diver	\$58.56	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	<u>Laborers</u>	Drill Operator (Hydraulic, Diamond)	\$57.84	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	Laborers	Dry Stack Walls	\$56.80	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	Laborers	Dump Person	\$56.80	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	Laborers	Epoxy Technician	\$56.80	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	Laborers	Erosion Control Worker	\$56.80	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	Laborers	Faller & Bucker Chain Saw	\$57.84	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	Laborers	Fine Graders	\$56.80	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	Laborers	Firewatch	\$48.14	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	Laborers	Form Setter	\$57.84	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	Laborers	Gabian Basket Builders	\$56.80	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	Laborers	General Laborer	\$56.80	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	<u>Laborers</u>	Grade Checker & Transit Person	\$59.85	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	Laborers	Grinders	\$56.80	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	Laborers	Grout Machine Tender	\$56.80	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	<u>Laborers</u>	Groutmen (Pressure) Including Post Tension	\$57.84	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>

		Beams					
Lewis	Laborers	Guardrail Erector	\$56.80	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	<u>Laborers</u>	Hazardous Waste Worker (Level A)	\$58.56	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	<u>Laborers</u>	Hazardous Waste Worker (Level B)	\$57.84	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	Laborers	Hazardous Waste Worker (Level C)	\$56.80	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	Laborers	High Scaler	\$58.56	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	Laborers	Jackhammer	\$57.84	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	Laborers	Laserbeam Operator	\$57.84	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	Laborers	Maintenance Person	\$56.80	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	Laborers	Manhole Builder-Mudman	\$57.84	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	Laborers	Material Yard Person	\$56.80	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	Laborers	Mold Abatement Worker	\$56.80	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	<u>Laborers</u>	Motorman-Dinky Locomotive	\$59.95	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	<u>Laborers</u>	nozzleman (concrete pump, green cutter when using combination of high pressure air & water on concrete & rock, sandblast, gunite, shotcrete, water blaster, vacuum blaster)	\$59.85	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	Laborers	Pavement Breaker	\$57.84	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	Laborers	Pilot Car	\$48.14	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	Laborers	Pipe Layer (Lead)	\$59.85	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	Laborers	Pipe Layer/Tailor	\$57.84	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	Laborers	Pipe Pot Tender	\$57.84	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	Laborers	Pipe Reliner	\$57.84	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	Laborers	Pipe Wrapper	\$57.84	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	Laborers	Pot Tender	\$56.80	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	Laborers	Powderman	\$58.56	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	Laborers	Powderman's Helper	\$56.80	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	Laborers	Power Jacks	\$57.84	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	<u>Laborers</u>	Railroad Spike Puller - Power	\$57.84	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	Laborers	Raker - Asphalt	\$59.85	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	Laborers	Re-timberman	\$58.56	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	Laborers	Remote Equipment Operator	\$57.84	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	Laborers	Rigger/Signal Person	\$57.84	<u>15J</u>	<u>4V</u>	<u>8Y</u>	View
Lewis	Laborers	Rip Rap Person	\$56.80	<u>15J</u>	<u>4V</u>	<u>8Y</u>	View
Lewis	Laborers	Rivet Buster	\$57.84	<u>15J</u>	<u>4V</u>	<u>8Y</u>	View
Lewis	Laborers	Rodder	\$57.84	<u>15J</u>	<u>4V</u>	<u>8Y</u>	View
Lewis	Laborers	Scaffold Erector	\$56.80	<u>15J</u>	<u>4V</u>	<u>8Y</u>	View
Lewis	Laborers	Scale Person	\$56.80	<u>15J</u>	<u>4V</u>	<u>8Y</u>	View
Lewis	Laborers	Sloper (Over 20")	\$57.84	<u>15J</u>	<u>4V</u>	<u>8Y</u>	View
Lewis	<u>Laborers</u>	Sloper Sprayer	\$56.80	<u>15J</u>	<u>4V</u>	<u>8Y</u>	View

Lewis	Laborers	Spreader (Concrete)	\$57.84	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	Laborers	Stake Hopper	\$56.80	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	Laborers	Stock Piler	\$56.80	<u>15J</u>	<u>4V</u>	<u>8Y</u>	View
Lewis	Laborers	Swinging Stage/Boatswain Chair	\$48.14	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	Laborers	Tamper & Similar Electric, Air & Gas Operated Tools	\$57.84	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	Laborers	Tamper (Multiple & Self- propelled)	\$57.84	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	Laborers	Timber Person - Sewer (Lagger, Shorer & Cribber)	\$57.84	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	Laborers	Toolroom Person (at Jobsite)	\$56.80	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	Laborers	Topper	\$56.80	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	Laborers	Track Laborer	\$56.80	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	Laborers	Track Liner (Power)	\$57.84	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	Laborers	Traffic Control Laborer	\$51.48	<u>15J</u>	<u>4V</u>	<u>9C</u>	<u>View</u>
Lewis	Laborers	Traffic Control Supervisor	\$54.55	<u>15J</u>	<u>4V</u>	<u>9C</u>	View
Lewis	Laborers	Truck Spotter	\$56.80	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	Laborers	Tugger Operator	\$57.84	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	Laborers	Tunnel Work-Compressed Air Worker 0-30 psi	\$158.87	<u>15J</u>	<u>4V</u>	<u>9B</u>	<u>View</u>
Lewis	Laborers	Tunnel Work-Compressed Air Worker 30.01-44.00 psi	\$163.90	<u>15J</u>	<u>4V</u>	<u>9B</u>	<u>View</u>
Lewis	<u>Laborers</u>	Tunnel Work-Compressed Air Worker 44.01-54.00 psi	\$167.58	<u>15J</u>	<u>4V</u>	<u>9B</u>	<u>View</u>
Lewis	<u>Laborers</u>	Tunnel Work-Compressed Air Worker 54.01-60.00 psi	\$173.28	<u>15J</u>	<u>4V</u>	<u>9B</u>	<u>View</u>
Lewis	<u>Laborers</u>	Tunnel Work-Compressed Air Worker 60.01-64.00 psi	\$175.40	<u>15J</u>	<u>4V</u>	<u>9B</u>	<u>View</u>
Lewis	<u>Laborers</u>	Tunnel Work-Compressed Air Worker 64.01-68.00 psi	\$180.50	<u>15J</u>	<u>4V</u>	<u>9B</u>	<u>View</u>
Lewis	<u>Laborers</u>	Tunnel Work-Compressed Air Worker 68.01-70.00 psi	\$182.40	<u>15J</u>	<u>4V</u>	<u>9B</u>	<u>View</u>
Lewis	<u>Laborers</u>	Tunnel Work-Compressed Air Worker 70.01-72.00 psi	\$184.40	<u>15J</u>	<u>4V</u>	<u>9B</u>	<u>View</u>
Lewis	<u>Laborers</u>	Tunnel Work-Compressed Air Worker 72.01-74.00 psi	\$186.40	<u>15J</u>	<u>4V</u>	<u>9B</u>	<u>View</u>
Lewis	<u>Laborers</u>	Tunnel Work-Guage and Lock Tender	\$59.95	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	Laborers	Tunnel Work-Miner	\$59.95	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	Laborers	Vibrator	\$57.84	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	Laborers	Vinyl Seamer	\$56.80	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	Laborers	Watchman	\$43.76	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	Laborers	Welder	\$57.84	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	Laborers	Well Point Laborer	\$57.84	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	Laborers	Window Washer/Cleaner	\$43.76	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	Laborers - Underground Sewer & Water	General Laborer & Topman	\$56.80	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>

Lewis	<u>Laborers - Underground</u> <u>Sewer &amp; Water</u>	Pipe Layer	\$57.84	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	Landscape Construction	Landscape Construction/Landscaping Or Planting Laborers	\$43.76	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	Landscape Construction	Landscape Operator	\$74.83	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Landscape Maintenance	Groundskeeper	\$15.74		<u>1</u>		<u>View</u>
Lewis	Lathers	Journey Level	\$71.53	<u>15J</u>	<u>4C</u>		<u>View</u>
Lewis	<u>Marble Setters</u>	Journey Level	\$66.32	<u>7E</u>	<u>1N</u>		<u>View</u>
Lewis	<u>Metal Fabrication (In Shop)</u>	Fitter	\$15.74		<u>1</u>		<u>View</u>
Lewis	<u>Metal Fabrication (In Shop)</u>	Laborer	\$15.74		<u>1</u>		<u>View</u>
Lewis	<u>Metal Fabrication (In Shop)</u>	Machine Operator	\$15.74		<u>1</u>		<u>View</u>
Lewis	<u>Metal Fabrication (In Shop)</u>	Painter	\$15.74		<u>1</u>		<u>View</u>
Lewis	Metal Fabrication (In Shop)	Welder	\$15.74		<u>1</u>		<u>View</u>
Lewis	<u>Millwright</u>	Journey Level	\$73.08	<u>15J</u>	<u>4C</u>		<u>View</u>
Lewis	<u>Modular Buildings</u>	Cabinet Assembly	\$15.74		<u>1</u>		<u>View</u>
Lewis	<u>Modular Buildings</u>	Electrician	\$15.74		<u>1</u>		<u>View</u>
Lewis	<u>Modular Buildings</u>	Equipment Maintenance	\$15.74		<u>1</u>		<u>View</u>
Lewis	<u>Modular Buildings</u>	Plumber	\$15.74		<u>1</u>		<u>View</u>
Lewis	<u>Modular Buildings</u>	Production Worker	\$15.74		<u>1</u>		<u>View</u>
Lewis	<u>Modular Buildings</u>	Tool Maintenance	\$15.74		<u>1</u>		<u>View</u>
Lewis	<u>Modular Buildings</u>	Utility Person	\$15.74		<u>1</u>		<u>View</u>
Lewis	<u>Modular Buildings</u>	Welder	\$15.74		<u>1</u>		<u>View</u>
Lewis	Painters	Journey Level	\$49.46	<u>6Z</u>	<u>11J</u>		<u>View</u>
Lewis	<u>Pile Driver</u>	Crew Tender	\$77.16	<u>15J</u>	<u>4C</u>		<u>View</u>
Lewis	<u>Pile Driver</u>	Journey Level	\$71.98	<u>15J</u>	<u>4C</u>		<u>View</u>
Lewis	<u>Plasterers</u>	Journey Level	\$67.49	<u>7Q</u>	<u>1R</u>		<u>View</u>
Lewis	<u>Plasterers</u>	Nozzleman	\$71.49	<u>7Q</u>	<u>1R</u>		<u>View</u>
Lewis	<u>Playground &amp; Park</u> Equipment Installers	Journey Level	\$15.74		<u>1</u>		<u>View</u>
Lewis	Plumbers & Pipefitters	Journey Level	\$84.72	<u>5A</u>	<u>1G</u>		<u>View</u>
Lewis	Power Equipment Operators	Asphalt Plant Operator	\$76.08	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Assistant Engineer	\$72.22	<u>7A</u>	<u>11H</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Barrier Machine (zipper)	\$75.41	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Batch Plant Operator: Concrete	\$75.41	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Bobcat	\$71.57	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Brokk - Remote Demolition Equipment	\$71.57	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Brooms	\$71.57	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Bump Cutter	\$75.41	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Cableways	\$76.08	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Chipper	\$75.41	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Compressor	\$71.57	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Concrete Pump: Truck Mount With Boom Attachment Over 42m	\$76.08	<u>15J</u>	<u>3K</u>	<u>8X</u>	View

Lewis	Power Equipment Operators	Concrete Finish Machine - laser Screed	\$71.57	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Concrete Pump - Mounted Or Trailer High Pressure Line Pump, Pump High Pressure	\$74.83	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Concrete Pump: Truck Mount With Boom Attachment Up To 42m	\$75.41	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Conveyors	\$74.83	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Cranes Friction: 200 tons and over	\$79.13	<u>7A</u>	<u>11H</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Cranes, A-frame: 10 tons and under	\$72.22	<u>7A</u>	<u>11H</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Cranes: 100 tons through 199 tons, or 150' of boom (including jib with attachments)	\$77.56	<u>7A</u>	<u>11H</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Cranes: 20 tons through 44 tons with attachments	\$76.11	<u>7A</u>	<u>11H</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Cranes: 200 tons- 299 tons, or 250' of boom including jib with attachments	\$78.36	<u>7A</u>	<u>11H</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Cranes: 300 tons and over or 300' of boom including jib with attachments	\$79.13	<u>7A</u>	<u>11H</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Cranes: 45 tons through 99 tons, under 150' of boom(including jib with attachments)	\$76.79	<u>7A</u>	<u>11H</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Cranes: Friction cranes through 199 tons	\$78.36	<u>7A</u>	<u>11H</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Cranes: through 19 tons with attachments, A- frame over 10 tons	\$75.53	<u>7A</u>	<u>11H</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Crusher	\$75.41	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Deck Engineer/deck Winches (power)	\$75.41	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Derricks: on building work	\$76.79	<u>7A</u>	<u>11H</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Dozers D-9 & Under	\$74.83	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Drill Oilers: Auger Type, Truck Or Crane Mount	\$74.83	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Drilling Machine	\$76.85	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Elevator and man-lift: permanent and shaft type	\$72.22	<u>7A</u>	<u>11H</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Finishing Machine, Bidwell And Gamaco & Similar Equipment	\$75.41	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Forklift: 3000 lbs and over with attachments	\$75.53	<u>7A</u>	<u>11H</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Forklifts: under 3000 lbs. with attachments	\$72.22	<u>7A</u>	<u>11H</u>	<u>8X</u>	<u>View</u>

Lewis	Power Equipment Operators	Grade Engineer: Using Blueprints, Cut Sheets,etc.	\$75.41	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Gradechecker/stakeman	\$71.57	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Guardrail punch/Auger	\$75.41	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Hard Tail End Dump Articulating Off- Road Equipment 45 Yards. & Over	\$76.08	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Hard Tail End Dump Articulating Off-road Equipment Under 45 Yards	\$75.41	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Horizontal/directional Drill Locator	\$74.83	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Horizontal/directional Drill Operator	\$75.41	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Hydralifts/boom trucks: 10 tons and under	\$72.22	<u>7A</u>	<u>11H</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Hydralifts/boom trucks: over 10 tons	\$75.53	<u>7A</u>	<u>11H</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Loader, Overhead 8 Yards. & Over	\$76.85	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Loader, Overhead, 6 Yards. But Not Including 8 Yards	\$76.08	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Loaders, Overhead Under 6 Yards	\$75.41	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Loaders, Plant Feed	\$75.41	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Loaders: Elevating Type Belt	\$74.83	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Locomotives, All	\$75.41	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Material Transfer Device	\$75.41	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Mechanics: all (Leadmen - \$0.50 per hour over mechanic)	\$77.56	<u>7A</u>	<u>11H</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Motor patrol graders	\$76.08	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Mucking Machine, Mole, Tunnel Drill, Boring, Road Header And/or Shield	\$76.08	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Oil Distributors, Blower Distribution & Mulch Seeding Operator	\$71.57	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Outside Hoists (elevators and manlifts), Air Tuggers, Strato	\$75.53	<u>7A</u>	<u>11H</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Overhead, bridge type Crane: 20 tons through 44 tons	\$76.11	<u>7A</u>	<u>11H</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Overhead, bridge type: 100 tons and over	\$77.56	<u>7A</u>	<u>11H</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Overhead, bridge type: 45 tons through 99 tons	\$76.79	<u>7A</u>	<u>11H</u>	<u>8X</u>	<u>View</u>
		Pavement Breaker	\$71.57				

Lewis	Power Equipment Operators	Pile Driver (other Than	\$75.41	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
		Crane Mount)					
Lewis	Power Equipment Operators	Plant Oiler - Asphalt, Crusher	\$74.83	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Posthole Digger, Mechanical	\$71.57	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Power Plant	\$71.57	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Pumps - Water	\$71.57	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Quad 9, HD 41, D10 And Over	\$76.08	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Quick Tower: no cab, under 100 feet in height based to boom	\$72.22	<u>7A</u>	<u>11H</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Remote Control Operator On Rubber Tired Earth Moving Equipment	\$76.08	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Rigger and Bellman	\$72.22	<u>7A</u>	<u>11H</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Rigger/Signal Person, Bellman(Certified)	\$75.53	<u>7A</u>	<u>11H</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Rollagon	\$76.08	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Roller, Other Than Plant Mix	\$71.57	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Roller, Plant Mix Or Multi- lift Materials	\$74.83	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Roto-mill, Roto-grinder	\$75.41	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Saws - Concrete	\$74.83	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Scraper, Self Propelled Under 45 Yards	\$75.41	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Scrapers - Concrete & Carry All	\$74.83	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Scrapers, Self-propelled: 45 Yards And Over	\$76.08	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Service Engineers: equipment	\$75.53	<u>7A</u>	<u>11H</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Shotcrete/gunite Equipment	\$71.57	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Shovel, Excavator, Backhoe, Tractors Under 15 Metric Tons	\$74.83	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Shovel, Excavator, Backhoe: Over 30 Metric Tons To 50 Metric Tons	\$76.08	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Shovel, Excavator, Backhoes, Tractors: 15 To 30 Metric Tons	\$75.41	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Shovel, Excavator, Backhoes: Over 50 Metric Tons To 90 Metric Tons	\$76.85	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Shovel, Excavator, Backhoes: Over 90 Metric Tons	\$77.63	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Slipform Pavers	\$76.08	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>

Lewis	Power Equipment Operators	Spreader, Topsider & Screedman	\$76.08	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Subgrader Trimmer	\$75.41	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Tower Bucket Elevators	\$74.83	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Tower Crane: over 175' through 250' in height, base to boom	\$78.36	<u>7A</u>	<u>11H</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Tower crane: up to 175' in height base to boom	\$77.56	<u>7A</u>	<u>11H</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Tower Cranes: over 250' in height from base to boom.	\$79.13	<u>7A</u>	<u>11H</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Transporters, All Track Or Truck Type	\$76.08	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Trenching Machines	\$74.83	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Truck Crane Oiler/Driver: 100 tons and over	\$76.11	<u>7A</u>	<u>11H</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Truck crane oiler/driver: under 100 tons	\$75.53	<u>7A</u>	<u>11H</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Truck Mount Portable Conveyor	\$75.41	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Vac Truck (Vactor Guzzler, Hydro Excavator)	\$75.41	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Welder	\$76.79	<u>7A</u>	<u>11H</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Wheel Tractors, Farmall Type	\$71.57	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators	Yo Yo Pay Dozer	\$75.41	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	<u>Power Equipment</u> <u>Operators- Underground</u> <u>Sewer &amp; Water</u>	Asphalt Plant Operator	\$76.08	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators- Underground Sewer & Water	Assistant Engineer	\$72.22	<u>7A</u>	<u>11H</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators- Underground Sewer & Water	Barrier Machine (zipper)	\$75.41	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators- Underground Sewer & Water	Batch Plant Operator: Concrete	\$75.41	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators- Underground Sewer & Water	Bobcat	\$71.57	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators- Underground Sewer & Water	Brokk - Remote Demolition Equipment	\$71.57	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators- Underground Sewer & Water	Brooms	\$71.57	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators- Underground Sewer & Water	Bump Cutter	\$75.41	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators- Underground	Cableways	\$76.08	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>

Lewis	<u>Power Equipment</u> <u>Operators- Underground</u> <u>Sewer &amp; Water</u>	Chipper	\$75.41	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators- Underground Sewer & Water	Compressor	\$71.57	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators- Underground Sewer & Water	Concrete Pump: Truck Mount With Boom Attachment Over 42m	\$76.08	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	<u>Power Equipment</u> <u>Operators- Underground</u> <u>Sewer &amp; Water</u>	Concrete Finish Machine - laser Screed	\$71.57	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	<u>Power Equipment</u> <u>Operators- Underground</u> <u>Sewer &amp; Water</u>	Concrete Pump - Mounted Or Trailer High Pressure Line Pump, Pump High Pressure	\$74.83	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	<u>Power Equipment</u> <u>Operators- Underground</u> <u>Sewer &amp; Water</u>	Concrete Pump: Truck Mount With Boom Attachment Up To 42m	\$75.41	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	<u>Power Equipment</u> <u>Operators- Underground</u> <u>Sewer &amp; Water</u>	Conveyors	\$74.83	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	<u>Power Equipment</u> <u>Operators- Underground</u> <u>Sewer &amp; Water</u>	Cranes Friction: 200 tons and over	\$79.13	<u>7A</u>	<u>11H</u>	<u>8X</u>	<u>View</u>
Lewis	<u>Power Equipment</u> <u>Operators- Underground</u> <u>Sewer &amp; Water</u>	Cranes, A-frame: 10 tons and under	\$72.22	<u>7A</u>	<u>11H</u>	<u>8X</u>	<u>View</u>
Lewis	<u>Power Equipment</u> <u>Operators- Underground</u> <u>Sewer &amp; Water</u>	Cranes: 100 tons through 199 tons, or 150' of boom (including jib with attachments)	\$77.56	<u>7A</u>	<u>11H</u>	<u>8X</u>	<u>View</u>
Lewis	<u>Power Equipment</u> <u>Operators- Underground</u> <u>Sewer &amp; Water</u>	Cranes: 20 tons through 44 tons with attachments	\$76.11	<u>7A</u>	<u>11H</u>	<u>8X</u>	<u>View</u>
Lewis	<u>Power Equipment</u> <u>Operators- Underground</u> <u>Sewer &amp; Water</u>	Cranes: 200 tons- 299 tons, or 250' of boom including jib with attachments	\$78.36	<u>7A</u>	<u>11H</u>	<u>8X</u>	<u>View</u>
Lewis	<u>Power Equipment</u> <u>Operators- Underground</u> <u>Sewer &amp; Water</u>	Cranes: 300 tons and over or 300' of boom including jib with attachments	\$79.13	<u>7A</u>	<u>11H</u>	<u>8X</u>	<u>View</u>
Lewis	<u>Power Equipment</u> <u>Operators- Underground</u> <u>Sewer &amp; Water</u>	Cranes: 45 tons through 99 tons, under 150' of boom(including jib with attachments)	\$76.79	<u>7A</u>	<u>11H</u>	<u>8X</u>	<u>View</u>
Lewis	<u>Power Equipment</u> <u>Operators- Underground</u> <u>Sewer &amp; Water</u>	Cranes: Friction cranes through 199 tons	\$78.36	<u>7A</u>	<u>11H</u>	<u>8X</u>	<u>View</u>
Lewis	<u>Power Equipment</u> <u>Operators- Underground</u> <u>Sewer &amp; Water</u>	Cranes: through 19 tons with attachments, A- frame over 10 tons	\$75.53	<u>7A</u>	<u>11H</u>	<u>8X</u>	<u>View</u>
Lewis	<u>Power Equipment</u> <u>Operators- Underground</u>	Crusher	\$75.41	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>

Lewis	<u>Power Equipment</u> <u>Operators- Underground</u> <u>Sewer &amp; Water</u>	Deck Engineer/deck Winches (power)	\$75.41	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators- Underground Sewer & Water	Derricks: on building work	\$76.79	<u>7A</u>	<u>11H</u>	<u>8X</u>	<u>View</u>
Lewis	<u>Power Equipment</u> <u>Operators- Underground</u> <u>Sewer &amp; Water</u>	Dozers D-9 & Under	\$74.83	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	<u>Power Equipment</u> <u>Operators- Underground</u> <u>Sewer &amp; Water</u>	Drill Oilers: Auger Type, Truck Or Crane Mount	\$74.83	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	<u>Power Equipment</u> <u>Operators- Underground</u> <u>Sewer &amp; Water</u>	Drilling Machine	\$76.85	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	<u>Power Equipment</u> <u>Operators- Underground</u> <u>Sewer &amp; Water</u>	Elevator and man-lift: permanent and shaft type	\$72.22	<u>7A</u>	<u>11H</u>	<u>8X</u>	<u>View</u>
Lewis	<u>Power Equipment</u> <u>Operators- Underground</u> <u>Sewer &amp; Water</u>	Finishing Machine, Bidwell And Gamaco & Similar Equipment	\$75.41	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	<u>Power Equipment</u> <u>Operators- Underground</u> <u>Sewer &amp; Water</u>	Forklift: 3000 lbs and over with attachments	\$75.53	<u>7A</u>	<u>11H</u>	<u>8X</u>	<u>View</u>
Lewis	<u>Power Equipment</u> <u>Operators- Underground</u> <u>Sewer &amp; Water</u>	Forklifts: under 3000 lbs. with attachments	\$72.22	<u>7A</u>	<u>11H</u>	<u>8X</u>	<u>View</u>
Lewis	<u>Power Equipment</u> <u>Operators- Underground</u> <u>Sewer &amp; Water</u>	Grade Engineer: Using Blueprints, Cut Sheets,etc.	\$75.41	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	<u>Power Equipment</u> <u>Operators- Underground</u> <u>Sewer &amp; Water</u>	Gradechecker/stakeman	\$71.57	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	<u>Power Equipment</u> <u>Operators- Underground</u> <u>Sewer &amp; Water</u>	Guardrail punch/Auger	\$75.41	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	<u>Power Equipment</u> <u>Operators- Underground</u> <u>Sewer &amp; Water</u>	Hard Tail End Dump Articulating Off- Road Equipment 45 Yards. & Over	\$76.08	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	<u>Power Equipment</u> <u>Operators- Underground</u> <u>Sewer &amp; Water</u>	Hard Tail End Dump Articulating Off-road Equipment Under 45 Yards	\$75.41	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	<u>Power Equipment</u> <u>Operators- Underground</u> <u>Sewer &amp; Water</u>	Horizontal/directional Drill Locator	\$74.83	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	<u>Power Equipment</u> <u>Operators- Underground</u> <u>Sewer &amp; Water</u>	Horizontal/directional Drill Operator	\$75.41	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	<u>Power Equipment</u> <u>Operators- Underground</u> <u>Sewer &amp; Water</u>	Hydralifts/boom trucks: 10 tons and under	\$72.22	<u>7A</u>	<u>11H</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators- Underground	Hydralifts/boom trucks: over 10 tons	\$75.53	<u>7A</u>	<u>11H</u>	<u>8X</u>	<u>View</u>

Lewis	Power Equipment Operators- Underground	Loader, Overhead 8 Yards. & Over	\$76.85	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
	<u>Sewer &amp; Water</u>						
Lewis	<u>Power Equipment</u> <u>Operators- Underground</u> <u>Sewer &amp; Water</u>	Loader, Overhead, 6 Yards. But Not Including 8 Yards	\$76.08	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	<u>Power Equipment</u> <u>Operators- Underground</u> <u>Sewer &amp; Water</u>	Loaders, Overhead Under 6 Yards	\$75.41	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	<u>Power Equipment</u> <u>Operators- Underground</u> <u>Sewer &amp; Water</u>	Loaders, Plant Feed	\$75.41	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators- Underground Sewer & Water	Loaders: Elevating Type Belt	\$74.83	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators- Underground Sewer & Water	Locomotives, All	\$75.41	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators- Underground Sewer & Water	Material Transfer Device	\$75.41	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators- Underground Sewer & Water	Mechanics: all (Leadmen - \$0.50 per hour over mechanic)	\$77.56	<u>7A</u>	<u>11H</u>	<u>8X</u>	<u>View</u>
Lewis	<u>Power Equipment</u> <u>Operators- Underground</u> <u>Sewer &amp; Water</u>	Motor patrol graders	\$76.08	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators- Underground Sewer & Water	Mucking Machine, Mole, Tunnel Drill, Boring, Road Header And/or Shield	\$76.08	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators- Underground Sewer & Water	Oil Distributors, Blower Distribution & Mulch Seeding Operator	\$71.57	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators- Underground Sewer & Water	Outside Hoists (elevators and manlifts), Air Tuggers, Strato	\$75.53	<u>7A</u>	<u>11H</u>	<u>8X</u>	<u>View</u>
Lewis	<u>Power Equipment</u> <u>Operators- Underground</u> <u>Sewer &amp; Water</u>	Overhead, bridge type Crane: 20 tons through 44 tons	\$76.11	<u>7A</u>	<u>11H</u>	<u>8X</u>	<u>View</u>
Lewis	<u>Power Equipment</u> <u>Operators- Underground</u> <u>Sewer &amp; Water</u>	Overhead, bridge type: 100 tons and over	\$77.56	<u>7A</u>	<u>11H</u>	<u>8X</u>	<u>View</u>
Lewis	<u>Power Equipment</u> <u>Operators- Underground</u> <u>Sewer &amp; Water</u>	Overhead, bridge type: 45 tons through 99 tons	\$76.79	<u>7A</u>	<u>11H</u>	<u>8X</u>	<u>View</u>
Lewis	<u>Power Equipment</u> <u>Operators- Underground</u> <u>Sewer &amp; Water</u>	Pavement Breaker	\$71.57	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators- Underground Sewer & Water	Pile Driver (other Than Crane Mount)	\$75.41	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	<u>Power Equipment</u> <u>Operators- Underground</u> Sewer & Water	Plant Oiler - Asphalt, Crusher	\$74.83	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>

Lewis	<u>Power Equipment</u> <u>Operators- Underground</u> <u>Sewer &amp; Water</u>	Posthole Digger, Mechanical	\$71.57	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	<u>Power Equipment</u> <u>Operators- Underground</u> <u>Sewer &amp; Water</u>	Power Plant	\$71.57	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	<u>Power Equipment</u> <u>Operators- Underground</u> <u>Sewer &amp; Water</u>	Pumps - Water	\$71.57	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	<u>Power Equipment</u> <u>Operators- Underground</u> <u>Sewer &amp; Water</u>	Quad 9, HD 41, D10 And Over	\$76.08	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	<u>Power Equipment</u> <u>Operators- Underground</u> <u>Sewer &amp; Water</u>	Quick Tower: no cab, under 100 feet in height based to boom	\$72.22	<u>7A</u>	<u>11H</u>	<u>8X</u>	<u>View</u>
Lewis	<u>Power Equipment</u> <u>Operators- Underground</u> <u>Sewer &amp; Water</u>	Remote Control Operator On Rubber Tired Earth Moving Equipment	\$76.08	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	<u>Power Equipment</u> <u>Operators- Underground</u> <u>Sewer &amp; Water</u>	Rigger and Bellman	\$72.22	<u>7A</u>	<u>11H</u>	<u>8X</u>	<u>View</u>
Lewis	<u>Power Equipment</u> <u>Operators- Underground</u> <u>Sewer &amp; Water</u>	Rigger/Signal Person, Bellman(Certified)	\$75.53	<u>7A</u>	<u>11H</u>	<u>8X</u>	<u>View</u>
Lewis	<u>Power Equipment</u> <u>Operators- Underground</u> <u>Sewer &amp; Water</u>	Rollagon	\$76.08	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	<u>Power Equipment</u> <u>Operators- Underground</u> <u>Sewer &amp; Water</u>	Roller, Other Than Plant Mix	\$71.57	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators- Underground Sewer & Water	Roller, Plant Mix Or Multi- lift Materials	\$74.83	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators- Underground Sewer & Water	Roto-mill, Roto-grinder	\$75.41	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators- Underground Sewer & Water	Saws - Concrete	\$74.83	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators- Underground Sewer & Water	Scraper, Self Propelled Under 45 Yards	\$75.41	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators- Underground Sewer & Water	Scrapers - Concrete & Carry All	\$74.83	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	<u>Power Equipment</u> <u>Operators- Underground</u> <u>Sewer &amp; Water</u>	Scrapers, Self-propelled: 45 Yards And Over	\$76.08	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators- Underground Sewer & Water	Service Engineers: equipment	\$75.53	<u>7A</u>	<u>11H</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators- Underground Sewer & Water	Shotcrete/gunite Equipment	\$71.57	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>

Lewis	<u>Power Equipment</u> <u>Operators- Underground</u> <u>Sewer &amp; Water</u>	Shovel, Excavator, Backhoe, Tractors Under 15 Metric Tons	\$74.83	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators- Underground Sewer & Water	Shovel, Excavator, Backhoe: Over 30 Metric Tons To 50 Metric Tons	\$76.08	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	<u>Power Equipment</u> <u>Operators- Underground</u> <u>Sewer &amp; Water</u>	Shovel, Excavator, Backhoes, Tractors: 15 To 30 Metric Tons	\$75.41	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators- Underground Sewer & Water	Shovel, Excavator, Backhoes: Over 50 Metric Tons To 90 Metric Tons	\$76.85	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators- Underground Sewer & Water	Slipform Pavers	\$76.08	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators- Underground Sewer & Water	Spreader, Topsider & Screedman	\$76.08	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators- Underground Sewer & Water	Subgrader Trimmer	\$75.41	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	<u>Power Equipment</u> <u>Operators- Underground</u> <u>Sewer &amp; Water</u>	Tower Bucket Elevators	\$74.83	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	<u>Power Equipment</u> <u>Operators- Underground</u> Sewer & Water	Tower Crane: over 175' through 250' in height, base to boom	\$78.36	<u>7A</u>	<u>11H</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators- Underground Sewer & Water	Tower crane: up to 175' in height base to boom	\$77.56	<u>7A</u>	<u>11H</u>	<u>8X</u>	<u>View</u>
Lewis	<u>Power Equipment</u> <u>Operators- Underground</u> <u>Sewer &amp; Water</u>	Tower Cranes: over 250' in height from base to boom.	\$79.13	<u>7A</u>	<u>11H</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators- Underground Sewer & Water	Transporters, All Track Or Truck Type	\$76.08	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators- Underground Sewer & Water	Trenching Machines	\$74.83	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators- Underground Sewer & Water	Truck Crane Oiler/Driver: 100 tons and over	\$76.11	<u>7A</u>	<u>11H</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators- Underground Sewer & Water	Truck crane oiler/driver: under 100 tons	\$75.53	<u>7A</u>	<u>11H</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators- Underground Sewer & Water	Truck Mount Portable Conveyor	\$75.41	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators- Underground Sewer & Water	Vac Truck (Vactor Guzzler, Hydro Excavator)	\$75.41	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators- Underground Sewer & Water	Welder	\$76.79	<u>7A</u>	<u>11H</u>	<u>8X</u>	<u>View</u>

Lewis	<u>Power Equipment</u> <u>Operators- Underground</u> <u>Sewer &amp; Water</u>	Wheel Tractors, Farmall Type	\$71.57	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Equipment Operators- Underground Sewer & Water	Yo Yo Pay Dozer	\$75.41	<u>15J</u>	<u>3K</u>	<u>8X</u>	<u>View</u>
Lewis	Power Line Clearance Tree Trimmers	Journey Level In Charge	\$57.22	<u>5A</u>	<u>4A</u>		<u>View</u>
Lewis	Power Line Clearance Tree Trimmers	Spray Person	\$54.32	<u>5A</u>	<u>4A</u>		<u>View</u>
Lewis	Power Line Clearance Tree Trimmers	Tree Equipment Operator	\$57.22	<u>5A</u>	<u>4A</u>		<u>View</u>
Lewis	Power Line Clearance Tree Trimmers	Tree Trimmer	\$51.18	<u>5A</u>	<u>4A</u>		<u>View</u>
Lewis	Power Line Clearance Tree Trimmers	Tree Trimmer Groundperson	\$38.99	<u>5A</u>	<u>4A</u>		<u>View</u>
Lewis	Refrigeration & Air Conditioning Mechanics	Journey Level	\$85.71	<u>5A</u>	<u>1G</u>		<u>View</u>
Lewis	Residential Brick Mason	Journey Level	\$21.96		<u>1</u>		View
Lewis	Residential Carpenters	Journey Level	\$24.89		<u>1</u>		View
Lewis	Residential Cement Masons	Journey Level	\$16.79		<u>1</u>		View
Lewis	Residential Drywall Applicators	Journey Level	\$36.07		<u>1</u>		<u>View</u>
Lewis	Residential Drywall Tapers	Journey Level	\$24.48		<u>1</u>		<u>View</u>
Lewis	Residential Electricians	Journey Level	\$43.03	<u>6Z</u>	<u>1B</u>		<u>View</u>
Lewis	Residential Glaziers	Journey Level	\$25.40		<u>1</u>		<u>View</u>
Lewis	Residential Insulation Applicators	Journey Level	\$28.53		<u>1</u>		<u>View</u>
Lewis	Residential Laborers	Journey Level	\$23.10		<u>1</u>		<u>View</u>
Lewis	Residential Marble Setters	Journey Level	\$21.96		<u>1</u>		<u>View</u>
Lewis	Residential Painters	Journey Level	\$18.76		<u>1</u>		<u>View</u>
Lewis	Residential Plumbers & Pipefitters	Journey Level	\$26.35		<u>1</u>		<u>View</u>
Lewis	Residential Refrigeration & Air Conditioning Mechanics	Journey Level	\$32.89		1		<u>View</u>
Lewis	Residential Sheet Metal Workers	Journey Level	\$33.28		<u>1</u>		<u>View</u>
Lewis	Residential Soft Floor Layers	Journey Level	\$15.74		<u>1</u>		<u>View</u>
Lewis	Residential Sprinkler Fitters (Fire Protection)	Journey Level	\$20.28		<u>1</u>		<u>View</u>
Lewis	Residential Stone Masons	Journey Level	\$21.96		<u>1</u>		<u>View</u>
Lewis	<u>Residential Terrazzo</u> <u>Workers</u>	Journey Level	\$15.74		<u>1</u>		<u>View</u>
Lewis	Residential Terrazzo/Tile Finishers	Journey Level	\$15.74		<u>1</u>		<u>View</u>
Lewis	Residential Tile Setters	Journey Level	\$15.74		<u>1</u>		<u>View</u>
Lewis	Roofers	Journey Level	\$60.90	<u>5A</u>	<u>3H</u>		View
Lewis	Roofers	Using Irritable Bituminous Materials	\$63.90	<u>5A</u>	<u>3H</u>		<u>View</u>
Lewis	Sheet Metal Workers	Journey Level (Field or Shop)	\$94.11	<u>7F</u>	<u>1E</u>		<u>View</u>

Lewis	<u>Sign Makers &amp; Installers</u> ( <u>Electrical)</u>	Journey Level	\$18.04		1		<u>View</u>
Lewis	Sign Makers & Installers (Non-Electrical)	Journey Level	\$56.80	<u>15J</u>	<u>4V</u>	<u>8Y</u>	<u>View</u>
Lewis	Soft Floor Layers	Journey Level	\$62.39	<u>15J</u>	<u>4C</u>		<u>View</u>
Lewis	Solar Controls For Windows	Journey Level	\$15.74		<u>1</u>		<u>View</u>
Lewis	<u>Sprinkler Fitters (Fire</u> <u>Protection)</u>	Journey Level	\$70.52	<u>7J</u>	<u>1R</u>		<u>View</u>
Lewis	<u>Stage Rigging Mechanics</u> (Non Structural)	Journey Level	\$15.74		<u>1</u>		<u>View</u>
Lewis	Stone Masons	Journey Level	\$66.32	<u>7E</u>	<u>1N</u>		<u>View</u>
Lewis	Street And Parking Lot Sweeper Workers	Journey Level	\$16.00		<u>1</u>		<u>View</u>
Lewis	<u>Surveyors</u>	Assistant Construction Site Surveyor	\$75.53	<u>7A</u>	<u>11H</u>	<u>8X</u>	<u>View</u>
Lewis	<u>Surveyors</u>	Chainman	\$72.22	<u>7A</u>	<u>11H</u>	<u>8X</u>	<u>View</u>
Lewis	<u>Surveyors</u>	Construction Site Surveyor	\$76.79	<u>7A</u>	<u>11H</u>	<u>8X</u>	<u>View</u>
Lewis	<u>Surveyors</u>	Drone Operator (when used in conjunction with surveying work only)	\$72.22	<u>7A</u>	<u>11H</u>	<u>8X</u>	<u>View</u>
Lewis	<u>Surveyors</u>	Ground Penetrating Radar	\$72.22	<u>7A</u>	<u>11H</u>	<u>8X</u>	<u>View</u>
Lewis	Telecommunication Technicians	Journey Level	\$51.14	<u>67</u>	<u>1B</u>		<u>View</u>
Lewis	Telephone Line Construction - Outside	Cable Splicer	\$39.15	<u>5A</u>	<u>2B</u>		<u>View</u>
Lewis	Telephone Line Construction - Outside	Hole Digger/Ground Person	\$26.29	<u>5A</u>	<u>2B</u>		<u>View</u>
Lewis	Telephone Line Construction - Outside	Telephone Equipment Operator (Light)	\$32.72	<u>5A</u>	<u>2B</u>		<u>View</u>
Lewis	Telephone Line Construction - Outside	Telephone Lineperson	\$37.00	<u>5A</u>	<u>2B</u>		<u>View</u>
Lewis	Terrazzo Workers	Journey Level	\$60.36	<u>7E</u>	<u>1N</u>		<u>View</u>
Lewis	Tile Setters	Journey Level	\$60.36	<u>7E</u>	<u>1N</u>		<u>View</u>
Lewis	<u>Tile, Marble &amp; Terrazzo</u> <u>Finishers</u>	Finisher	\$51.19	<u>7E</u>	<u>1N</u>		<u>View</u>
Lewis	Traffic Control Stripers	Journey Level	\$51.90	<u>7A</u>	<u>1K</u>		<u>View</u>
Lewis	Truck Drivers	Asphalt Mix Over 16 Yards	\$71.70	<u>15J</u>	<u>11M</u>	<u>8L</u>	<u>View</u>
Lewis	Truck Drivers	Asphalt Mix To 16 Yards	\$70.86	<u>15J</u>	<u>11M</u>	<u>8L</u>	<u>View</u>
Lewis	Truck Drivers	Dump Truck	\$70.86	<u>15J</u>	<u>11M</u>	<u>8L</u>	View
Lewis	Truck Drivers	Dump Truck & Trailer	\$71.70	<u>15J</u>	<u>11M</u>	<u>8L</u>	<u>View</u>
Lewis	Truck Drivers	Other Trucks	\$71.70	<u>15J</u>	<u>11M</u>	<u>8L</u>	<u>View</u>
Lewis	Truck Drivers - Ready Mix	Transit Mix	\$71.70	<u>15J</u>	<u>11M</u>	<u>8L</u>	View
Lewis	Well Drillers & Irrigation Pump Installers	Irrigation Pump Installer	\$18.18		<u><u>1</u></u>		View
Lewis	Well Drillers & Irrigation Pump Installers	Oiler	\$15.74		<u>1</u>		<u>View</u>
Lewis	Well Drillers & Irrigation Pump Installers	Well Driller	\$18.00		<u>1</u>		<u>View</u>

#### Washington State Department of Labor and Industries Policy Statement (Regarding the Production of "Standard" or "Non-standard" Items)

Below is the department's (State L&I's) list of criteria to be used in determining whether a prefabricated item is "standard" or "non-standard". For items not appearing on WSDOT's predetermined list, these criteria shall be used by the Contractor (and the Contractor's subcontractors, agents to subcontractors, suppliers, manufacturers, and fabricators) to determine coverage under RCW 39.12. The production, in the State of Washington, of non-standard items is covered by RCW 39.12, and the production of standard items is not. The production of any item outside the State of Washington is not covered by RCW 39.12.

1. Is the item fabricated for a public works project? If not, it is not subject to RCW 39.12. If it is, go to question 2.

2. Is the item fabricated on the public works jobsite? If it is, the work is covered under RCW 39.12. If not, go to question 3.

3. Is the item fabricated in an assembly/fabrication plant set up for, and dedicated primarily to, the public works project? If it is, the work is covered by RCW 39.12. If not, go to question 4.

4. Does the item require any assembly, cutting, modification or other fabrication by the supplier? If not, the work is not covered by RCW 39.12. If yes, go to question 5.

5. Is the prefabricated item intended for the public works project typically an inventory item which could reasonably be sold on the general market? If not, the work is covered by RCW 39.12. If yes, go to question 6.

6. Does the specific prefabricated item, generally defined as standard, have any unusual characteristics such as shape, type of material, strength requirements, finish, etc? If yes, the work is covered under RCW 39.12.

Any firm with questions regarding the policy, WSDOT's Predetermined List, or for determinations of covered and non-covered workers shall be directed to State L&I at (360) 902-5330.

#### WSDOT's Predetermined List for Suppliers - Manufactures - Fabricator

Below is a list of potentially prefabricated items, originally furnished by WSDOT to Washington State Department of Labor and Industries, that may be considered nonstandard and therefore covered by the prevailing wage law, RCW 39.12. Items marked with an X in the "YES" column should be considered to be non-standard and therefore covered by RCW 39.12. Items marked with an X in the "NO" column should be considered to be standard and therefore not covered. Of course, exceptions to this general list may occur, and in that case shall be evaluated according to the criteria described in State and L&I's policy statement.

	ITEM DESCRIPTION	YES	NO
1.	Metal rectangular frames, solid metal covers, herringbone grates, and bi-directional vaned grates for Catch Basin Types 1, 1L, 1P, and 2 and Concrete Inlets. See Std. Plans		x
2.	Metal circular frames (rings) and covers, circular grates, and prefabricated ladders for Manhole Types 1, 2, and 3, Drywell Types 1, 2, and 3 and Catch Basin Type 2. See Std. Plans		x
3.	Prefabricated steel grate supports and welded grates, metal frames and dual vaned grates, and Type 1, 2, and 3 structural tubing grates for Drop Inlets. See Std. Plans.		X
4.	Concrete Pipe - Plain Concrete pipe and reinforced concrete pipe Class 2 to 5 sizes smaller than 60 inch diameter.		X
5.	Concrete Pipe - Plain Concrete pipe and reinforced concrete pipe Class 2 to 5 sizes larger than 60 inch diameter.		X
6.	Corrugated Steel Pipe - Steel lock seam corrugated pipe for culverts and storm sewers, sizes 30 inch to 120 inches in diameter. May also be treated, 1 thru 5.		x
7.	Corrugated Aluminum Pipe - Aluminum lock seam corrugated pipe for culverts and storm sewers, sizes 30 inch to 120 inches in diameter. May also be treated, #5.		x

8.	Anchor Bolts & Nuts - Anchor Bolts and Nuts, for mounting sign structures, luminaries and other items, shall be made from commercial bolt stock. See Contract Plans and Std. Plans for size and material type.		Х
9.	Aluminum Pedestrian Handrail - Pedestrian handrail conforming to the type and material specifications set forth in the contract plans. Welding of aluminum shall be in accordance with Section 9-28.14(3).	х	
10.	Major Structural Steel Fabrication - Fabrication of major steel items such as trusses, beams, girders, etc., for bridges.	Х	
11.	Minor Structural Steel Fabrication - Fabrication of minor steel Items such as special hangers, brackets, access doors for structures, access ladders for irrigation boxes, bridge expansion joint systems, etc., involving welding, cutting, punching and/or boring of holes. See Contact Plans for item description and shop drawings.	Х	
12.	Aluminum Bridge Railing Type BP - Metal bridge railing conforming to the type and material specifications set forth in the Contract Plans. Welding of aluminum shall be in accordance with Section 9-28.14(3).		Х
13.	Concrete PilingPrecast-Prestressed concrete piling for use as 55 and 70 ton concrete piling. Concrete to conform to Section 9-19.1 of Std. Spec	х	
14.	Precast Manhole Types 1, 2, and 3 with cones, adjustment sections and flat top slabs. See Std. Plans.		Х
15.	Precast Drywell Types 1, 2, and with cones and adjustment Sections. See Std. Plans.		Х
16.	Precast Catch Basin - Catch Basin type 1, 1L, 1P, and 2 With adjustment sections. See Std. Plans.		Х

	ITEM DESCRIPTION	YES	NO
17.	Precast Concrete Inlet - with adjustment sections, See Std. Plans		х
18.	Precast Drop Inlet Type 1 and 2 with metal grate supports. See Std. Plans.		X
19.	Precast Grate Inlet Type 2 with extension and top units. See Std. Plans		X
20.	Metal frames, vaned grates, and hoods for Combination Inlets. See Std. Plans		X
21.	Precast Concrete Utility Vaults - Precast Concrete utility vaults of various sizes. Used for in ground storage of utility facilities and controls. See Contract Plans for size and construction requirements. Shop drawings are to be provided for approval prior to casting		X
22.	Vault Risers - For use with Valve Vaults and Utilities X Vaults.		x
23.	Valve Vault - For use with underground utilities. See Contract Plans for details.		Х
24.	Precast Concrete Barrier - Precast Concrete Barrier for use as new barrier or may also be used as Temporary Concrete Barrier. Only new state approved barrier may be used as permanent barrier.		x
25.	Reinforced Earth Wall Panels – Reinforced Earth Wall Panels in size and shape as shown in the Plans. Fabrication plant has annual approval for methods and materials to be used. See Shop Drawing. Fabrication at other locations may be approved, after facilities inspection, contact HQ. Lab.	x	
26.	Precast Concrete Walls - Precast Concrete Walls - tilt-up wall panel in size and shape as shown in Plans. Fabrication plant has annual approval for methods and materials to be used	X	

#### **ITEM DESCRIPTION**

27.	Precast Railroad Crossings - Concrete Crossing Structure Slabs.	Х	
28.	<ul> <li>12, 18 and 26 inch Standard Precast Prestressed Girder – Standard Precast Prestressed Girder for use in structures.</li> <li>Fabricator plant has annual approval of methods and materials to</li> <li>be used. Shop Drawing to be provided for approval prior to casting girders.</li> <li>See Std. Spec. Section 6-02.3(25)A</li> </ul>	Х	
29.	Prestressed Concrete Girder Series 4-14 - Prestressed Concrete Girders for use in structures. Fabricator plant has annual approval of methods and materials to be used. Shop Drawing to be provided for approval prior to casting girders. See Std. Spec. Section 6-02.3(25)A	Х	
30.	Prestressed Tri-Beam Girder - Prestressed Tri-Beam Girders for use in structures. Fabricator plant has annual approval of methods and materials to be used. Shop Drawing to be provided for approval prior to casting girders. See Std. Spec. Section 6-02.3(25)A	Х	
31.	Prestressed Precast Hollow-Core Slab – Precast Prestressed Hollow-core slab for use in structures. Fabricator plant has annual approval of methods and materials to be used. Shop Drawing to be provided for approval prior to casting girders. See Std. Spec. Section 6-02.3(25)A.	Х	
32.	Prestressed-Bulb Tee Girder - Bulb Tee Prestressed Girder for use in structures. Fabricator plant has annual approval of methods and materials to be used. Shop Drawing to be provided for approval prior to casting girders. See Std. Spec. Section 6-02.3(25)A	х	
33.	Monument Case and Cover See Std. Plan.		Х

34.	Cantilever Sign Structure - Cantilever Sign Structure fabricated from steel tubing meeting AASHTO-M-183. See Std. Plans, and Contract Plans for details. The steel structure shall be galvanized after fabrication in accordance with AASHTO-M-111.	Х	
35.	Mono-tube Sign Structures - Mono-tube Sign Bridge fabricated to details shown in the Plans. Shop drawings for approval are required prior to fabrication.	Х	
36.	<ul> <li>Steel Sign Bridges - Steel Sign Bridges fabricated from steel tubing meeting AASHTO-M-138 for Aluminum Alloys.</li> <li>See Std. Plans, and Contract Plans for details. The steel structure</li> <li>shall be galvanized after fabrication in accordance with AASHTO-M-111.</li> </ul>	Х	
37.	Steel Sign Post - Fabricated Steel Sign Posts as detailed in Std Plans. Shop drawings for approval are to be provided prior to fabrication		Х
38.	Light Standard-Prestressed - Spun, prestressed, hollow concrete poles.	Х	
39.	Light Standards - Lighting Standards for use on highway illumination systems, poles to be fabricated to conform with methods and materials as specified on Std. Plans. See Specia Provisions for pre-approved drawings.	Х	
40.	Traffic Signal Standards - Traffic Signal Standards for use on highway and/or street signal systems. Standards to be fabricated to conform with methods and material as specified on Std. Plans. See Special Provisions for pre-approved drawings	х	
41.	Precast Concrete Sloped Mountable Curb (Single and DualFaced) See Std. Plans.		Х

	ITEM DESCRIPTION	YES	NO
42.	<ul> <li>Traffic Signs - Prior to approval of a Fabricator of Traffic Signs, the sources of the following materials must be submitted and approved for reflective sheeting, legend material, and aluminum</li> <li>sheeting.</li> <li><b>NOTE:</b> *** Fabrication inspection required. Only signs tagged "Fabrication Approved" by WSDOT Sign Fabrication Inspector to be installed</li> </ul>	X	x
		Custom Message	Std Signing Message
43.	Cutting & bending reinforcing steel		Х
44.	Guardrail components	Х	Х
		Custom End Sec	Standard Sec
45.	Aggregates/Concrete mixes	Covered by WAC 296-127-018	
46.	Asphalt	Covered by WAC 296-127-018	
47.	Fiber fabrics		Х
48.	Electrical wiring/components		Х
49.	treated or untreated timber pile		Х
50.	Girder pads (elastomeric bearing)	Х	
51.	Standard Dimension lumber		Х
52.	Irrigation components		Х

	ITEM DESCRIPTION	YES	NO
53.	Fencing materials		Х
54.	Guide Posts		Х
55.	Traffic Buttons		Х
56.	Ероху		Х
57.	Cribbing		Х
58.	Water distribution materials		Х
59.	Steel "H" piles		Х
60.	Steel pipe for concrete pile casings		Х
61.	Steel pile tips, standard		Х
62.	Steel pile tips, custom	Х	

Prefabricated items specifically produced for public works projects that are prefabricated in a county other than the county wherein the public works project is to be completed, the wage for the offsite prefabrication shall be the applicable prevailing wage for the county in which the actual prefabrication takes place.

It is the manufacturer of the prefabricated product to verify that the correct county wage rates are applied to work they perform.

See RCW <u>39.12.010</u>

<sup>(</sup>The definition of "locality" in RCW <u>39.12.010</u>(2) contains the phrase "wherein the physical work is being performed." The department interprets this phrase to mean the actual work site.

### WSDOT's List of State Occupations not applicable to Heavy and Highway Construction Projects

This project is subject to the state hourly minimum rates for wages and fringe benefits in the contract provisions, as provided by the state Department of Labor and Industries.

The following list of occupations, is comprised of those occupations that are not normally used in the construction of heavy and highway projects.

When considering job classifications for use and / or payment when bidding on, or building heavy and highway construction projects for, or administered by WSDOT, these Occupations will be excepted from the included "Washington State Prevailing Wage Rates For Public Work Contracts" documents.

- Building Service Employees
- Electrical Fixture Maintenance Workers
- Electricians Motor Shop
- Heating Equipment Mechanics
- Industrial Engine and Machine Mechanics
- Industrial Power Vacuum Cleaners
- Inspection, Cleaning, Sealing of Water Systems by Remote Control
- Laborers Underground Sewer & Water
- Machinists (Hydroelectric Site Work)
- Modular Buildings
- Playground & Park Equipment Installers
- Power Equipment Operators Underground Sewer & Water
- Residential \*\*\* ALL ASSOCIATED RATES \*\*\*
- Sign Makers and Installers (Non-Electrical)
- Sign Makers and Installers (Electrical)
- Stage Rigging Mechanics (Non Structural)

The following occupations may be used only as outlined in the preceding text concerning "WSDOT's list for Suppliers - Manufacturers - Fabricators"

- Fabricated Precast Concrete Products
- Metal Fabrication (In Shop)

Definitions for the Scope of Work for prevailing wages may be found at the Washington State Department of Labor and Industries web site and in WAC Chapter 296-127.

#### Washington State Department of Labor and Industries Policy Statements (Regarding Production and Delivery of Gravel, Concrete, Asphalt, etc.)

## WAC 296-127-018 Agency filings affecting this section

# Coverage and exemptions of workers involved in the production and delivery of gravel, concrete, asphalt, or similar materials.

(1) The materials covered under this section include but are not limited to: Sand, gravel, crushed rock, concrete, asphalt, or other similar materials.

(2) All workers, regardless of by whom employed, are subject to the provisions of chapter 39.12 RCW when they perform any or all of the following functions:

(a) They deliver or discharge any of the above-listed materials to a public works project site:

(i) At one or more point(s) directly upon the location where the material will be incorporated into the project; or

(ii) At multiple points at the project; or

(iii) Adjacent to the location and coordinated with the incorporation of those materials.

(b) They wait at or near a public works project site to perform any tasks subject to this section of the rule.

(c) They remove any materials from a public works construction site pursuant to contract requirements or specifications (e.g., excavated materials, materials from demolished structures, clean-up materials, etc.).

(d) They work in a materials production facility (e.g., batch plant, borrow pit, rock quarry, etc.,) which is established for a public works project for the specific, but not necessarily exclusive, purpose of supplying materials for the project.

(e) They deliver concrete to a public works site regardless of the method of incorporation.

(f) They assist or participate in the incorporation of any materials into the public works project.

(3) All travel time that relates to the work covered under subsection (2) of this section requires the payment of prevailing wages. Travel time includes time spent waiting to load, loading, transporting, waiting to unload, and delivering materials. Travel time would include all time spent in travel in support of a public works project whether the vehicle is empty or full. For example, travel time spent returning to a supply source to obtain another load of material for use on a public works site or returning to the public works site to obtain another load of excavated material is time spent in travel that is subject to prevailing wage. Travel to a supply source, including travel from a public works site, to obtain materials for use on a private project would not be travel subject to the prevailing wage.

(4) Workers are not subject to the provisions of chapter 39.12 RCW when they deliver materials to a stockpile.

(a) A "stockpile" is defined as materials delivered to a pile located away from the site of incorporation such that the stockpiled materials must be physically moved from the stockpile and transported to another location on the project site in order to be incorporated into the project.

(b) A stockpile does not include any of the functions described in subsection (2)(a) through (f) of this section; nor does a stockpile include materials delivered or distributed to multiple locations upon the project site; nor does a stockpile include materials dumped at the place of incorporation, or adjacent to the location and coordinated with the incorporation.

(5) The applicable prevailing wage rate shall be determined by the locality in which the work is performed. Workers subject to subsection (2)(d) of this section, who produce such materials at an off-site facility shall be paid the applicable prevailing wage rates for the county in which the off-site facility is located. Workers subject to subsection (2) of this section, who deliver such materials to a public works project site shall be paid the applicable prevailing wage rates for the county in which the prevailing wage rates for the county in which the prevailing wage rates for the county in which the public works project is located.

[Statutory Authority: Chapter 39.12 RCW, RCW 43.22.051 and 43.22.270. 08-24-101, § 296-127-018, filed 12/2/08, effective 1/2/09. Statutory Authority: Chapters 39.04 and 39.12 RCW and RCW 43.22.270. 92-01-104 and 92-08-101, § 296-127-018, filed 12/18/91 and 4/1/92, effective 8/31/92.]

#### \*\*\*\*\*

#### **Overtime Codes**

**Overtime calculations** are based on the hourly rate actually paid to the worker. On public works projects, the hourly rate must be not less than the prevailing rate of wage minus the hourly rate of the cost of fringe benefits actually provided for the worker.

- 1. ALL HOURS WORKED IN EXCESS OF EIGHT (8) HOURS PER DAY OR FORTY (40) HOURS PER WEEK SHALL BE PAID AT ONE AND ONE-HALF TIMES THE HOURLY RATE OF WAGE.
  - B. All hours worked on Saturdays shall be paid at one and one-half times the hourly rate of wage. All hours worked on Sundays and holidays shall be paid at double the hourly rate of wage.
  - C. The first two (2) hours after eight (8) regular hours Monday through Friday and the first ten (10) hours on Saturday shall be paid at one and one-half times the hourly rate of wage. All other overtime hours and all hours worked on Sundays and holidays shall be paid at double the hourly rate of wage.
  - D. The first two (2) hours before or after a five-eight (8) hour workweek day or a four-ten (10) hour workweek day and the first eight (8) hours worked the next day after either workweek shall be paid at one and one-half times the hourly rate of wage. All additional hours worked and all worked on Sundays and holidays shall be paid at double the hourly rate of wage.
  - E. The first two (2) hours after eight (8) regular hours Monday through Friday and the first eight (8) hours on Saturday shall be paid at one and one-half times the hourly rate of wage. All other hours worked Monday through Saturday, and all hours worked on Sundays and holidays shall be paid at double the hourly rate of wage.
  - F. The first two (2) hours after eight (8) regular hours Monday through Friday and the first ten (10) hours on Saturday shall be paid at one and one-half times the hourly rate of wage. All other overtime hours worked, except Labor Day, shall be paid at double the hourly rate of wage. All hours worked on Labor Day shall be paid at three times the hourly rate of wage.
  - G. The first ten (10) hours worked on Saturdays and the first ten (10) hours worked on a fifth calendar weekday in a fourten hour schedule, shall be paid at one and one-half times the hourly rate of wage. All hours worked in excess of ten (10) hours per day Monday through Saturday and all hours worked on Sundays and holidays shall be paid at double the hourly rate of wage.
  - H. All hours worked on Saturdays (except makeup days if work is lost due to inclement weather conditions or equipment breakdown) shall be paid at one and one-half times the hourly rate of wage. All hours worked Monday through Saturday over twelve (12) hours and all hours worked on Sundays and holidays shall be paid at double the hourly rate of wage.
  - I. All hours worked on Sundays and holidays shall also be paid at double the hourly rate of wage.
  - J. The first two (2) hours after eight (8) regular hours Monday through Friday and the first ten (10) hours on Saturday shall be paid at one and one-half times the hourly rate of wage. All hours worked over ten (10) hours Monday through Saturday, Sundays and holidays shall be paid at double the hourly rate of wage.
  - K. All hours worked on Saturdays and Sundays shall be paid at one and one-half times the hourly rate of wage. All hours worked on holidays shall be paid at double the hourly rate of wage.
  - M. All hours worked on Saturdays (except makeup days if work is lost due to inclement weather conditions) shall be paid at one and one-half times the hourly rate of wage. All hours worked on Sundays and holidays shall be paid at double the hourly rate of wage.
  - N. All hours worked on Saturdays (except makeup days) shall be paid at one and one-half times the hourly rate of wage. All hours worked on Sundays and holidays shall be paid at double the hourly rate of wage.

#### **Overtime Codes Continued**

- 1. O. The first ten (10) hours worked on Saturday shall be paid at one and one-half times the hourly rate of wage. All hours worked on Sundays, holidays and after twelve (12) hours, Monday through Friday and after ten (10) hours on Saturday shall be paid at double the hourly rate of wage.
  - P. All hours worked on Saturdays (except makeup days if circumstances warrant) and Sundays shall be paid at one and one-half times the hourly rate of wage. All hours worked on holidays shall be paid at double the hourly rate of wage.
  - Q. The first two (2) hours after eight (8) regular hours Monday through Friday and up to ten (10) hours worked on Saturdays shall be paid at one and one-half times the hourly rate of wage. All hours worked in excess of ten (10) hours per day Monday through Saturday and all hours worked on Sundays and holidays (except Christmas day) shall be paid at double the hourly rate of wage. All hours worked on Christmas day shall be paid at two and one-half times the hourly rate of wage.
  - R. All hours worked on Sundays and holidays shall be paid at two times the hourly rate of wage.
  - U. All hours worked on Saturdays shall be paid at one and one-half times the hourly rate of wage. All hours worked on Sundays and holidays (except Labor Day) shall be paid at two times the hourly rate of wage. All hours worked on Labor Day shall be paid at three times the hourly rate of wage.
  - V. All hours worked on Sundays and holidays (except Thanksgiving Day and Christmas day) shall be paid at one and one-half times the hourly rate of wage. All hours worked on Thanksgiving Day and Christmas day shall be paid at double the hourly rate of wage.
  - W. All hours worked on Saturdays and Sundays (except make-up days due to conditions beyond the control of the employer)) shall be paid at one and one-half times the hourly rate of wage. All hours worked on holidays shall be paid at double the hourly rate of wage.
  - X. The first four (4) hours after eight (8) regular hours Monday through Friday and the first twelve (12) hours on Saturday shall be paid at one and one-half times the hourly rate of wage. All hours worked over twelve (12) hours Monday through Saturday, Sundays and holidays shall be paid at double the hourly rate of wage. When holiday falls on Saturday or Sunday, the day before Saturday, Friday, and the day after Sunday, Monday, shall be considered the holiday and all work performed shall be paid at double the hourly rate of wage.
  - Y. All hours worked outside the hours of 5:00 am and 5:00 pm (or such other hours as may be agreed upon by any employer and the employee) and all hours worked in excess of eight (8) hours per day (10 hours per day for a 4 x 10 workweek) and on Saturdays and holidays (except labor day) shall be paid at one and one-half times the hourly rate of wage. (except for employees who are absent from work without prior approval on a scheduled workday during the workweek shall be paid at the straight-time rate until they have worked 8 hours in a day (10 in a 4 x 10 workweek) or 40 hours during that workweek.) All hours worked Monday through Saturday over twelve (12) hours and all hours worked on Sundays and Labor Day shall be paid at double the hourly rate of wage.
  - Z. All hours worked on Saturdays and Sundays shall be paid at one and one-half times the hourly rate of wage. All hours worked on holidays shall be paid the straight time rate of pay in addition to holiday pay.

#### **Overtime Codes Continued**

- 2. ALL HOURS WORKED IN EXCESS OF EIGHT (8) HOURS PER DAY OR FORTY (40) HOURS PER WEEK SHALL BE PAID AT ONE AND ONE-HALF TIMES THE HOURLY RATE OF WAGE.
  - B. All hours worked on holidays shall be paid at one and one-half times the hourly rate of wage.
  - F. The first eight (8) hours worked on holidays shall be paid at the straight hourly rate of wage in addition to the holiday pay. All hours worked in excess of eight (8) hours on holidays shall be paid at double the hourly rate of wage.
  - M. This code appears to be missing. All hours worked on Saturdays, Sundays and holidays shall be paid at double the hourly rate of wage.
  - O. All hours worked on Sundays and holidays shall be paid at one and one-half times the hourly rate of wage.
  - R. All hours worked on Sundays and holidays and all hours worked over sixty (60) in one week shall be paid at double the hourly rate of wage.
  - U. All hours worked on Saturdays shall be paid at one and one-half times the hourly rate of wage. All hours worked over 12 hours in a day or on Sundays and holidays shall be paid at double the hourly rate of wage.

## 3. ALL HOURS WORKED IN EXCESS OF EIGHT (8) HOURS PER DAY OR FORTY (40) HOURS PER WEEK SHALL BE PAID AT ONE AND ONE-HALF TIMES THE HOURLY RATE OF WAGE.

- F. All hours worked on Saturday shall be paid at one and one-half times the hourly rate of wage. All hours worked on Sunday shall be paid at two times the hourly rate of wage. All hours worked on paid holidays shall be paid at two and one-half times the hourly rate of wage including holiday pay.
- H. All work performed on Sundays between March 16th and October 14th and all Holidays shall be compensated for at two (2) times the regular rate of pay. Work performed on Sundays between October 15th and March 15th shall be compensated at one and one half (1-1/2) times the regular rate of pay.
- J. All hours worked between the hours of 10:00 pm and 5:00 am, Monday through Friday, and all hours worked on Saturdays shall be paid at a one and one-half times the hourly rate of wage. All hours worked on Sundays and holidays shall be paid at double the hourly rate of wage.
- K. Work performed in excess of eight (8) hours of straight time per day, or ten (10) hours of straight time per day when four ten (10) hour shifts are established, or forty (40) hours of straight time per week, Monday through Friday, or outside the normal 5 am to 6pm shift, and all work on Saturdays shall be paid at one and one-half times the hourly rate of wage. All work performed after 6:00 pm Saturday to 5:00 am Monday and Holidays, and all hours worked in excess of twelve (12) hours in a single shift shall be paid at double the hourly rate of wage.

After an employee has worked eight (8) hours at an applicable overtime rate, all additional hours shall be at the applicable overtime rate until such time as the employee has had a break of eight (8) hours or more. When an employee returns to work without at least eight (8) hours time off since their previous shift, all such time shall be a continuation of shift and paid at the applicable overtime rate until he/she shall have the eight (8) hours rest period.

#### **Overtime Codes Continued**

# 4. ALL HOURS WORKED IN EXCESS OF EIGHT (8) HOURS PER DAY OR FORTY (40) HOURS PER WEEK SHALL BE PAID AT ONE AND ONE-HALF TIMES THE HOURLY RATE OF WAGE.

- A. All hours worked in excess of eight (8) hours per day or forty (40) hours per week shall be paid at double the hourly rate of wage. All hours worked on Saturdays, Sundays and holidays shall be paid at double the hourly rate of wage
- C. On Monday through Friday, the first four (4) hours of overtime after eight (8) hours of straight time work shall be paid at one and one half (1-1/2) times the straight time rate of pay, unless a four (4) day ten (10) hour workweek has been established. On a four (4) day ten (10) hour workweek scheduled Monday through Thursday, or Tuesday through Friday, the first two (2) hours of overtime after ten (10) hours of straight time work shall be paid at one and one half (1-1/2) times the straight time rate of pay. On Saturday, the first twelve (12) hours of work shall be paid at one and one half (1-1/2) times the straight time rate of pay, except that if the job is down on Monday through Friday due to weather conditions or other conditions outside the control of the employer, the first ten (10) hours on Saturday may be worked at the straight time rate of pay. All hours worked over twelve (12) hours in a day and all hours worked on Sunday and Holidays shall be paid at two (2) times the straight time rate of pay.
- D. All hours worked in excess of eight (8) hours per day or forty (40) hours per week shall be paid at double the hourly rate of wage. All hours worked on Saturday, Sundays and holidays shall be paid at double the hourly rate of pay. Rates include all members of the assigned crew.

#### EXCEPTION:

On all multipole structures and steel transmission lines, switching stations, regulating, capacitor stations, generating plants, industrial plants, associated installations and substations, except those substations whose primary function is to feed a distribution system, will be paid overtime under the following rates:

The first two (2) hours after eight (8) regular hours Monday through Friday of overtime on a regular workday, shall be paid at one and one-half times the hourly rate of wage. All hours in excess of ten (10) hours will be at two (2) times the hourly rate of wage. The first eight (8) hours worked on Saturday will be paid at one and one-half (1-1/2) times the hourly rate of wage. All hours worked in excess of eight (8) hours on Saturday, and all hours worked on Sundays and holidays will be at the double the hourly rate of wage.

All overtime eligible hours performed on the above described work that is energized, shall be paid at the double the hourly rate of wage.

E. The first two (2) hours after eight (8) regular hours Monday through Friday and the first eight (8) hours on Saturday shall be paid at one and one-half times the hourly rate of wage. All other hours worked Monday through Saturday, and all hours worked on Sundays and holidays shall be paid at double the hourly rate of wage.

On a four-day, ten-hour weekly schedule, either Monday thru Thursday or Tuesday thru Friday schedule, all hours worked after ten shall be paid at double the hourly rate of wage. The Monday or Friday not utilized in the normal fourday, ten hour work week, and Saturday shall be paid at one and one half  $(1\frac{1}{2})$  times the regular shift rate for the first eight (8) hours. All other hours worked Monday through Saturday, and all hours worked on Sundays and holidays shall be paid at double the hourly rate of wage.

- G. All hours worked on Saturdays shall be paid at one and one-half times the hourly rate of wage. All hours worked Monday through Saturday over twelve (12) hours and all hours worked on Sundays and holidays shall be paid at double the hourly rate of wage.
- I. The First eight (8) hours worked on Saturdays shall be paid at one and one-half times the hourly rate of wage. All hours worked in excess of eight (8) per day on Saturdays shall be paid at double the hourly rate of wage. All hours worked on Sundays and holidays shall be paid at double the hourly rate of wage.

#### **Overtime Codes Continued**

- 4. J. The first eight (8) hours worked on a Saturday shall be paid at one and one-half times the hourly rate of wage. All hours worked in excess of eight (8) hours on a Saturday shall be paid at double the hourly rate of wage. All hours worked over twelve (12) in a day, and all hours worked on Sundays and Holidays shall be paid at double the hourly rate of wage.
  - K. All hours worked on a Saturday shall be paid at one and one-half times the hourly rate of wage, so long as Saturday is the sixth consecutive day worked. All hours worked over twelve (12) in a day Monday through Saturday, and all hours worked on Sundays and Holidays shall be paid at double the hourly rate of wage.
  - L. The first twelve (12) hours worked on a Saturday shall be paid at one and one-half times the hourly rate of wage. All hours worked on a Saturday in excess of twelve (12) hours shall be paid at double the hourly rate of pay. All hours worked over twelve (12) in a day Monday through Friday, and all hours worked on Sundays shall be paid at double the hourly rate of wage. All hours worked on a holiday shall be paid at one and one-half times the hourly rate of wage, except that all hours worked on Labor Day shall be paid at double the hourly rate of pay.
  - U. The first four (4) hours after eight (8) regular hours Monday through Friday and the first twelve (12) hours on Saturday shall be paid at one and one-half times the hourly rate of wage. (Except on makeup days if work is lost due to inclement weather, then the first eight (8) hours on Saturday may be paid the regular rate.) All hours worked over twelve (12) hours Monday through Saturday, and all hours worked on Sundays and holidays shall be paid at double the hourly rate of wage.
  - S. On a four (4) day ten (10) hour workweek scheduled Monday through Thursday, or Tuesday through Friday, work performed in excess of (10) hours shall be paid at one and one half (1-1/2) times the hourly rate of pay. On Monday through Friday, work performed outside the normal work hours of 6:00 a.m. and 6:00 p.m. shall be paid at one and one-half (1-1/2) times the straight time rate, (except for special shifts or multiple shift operations).

All hours worked on Saturdays shall be paid at one and one-half times the hourly rate of wage. All work performed on Sundays and holidays shall be paid at double the hourly rate of wage. When an employee returns to work without at least eight (8) hours time off since their previous shift, all such time shall be a continuation of shift and paid at the applicable overtime rate until such time as the employee has had a break of eight (8) hours.

Multiple Shift Operations: When the first shift of a multiple shift (a two or three shift) operation is started at the basic straight time rate or at a specific overtime rate, all shifts of that day's operation shall be completed at that rate. Special Shifts: The Special Shift Premium is the basic hourly rate of pay plus \$2.00 an hour. When due to conditions beyond the control of the employer or when an owner (not acting as the contractor), a government agency or the contract specifications require more than four (4) hours of a special shift can only be performed outside the normal 6am to 6pm shift then the special shift premium will be applied to the basic straight time for the entire shift. When an employee works on a special shift, they shall be paid the special shift premium for each hour worked unless they are in overtime or double-time status. (For example, the special shift premium does not waive the overtime requirements for work performed on Saturday or Sunday).

#### **Overtime Codes Continued**

4. V. Work performed in excess of ten (10) hours of straight time per day when four ten (10) hour shifts are established or outside the normal shift (5 am to 6pm), and all work on Saturdays, except for make-up days shall be paid at time and one-half (1 <sup>1</sup>/<sub>2</sub>) the straight time rate.

In the event the job is down due to weather conditions, then Saturday may, be worked as a voluntary make-up day at the straight time rate. However, Saturday shall not be utilized as a make-up day when a holiday falls on Friday. All work performed on Sundays and holidays and work in excess of twelve (12) hours per day shall be paid at double (2x) the straight time rate of pay.

After an employee has worked eight (8) hours at an applicable overtime rate, all additional hours shall be at the applicable overtime rate until such time as the employee has had a break of eight (8) hours.

When an employee returns to work without a break of eight (8) hours since their previous shift, all such time shall be a continuation of shift and paid at the applicable overtime rate until such time as the employee has had a break of eight (8) hours.

X. All hours worked on Saturdays shall be paid at one and one-half times the hourly rate of wage. All hours worked on Sundays and holidays shall be paid at double the hourly rate of wage. Work performed outside the normal shift of 6 am to 6pm shall be paid at one and one-half the straight time rate, (except for special shifts or three shift operations). All work performed on Sundays and holidays shall be paid at double the hourly rate of wage. Shifts may be established when considered necessary by the Employer.

The Employer may establish shifts consisting of eight (8) or ten (10) hours of work (subject to WAC 296-127-022), that shall constitute a normal forty (40) hour work week. The Employer can change from a 5-eight to a 4-ten hour schedule or back to the other. All hours of work on these shifts shall be paid for at the straight time hourly rate. Work performed in excess of eight hours (or ten hours per day (subject to WAC 296-127-022) shall be paid at one and one-half the straight time rate.

When due to conditions beyond the control of the Employer, or when contract specifications require that work can only be performed outside the regular day shift, then by mutual agreement a special shift may be worked at the straight time rate, eight (8) hours work for eight (8) hours pay. The starting time shall be arranged to fit such conditions of work.

When an employee returns to work without at a break of eight (8) hours since their previous shift, all such time shall be a continuation of shift and paid at the applicable overtime rate until such time as the employee has had a break of eight (8) hours.

# 11. ALL HOURS WORKED IN EXCESS OF EIGHT (8) HOURS PER DAY OR FORTY (40) HOURS PER WEEK SHALL BE PAID AT ONE AND ONE-HALF TIMES THE HOURLY RATE OF WAGE.

- B After an employee has worked eight (8) hours, all additional hours worked shall be paid at the applicable overtime rate until such time as the employee has had a break of eight (8) hours or more.
- C The first two (2) hours after eight (8) regular hours Monday through Friday and the first eight (8) hours on Saturday shall be paid at one and one-half times the hourly rate of wage. All other overtime hours worked, except Labor Day, and all hours on Sunday shall be paid at double the hourly rate of wage. All hours worked on Labor Day shall be paid at three times the hourly rate of wage. All non-overtime and non-holiday hours worked between 4:00 pm and 5:00 am, Monday through Friday, shall be paid at a premium rate of 15% over the hourly rate of wage.

#### **Overtime Codes Continued**

11. D. All hours worked on Saturdays and holidays shall be paid at one and one-half times the hourly rate of wage. All hours worked on Sundays shall be paid at double the hourly rate of wage.

After an employee has worked eight (8) hours, all additional hours worked shall be paid at the applicable overtime rate until such time as the employee has had a break of eight (8) hours or more.

E. The first two (2) hours after eight (8) regular hours Monday through Friday, the first ten (10) hours on Saturday, and the first ten (10) hours worked on Holidays shall be paid at one and one-half times the hourly rate of wage. All hours worked over ten (10) hours Monday through Saturday, and Sundays shall be paid at double the hourly rate of wage.

After an employee has worked eight (8) hours, all additional hours worked shall be paid at the applicable overtime rate until such time as the employee has had a break of eight (8) hours or more.

F. The first two (2) hours after eight (8) regular hours Monday through Friday and the first eight (8) hours on Saturday shall be paid at one and one-half times the hourly rate of wage. All other hours worked Monday through Saturday, and all hours worked on Sundays and holidays shall be paid at double the hourly rate of wage.

On a four-day, ten-hour weekly schedule, either Monday thru Thursday or Tuesday thru Friday schedule, all hours worked after ten shall be paid at double the hourly rate of wage. The Monday or Friday not utilized in the normal fourday, ten hour work week, and Saturday shall be paid at one-half times the hourly rate of wage for the first eight (8) hours. All other hours worked Monday through Saturday, and all hours worked on Sundays and holidays shall be paid at double the hourly rate of wage.

G. Work performed in excess of eight (8) hours of straight time per day, or ten (10) hours of straight time per day when four ten (10) hour shifts are established, or forty (40) hours of straight time per week, Monday through Friday, or outside the normal 5 am to 6pm shift, and all work on Saturdays shall be paid at one and one-half times the hourly rate of wage.

All work performed after 6:00 pm Saturday to 5:00 am Monday and Holidays, and all hours worked in excess of twelve (12) hours in a single shift shall be paid at double the hourly rate of wage.

After an employee has worked eight (8) hours at an applicable overtime rate, all additional hours shall be at the applicable overtime rate until such time as the employee has had a break of nine (9) hours or more. When an employee returns to work without at least nine (9) hours time off since their previous shift, all such time shall be a continuation of shift and paid at the applicable overtime rate until he/she shall have the nine (9) hours rest period.

H. Work performed in excess of eight (8) hours of straight time per day, or ten (10) hours of straight time per day when four ten (10) hour shifts are established, or forty (40) hours of straight time per week, Monday through Friday, or outside the normal 5 am to 6pm shift, and all work on Saturdays shall be paid at one and one-half times the hourly rate of wage.

All work performed after 6:00 pm Saturday to 5:00 am Monday and Holidays, and all hours worked in excess of twelve (12) hours in a single shift shall be paid at double the hourly rate of wage.

After an employee has worked eight (8) hours at an applicable overtime rate, all additional hours shall be at the applicable overtime rate until such time as the employee has had a break of ten (10) hours or more. When an employee returns to work without at least ten (10) hours time off since their previous shift, all such time shall be a continuation of shift and paid at the applicable overtime rate until he/she shall have the ten (10) hours rest period.

#### **Overtime Codes Continued**

- 11. J. All hours worked on holidays shall be paid at double the hourly rate of wage.
  - K. On Monday through Friday hours worked outside 4:00 am and 5:00 pm, and the first two (2) hours after eight (8) hours worked shall be paid at one and one-half times the hourly rate. All hours worked over 10 hours per day Monday through Friday, and all hours worked on Saturdays, Sundays, and Holidays worked shall be paid at double the hourly rate of wage.
  - L. An employee working outside 5:00 am and 5:00 pm shall receive an additional two dollar (\$2.00) per hour for all hours worked that shift. All hours worked on holidays shall be paid at one and one-half times the hourly rate of wage. All hours worked on holidays shall be paid at one and one-half times the hourly rate of wage.
  - M. On Monday through Friday, the first four (4) hours of overtime after eight (8) hours of straight time work shall be paid at one and one half (1-1/2) times the straight time rate of pay, unless a four (4) day ten (10) hour workweek has been established. On a four (4) day ten (10) hour workweek scheduled Monday through Thursday, or Tuesday through Friday, the first two (2) hours of overtime after ten (10) hours of straight time work shall be paid at one and one half (1-1/2) times the straight time rate of pay.

Work performed outside the normal work hours of 5:00 a.m. and 6:00 p.m. shall be paid at one and one-half (1-1/2) times the straight time rate, (except for special shifts or multiple shift operations). When the first shift of a multiple shift (a two or three shift) operation is started at the basic straight time rate or at a specific overtime rate, all shifts of that day's operation shall be completed at that rate. When due to conditions beyond the control of the Employer or when contract specifications require that work can only be performed outside the regular day shift of 5:00 am to 6:00 pm, then a special shift may be worked at the straight time rate, plus the shift pay premium when applicable. The starting time of work will be arranged to fit such conditions of work. Such shift shall consist of eight (8) hours work for eight (8) hours pay or ten (10) hours work for ten (10) hours pay for four ten shifts.

On Saturday, the first twelve (12) hours of work shall be paid at one and one half (1-1/2) times the straight time rate of pay. All work performed after 6:00 pm Saturday to 5:00 am Monday, all work performed over twelve (12) hours, and all work performed on holidays shall be paid at double the straight time rate of pay.

Shift Pay Premium: In an addition to any overtime already required, all hours worked between the hours of 6:00 pm and 5:00 am shall receive an additional two dollars (\$2.00) per hour.

N. All work performed over twelve hours in a shift and all work performed on Sundays and Holidays shall be paid at double the straight time rate.

Any time worked over eight (8) hours on Saturday shall be paid double the straight time rate, except employees assigned to work six 10-hour shifts per week shall be paid double the straight time rate for any time worked on Saturday over 10 hours.

#### **Holiday Codes**

- 5. A. Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, Friday after Thanksgiving Day, and Christmas Day (7).
  - B. Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, Friday after Thanksgiving Day, the day before Christmas, and Christmas Day (8).
  - C. Holidays: New Year's Day, Presidents' Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, the Friday after Thanksgiving Day, And Christmas Day (8).
  - D. Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, the Friday and Saturday after Thanksgiving Day, And Christmas Day (8).
  - H. Holidays: New Year's Day, Memorial Day, Independence Day, Thanksgiving Day, the Day after Thanksgiving Day, And Christmas (6).
  - I. Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, and Christmas Day (6).
  - K. Holidays: New Year's Day, Presidents' Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, Friday After Thanksgiving Day, The Day Before Christmas, And Christmas Day (9).
  - L. Holidays: New Year's Day, Martin Luther King Jr. Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, Friday after Thanksgiving Day, And Christmas Day (8).
  - N. Holidays: New Year's Day, Presidents' Day, Memorial Day, Independence Day, Labor Day, Veterans' Day, Thanksgiving Day, The Friday After Thanksgiving Day, And Christmas Day (9).
  - P. Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, Friday And Saturday After Thanksgiving Day, The Day Before Christmas, And Christmas Day (9). If A Holiday Falls On Sunday, The Following Monday Shall Be Considered As A Holiday.
  - Q. Paid Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, and Christmas Day (6).
  - R. Paid Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, Day After Thanksgiving Day, One-Half Day Before Christmas Day, And Christmas Day. (7 1/2).
  - S. Paid Holidays: New Year's Day, Presidents' Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, And Christmas Day (7).
  - Z. Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Veterans Day, Thanksgiving Day, the Friday after Thanksgiving Day, And Christmas Day (8).
- 6. G. Paid Holidays: New Year's Day, Martin Luther King Jr. Day, Presidents' Day, Memorial Day, Independence Day, Labor Day, Veterans' Day, Thanksgiving Day, the Friday after Thanksgiving Day, Christmas Day, and Christmas Eve Day (11).
  - Paid Holidays: New Year's Day, New Year's Eve Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, Friday After Thanksgiving Day, Christmas Day, The Day After Christmas, And A Floating Holiday (10).

#### **Holiday Codes Continued**

- 6. T. Paid Holidays: New Year's Day, Presidents' Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, The Friday After Thanksgiving Day, The Last Working Day Before Christmas Day, And Christmas Day (9).
  - Z. Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, Friday after Thanksgiving Day, And Christmas Day (7). If a holiday falls on Saturday, the preceding Friday shall be considered as the holiday. If a holiday falls on Sunday, the following Monday shall be considered as the holiday.
- 7. A. Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, the Friday and Saturday after Thanksgiving Day, And Christmas Day (8). Any Holiday Which Falls On A Sunday Shall Be Observed As A Holiday On The Following Monday. If any of the listed holidays falls on a Saturday, the preceding Friday shall be a regular work day.
  - B. Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, the Friday and Saturday after Thanksgiving Day, And Christmas Day (8). Any holiday which falls on a Sunday shall be observed as a holiday on the following Monday. Any holiday which falls on a Saturday shall be observed as a holiday on the preceding Friday.
  - C. Holidays: New Year's Day, Martin Luther King Jr. Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, the Friday after Thanksgiving Day, And Christmas Day (8). Any holiday which falls on a Sunday shall be observed as a holiday on the following Monday. Any holiday which falls on a Saturday shall be observed as a holiday on the preceding Friday.
  - D. Paid Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Veteran's Day, Thanksgiving Day, the Friday after Thanksgiving Day, And Christmas Day (8). Unpaid Holidays: President's Day. Any paid holiday which falls on a Sunday shall be observed as a holiday on the following Monday. Any paid holiday which falls on a Saturday shall be observed as a holiday on the preceding Friday.
  - E. Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, the Friday after Thanksgiving Day, And Christmas Day (7). Any holiday which falls on a Sunday shall be observed as a holiday on the following Monday. Any holiday which falls on a Saturday shall be observed as a holiday on the preceding Friday.
  - F. Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, the Friday after Thanksgiving Day, the last working day before Christmas day and Christmas day (8). Any holiday which falls on a Sunday shall be observed as a holiday on the following Monday. Any holiday which falls on a Saturday shall be observed as a holiday on the preceding Friday.
  - G. Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, and Christmas Day (6). Any holiday which falls on a Sunday shall be observed as a holiday on the following Monday.
  - H. Holidays: New Year's Day, Martin Luther King Jr. Day, Independence Day, Memorial Day, Labor Day, Thanksgiving Day, the Friday after Thanksgiving Day, the Last Working Day before Christmas Day and Christmas Day (9). Any holiday which falls on a Sunday shall be observed as a holiday on the following Monday. Any holiday which falls on a Saturday shall be observed as a holiday on the preceding Friday.
  - I. Holidays: New Year's Day, President's Day, Independence Day, Memorial Day, Labor Day, Thanksgiving Day, The Friday After Thanksgiving Day, The Day Before Christmas Day And Christmas Day (9). Any holiday which falls on a Sunday shall be observed as a holiday on the following Monday. Any holiday which falls on a Saturday shall be observed as a holiday on the preceding Friday.

#### **Holiday Codes Continued**

- 7. J. Holidays: New Year's Day, Independence Day, Memorial Day, Labor Day, Thanksgiving Day and Christmas Day (6). Any holiday which falls on a Sunday shall be observed as a holiday on the following Monday. Any holiday which falls on a Saturday shall be observed as a holiday on the preceding Friday.
  - K. Holidays: New Year's Day, Memorial Day, Independence Day, Thanksgiving Day, the Friday and Saturday after Thanksgiving Day, And Christmas Day (8). Any holiday which falls on a Sunday shall be observed as a holiday on the following Monday. Any holiday which falls on a Saturday shall be observed as a holiday on the preceding Friday.
  - L. Holidays: New Year's Day, Memorial Day, Labor Day, Independence Day, Thanksgiving Day, the Last Work Day before Christmas Day, And Christmas Day (7). Any holiday which falls on a Sunday shall be observed as a holiday on the following Monday. Any holiday which falls on a Saturday shall be observed as a holiday on the preceding Friday.
  - N. Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, the Friday after Thanksgiving Day, And Christmas Day (7). Any holiday which falls on a Sunday shall be observed as a holiday on the following Monday. When Christmas falls on a Saturday, the preceding Friday shall be observed as a holiday.
  - P. Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, Friday after Thanksgiving Day, And Christmas Day (7). Any holiday which falls on a Sunday shall be observed as a holiday on the following Monday.
  - Q. Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, the Friday after Thanksgiving Day, the Last Working Day before Christmas Day and Christmas Day (8). Any holiday which falls on a Sunday shall be observed as a holiday on the following Monday. If any of the listed holidays falls on a Saturday, the preceding Friday shall be a regular work day.
  - S. Paid Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, Friday after Thanksgiving Day, Christmas Day, the Day after Christmas, and A Floating Holiday (9). If any of the listed holidays falls on a Sunday, the day observed by the Nation shall be considered a holiday and compensated accordingly.
  - V. Holidays: New Year's Day, President's Birthday, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, the Friday after Thanksgiving Day, Christmas Day, the day before or after Christmas, and the day before or after New Year's Day. If any of the above listed holidays falls on a Sunday, the day observed by the Nation shall be considered a holiday and compensated accordingly.
  - W. Holidays: New Year's Day, Day After New Year's, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, the Friday after Thanksgiving Day, Christmas Eve Day, Christmas Day, the day after Christmas, the day before New Year's Day, and a Floating Holiday.
  - X. Holidays: New Year's Day, Day before or after New Year's Day, Presidents' Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, the Friday after Thanksgiving Day, Christmas Day, and the day before or after Christmas day. If a holiday falls on a Saturday or on a Friday that is the normal day off, then the holiday will be taken on the last normal workday. If the holiday falls on a Monday that is the normal day off or on a Sunday, then the holiday will be taken on the next normal workday.
  - Y. Holidays: New Year's Day, Presidents' Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, the Friday after Thanksgiving Day, and Christmas Day. (8) If the holiday falls on a Sunday, then the day observed by the federal government shall be considered a holiday and compensated accordingly.
  - Z. Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, the Friday and Saturday after Thanksgiving Day, Christmas Eve, and Christmas Day (9). Any holiday which falls on a Saturday shall be observed as a holiday on the preceding Friday. Any holiday which falls on a Sunday shall be observed as a holiday on the following Monday.

#### **Holiday Codes Continued**

- 15. G. New Year's Day, Washington's Birthday, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, The Friday After Thanksgiving Day, the last scheduled workday before Christmas, and Christmas Day (9). If any of the listed holidays falls on a Sunday, the day observed by the Nation shall be considered a holiday and compensated accordingly.
  - H. Holidays: New Year's Day, Martin Luther King Jr. Day, Independence Day, Memorial Day, Labor Day, Thanksgiving Day, the Friday after Thanksgiving Day, the Last Working Day before Christmas Day and Christmas Day (9). Any holiday which falls on a Sunday shall be observed as a holiday on the following Monday. Any holiday which falls on a Saturday shall be observed as a holiday on the preceding Friday.
  - I. Holidays: New Year's Day, President's Day, Independence Day, Memorial Day, Labor Day, Thanksgiving Day, The Friday After Thanksgiving Day, The Day Before Christmas Day And Christmas Day (9). Any holiday which falls on a Sunday shall be observed as a holiday on the following Monday. Any holiday which falls on a Saturday shall be observed as a holiday on the preceding Friday.
  - J. Holidays: New Year's Day, Independence Day, Memorial Day, Labor Day, Thanksgiving Day and Christmas Day (6). Any holiday which falls on a Sunday shall be observed as a holiday on the following Monday. Any holiday which falls on a Saturday shall be observed as a holiday on the preceding Friday.
  - K. Holidays: New Year's Day, Memorial Day, Independence Day, Thanksgiving Day, the Friday and Saturday after Thanksgiving Day, And Christmas Day (8). Any holiday which falls on a Sunday shall be observed as a holiday on the following Monday. Any holiday which falls on a Saturday shall be observed as a holiday on the preceding Friday.

#### Note Codes

- 8. D. Workers working with supplied air on hazmat projects receive an additional \$1.00 per hour.
  - L. Workers on hazmat projects receive additional hourly premiums as follows -Level A: \$0.75, Level B: \$0.50, And Level C: \$0.25.
  - M. Workers on hazmat projects receive additional hourly premiums as follows: Levels A & B: \$1.00, Levels C & D: \$0.50.
  - N. Workers on hazmat projects receive additional hourly premiums as follows -Level A: \$1.00, Level B: \$0.75, Level C: \$0.50, And Level D: \$0.25.
  - S. Effective August 31, 2012 A Traffic Control Supervisor shall be present on the project whenever flagging or spotting or other traffic control labor is being utilized. Flaggers and Spotters shall be posted where shown on approved Traffic Control Plans or where directed by the Engineer. All flaggers and spotters shall possess a current flagging card issued by the State of Washington, Oregon, Montana, or Idaho. This classification is only effective on or after August 31, 2012.
  - T. Effective August 31, 2012 A Traffic Control Laborer performs the setup, maintenance and removal of all temporary traffic control devices and construction signs necessary to control vehicular, bicycle, and pedestrian traffic during construction operations. Flaggers and Spotters shall be posted where shown on approved Traffic Control Plans or where directed by the Engineer. All flaggers and spotters shall possess a current flagging card issued by the State of Washington, Oregon, Montana, or Idaho. This classification is only effective on or after August 31, 2012.

#### Note Codes Continued

- 8. U. Workers on hazmat projects receive additional hourly premiums as follows Class A Suit: \$2.00, Class B Suit: \$1.50, And Class C Suit: \$1.00. Workers performing underground work receive an additional \$0.40 per hour for any and all work performed underground, including operating, servicing and repairing of equipment. The premium for underground work shall be paid for the entire shift worked. Workers who work suspended by a rope or cable receive an additional \$0.50 per hour. The premium for work suspended shall be paid for the entire shift worked. Workers who do "pioneer" work (break open a cut, build road, etc.) more than one hundred fifty (150) feet above grade elevation receive an additional \$0.50 per hour.
  - V. In addition to the hourly wage and fringe benefits, the following depth and enclosure premiums shall be paid. The premiums are to be calculated for the maximum depth and distance into an enclosure that a diver reaches in a day. The premiums are to be paid one time for the day and are not used in calculating overtime pay.

Depth premiums apply to depths of fifty feet or more. Over 50' to 100' - \$2.00 per foot for each foot over 50 feet. Over 101' to 150' - \$3.00 per foot for each foot over 101 feet. Over 151' to 220' - \$4.00 per foot for each foot over 220 feet. Over 221' - \$5.00 per foot for each foot over 221 feet.

Enclosure premiums apply when divers enter enclosures (such as pipes or tunnels) where there is no vertical ascent and is measured by the distance travelled from the entrance. 25' to 300' - \$1.00 per foot from entrance. 300' to 600' - \$1.50 per foot beginning at 300'. Over 600' - \$2.00 per foot beginning at 600'.

- W. Meter Installers work on single phase 120/240V self-contained residential meters. The Lineman/Groundmen rates would apply to meters not fitting this description.
- Workers on hazmat projects receive additional hourly premiums as follows Class A Suit: \$2.00, Class B Suit:
   \$1.50, Class C Suit: \$1.00, and Class D Suit: \$0.50. Special Shift Premium: Basic hourly rate plus \$2.00 per hour.

When due to conditions beyond the control of the Employer or when an owner (not acting as the contractor), a government agency or the contract specifications requires that work can only be performed outside the normal 5 am to 6pm shift, then the special shift premium will be applied to the basic hourly rate. When an employee works on a special shift, they shall be paid a special shift premium for each hour worked unless they are in OT or Double-time status. (For example, the special shift premium does not waive the overtime requirements for work performed on Saturday or Sunday.)

Y. Tide Work: When employees are called out between the hours of 6:00 p.m. and 6:00 a.m. to work on tide work (work located in the tide plane) all time worked shall be at one and one-half times the hourly rate of pay.

Swinging Stage/Boatswains Chair: Employees working on a swinging state or boatswains chair or under conditions that require them to be tied off to allow their hands to be free shall receive seventy-five cents (\$0.75) per hour above the classification rate.

Z. Workers working with supplied air on hazmat projects receive an additional \$1.00 per hour.

Special Shift Premium: Basic hourly rate plus \$2.00 per hour. When due to conditions beyond the control of the Employer or when an owner (not acting as a contractor), a government agency or the contract specifications require that more than (4) hours of a special shift can only be performed outside the normal 6 am to 6pm shift, then the special shift premium will be applied to the basic straight time for the entire shift. When an employee works on a special shift, they will be paid a special shift premium for each hour worked unless they are in overtime or double-time status. (For example, the special shift premium does not waive the overtime requirements for work performed on Saturday or Sunday.)

#### **Note Codes Continued**

9. A. Workers working with supplied air on hazmat projects receive an additional \$1.00 per hour.

Special Shift Premium: Basic hourly rate plus \$2.00 per hour. When due to conditions beyond the control of the Employer or when an owner (not acting as the contractor), a government agency or the contract specifications require that more than four (4) hours of a special shift can only be performed outside the normal 6 am to 6pm shift, then the special shift premium will be applied to the basic straight time for the entire shift. When an employee works on a special shift, they shall be paid a special shift premium for each hour worked unless they are in overtime or double-time status. (For example, the special shift premium does not waive the overtime requirements for work performed on Saturday or Sunday.)

Certified Crane Operator Premium: Crane operators requiring certifications shall be paid \$0.50 per hour above their classification rate.

Boom Pay Premium: All cranes including tower shall be paid as follows based on boom length:

(A) -130' to 199' - \$0.50 per hour over their classification rate. (B) -200' to 299' - \$0.80 per hour over their classification rate. (C) -300' and over -\$1.00 per hour over their classification rate.

B. The highest pressure registered on the gauge for an accumulated time of more than fifteen (15) minutes during the shift shall be used in determining the scale paid.

Tide Work: When employees are called out between the hours of 6:00 p.m. and 6:00 a.m. to work on tide work (work located in the tide plane) all time worked shall be at one and one-half times the hourly rate of pay. Swinging Stage/Boatswains Chair: Employees working on a swinging stage or boatswains chair or under conditions that require them to be tied off to allow their hands to be free shall receive seventy-five cents (\$0.75) per hour above the classification rate.

C. Tide Work: When employees are called out between the hours of 6:00 p.m. and 6:00 a.m. to work on tide work (work located in the tide plane) all time worked shall be at one and one-half times the hourly rate of pay. Swinging Stage/Boatswains Chair: Employees working on a swinging stage or boatswains chair or under conditions that require them to be tied off to allow their hands to be free shall receive seventy-five cents (\$0.75) per hour above the classification rate.

Effective August 31, 2012 – A Traffic Control Supervisor shall be present on the project whenever flagging or spotting or other traffic control labor is being utilized. A Traffic Control Laborer performs the setup, maintenance and removal of all temporary traffic control devices and construction signs necessary to control vehicular, bicycle, and pedestrian traffic during construction operations. Flaggers and Spotters shall be posted where shown on approved Traffic Control Plans or where directed by the Engineer. All flaggers and spotters shall possess a current flagging card issued by the State of Washington, Oregon, Montana, or Idaho. These classifications are only effective on or after August 31, 2012.

- D. Industrial Painter wages are required for painting within industrial facilities such as treatment plants, pipelines, towers, dams, bridges, power generation facilities and manufacturing facilities such as chemical plants, etc., or anywhere abrasive blasting is necessary to prepare surfaces, or hazardous materials encapsulation is required.
- E. Heavy Construction includes construction, repair, alteration or additions to the production, fabrication or manufacturing portions of industrial or manufacturing plants, hydroelectric or nuclear power plants and atomic reactor construction. Workers on hazmat projects receive additional hourly premiums as follows -Level A: \$1.00, Level B: \$0.75, Level C: \$0.50, And Level D: \$0.25.
- F. Industrial Painter wages are required for painting within industrial facilities such as treatment plants, pipelines, towers, dams, power generation facilities and manufacturing facilities such as chemical plants, etc., or anywhere abrasive blasting is necessary to prepare surfaces, or hazardous materials encapsulation is required.

#### **Note Codes Continued**

9. H. One (1) person crew shall consist of a Party Chief. (Total Station or similar one (1) person survey system). Two (2) person survey party shall consist of a least a Party Chief and a Chain Person. Three (3) person survey party shall consist of at least a Party Chief, an Instrument Person, and a Chain Person.

### **APPENDIX B**

#### **BID PROPOSAL DOCUMENTS**

INCLUDING:

Notice to Contractor

**Proposal Form** 

**Non-Collusion Declaration** 

**Proposal Signature Page** 

**Certification of Compliance with Wage Payment Statutes** 



## Lewis County Department of Public Works

Josh S Metcalf, PE, Director

Tim Fife, PE, County Engineer

#### NOTICE TO CONTRACTORS

NOTICE IS HEREBY GIVEN that the Board of County Commissioners of Lewis County or designee, will open sealed proposals and publicly read them aloud at or after 12:15 p.m. on **Thursday, June 22**, **2023**, at the Lewis County Courthouse in Chehalis, Washington for the Pigeon Springs Road HMA Project, CRP 2200C.

#### SEALED BIDS MUST BE DELIVERED BY OR BEFORE 12:15 P.M. on Thursday, June 22, 2023

(Lewis County official time is displayed on Axxess Intertel phones in the office of the Board of County Commissioners. Bids submitted after 12:15 PM will not be considered for this project.)

Sealed proposals must be delivered to the Clerk of the Board of Lewis County Commissioners (351 N.W. North Street, Room 210, CMS-01, Chehalis, Washington 98532), by or before **12:15 P.M.** on the date specified for opening, and in an envelope clearly marked: *"SEALED BID FOR THE PIGEON SPRINGS ROAD HMA PROJECT, CRP 2200C, TO BE OPENED ON OR AFTER 12:15 P.M. ON THURSDAY, JUNE 22, 2023".* 

All bid proposals shall be accompanied by a bid proposal deposit in cash, certified check, cashier's check or surety bond in an amount equal to five percent (5%) of the amount of such bid proposal. Should the successful bidder fail to enter into such contract and furnish satisfactory contract bond within the time stated in the specifications, the bid proposal deposit shall be forfeited to the Lewis County Public Works Department.

Informational copies of maps, plans and specifications are on file for inspection in the office of the County Engineer of Lewis County in Chehalis, Washington. The contract documents may be viewed and downloaded from Lewis County's Web Site @ www.lewiscountywa.gov or you may call the Lewis County Engineers office @ (360) 740-1123 Ext. 7 and request a copy be mailed to you. All Contractor questions and Lewis County clarifying answers will be posted on our website. Plan or specification changes shall be accomplished through official project addendums.

The Lewis County Public Works Department in accordance with the provisions of Title VI of the Civil Rights Act of 1964 (78 Stat. 252, 42 U.S.C. 2000d to 2000d-4) and the Regulations, hereby notifies all bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement, disadvantaged business enterprises will be afforded full and fair opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award.

#### PROPOSAL

#### TO: BOARD OF COUNTY COMMISSIONERS LEWIS COUNTY CHEHALIS, WASHINGTON 98532

This certifies that the undersigned has examined the location of the Pigeon Springs Road HMA Project, CRP 2200C, in Lewis County, Washington, and that the plans, specifications and contract governing the work embraced in these improvements, and the method by which payment will be made for said work is understood. The undersigned hereby proposes to undertake and complete the work embraced in this improvement, or as much thereof as can be completed with the money available in accordance with the said plans, specifications and contract, and the following schedules of rates and prices:

NOTE:

Unit prices for all items, all extensions, and total amount of bid shall be shown: All entries must be typed or entered in ink.

ITEM NO.	PLAN QUANTITY	ITEM DESCRIPTION	UNIT PRICE DOLLARS CENTS	AMOUNT DOLLARS CENTS
1	1 L.S.	Mobilization	LUMP SUM	\$
2	1.10 Mile	Shoulder Finishing	\$	\$
3	138 S.Y.	Planing Bituminous Pavement	\$	\$
4	1,135 Ton	HMA For Prelevel CL. 3/8 In. PG 58H-22 Fiber Reinforced	\$	\$
5	695 Ton	HMA CL. 3/8 In. PG 58H-22 Fiber Reinforced	\$	\$
6	1 L.S.	Project Temporary Traffic Control	LUMP SUM	\$
7	2,900 L.F.	Temporary Pavement Marking - Short Duration	\$	\$
8	2,900 L.F.	Wattles	\$	\$
9	1 L.S.	Trimming and Cleanup	LUMP SUM	\$
10	1 L.S.	SPCC Plan	LUMP SUM	\$
			TOTAL BID	\$

Failure to return this Declaration as part of the bid proposal package will make the bid nonresponsive and ineligible for award.

#### NON-COLLUSION DECLARATION

I, by signing the proposal, hereby declare, under penalty of perjury under the laws of the United States that the following statements are true and correct:

- That the undersigned person(s), firm, association or corporation has (have) not, either directly or indirectly, entered into any agreement, participated in any collusion, or otherwise taken any action in restraint of free competitive bidding in connection with the project for which this proposal is submitted.
- That by signing the signature page of this proposal, I am deemed to have signed and to have agreed to the provisions of this declaration.

#### NOTICE TO ALL BIDDERS

To report rigging activities call:

#### 1-800-424-9071

The U.S. Department of Transportation (USDOT) operates the above toll-free "hotline" Monday through Friday, 8:00 a.m. to 5:00 p.m., eastern time. Anyone with knowledge of possible bid rigging, bidder collusion, or other fraudulent activities should use the "hotline" to report such activities.

The "hotline" is part of USDOT's continuing effort to identify and investigate highway construction contract fraud and abuse and is operated under the direction of the USDOT Inspector General. All information will be treated confidentially and caller anonymity will be respected.

SR

DOT Form 272-036I EF 07/2011 The bidder is hereby advised that by signature of this proposal he/she is deemed to have acknowledged all requirements and signed all certificates contained herein.

A proposal guaranty in an amount of five percent (5%) of the total bid, based upon the approximate estimate of quantities at the above prices and in the form as indicated below, is attached hereto:

CASH		OF	
CASHIER'S CHECK	<		_ DOLLARS
CERTIFIED CHECK	< 🗌 (\$) P	AYABLE TO THE LEWIS COUNTY T	REASURER
PROPOSAL BOND		OF 5% OF THE BID	
** Receipt is hereby acknow	vledged of addendum(s)	No.(s),,,	, &
SIGNATURE OF AL	JTHORIZED OFFICIAL(S	3)	
Proposal Must be Sig	gned		
	Firm Name		
	Address		
State of Washington Contrac	ctor's License No.		
Unified Business Ide	ntifier (U.B.I.) No.		
	Telephone No.		
	Federal ID No.		

#### Note:

This proposal form is not transferable and any alteration of the firm's name entered hereon without prior permission from the Lewis County Engineer will be cause for considering the proposal irregular and subsequent rejection of the bid.

\*Attach Power of Attorney



#### Contractor Certification Wage Law Compliance - Responsibility Criteria Washington State Public Works Contracts

# FAILURE TO RETURN THIS CERTIFICATION AS PART OF THE BID PROPOSAL PACKAGE WILL MAKE THIS BID NONRESPONSIVE AND INELIGIBLE FOR AWARD

I hereby certify, under penalty of perjury under the laws of the State of Washington, on behalf of the firm identified below that, to the best of my knowledge and belief, this firm has <u>NOT</u> been determined by a final and binding citation and notice of assessment issued by the Washington State Department of Labor and Industries or through a civil judgment entered by a court of limited or general jurisdiction to have willfully violated, as defined in RCW 49.48.082, any provision of RCW chapters 49.46, 49.48, or 49.52 within three (3) years prior to the date of the Call for Bids.

Bidder Name:				
Name of Contractor/Bidder - Print full legal entity name of firm				
Ву:				
Signature of authorized person	Print Name of person making certifications for firm			
Title:	Place:			
Title of person signing certificate	Print city and state where signed			
Date:				

Form 272-009 08/2017

## **APPENDIX C**

**CONTRACT DOCUMENTS** 

INCLUDING:

**Contract Form** 

**Contract Bond** 

**Power Equipment List** 

#### CONTRACT

THIS AGREEMENT, made and entered into this \_\_\_\_\_ day of \_\_\_\_\_\_, 2023, between the BOARD OF COUNTY COMMISSIONERS of LEWIS COUNTY, State of Washington, acting under and by virtue of RCW 36.77.040, hereinafter called

the Board, and of

for\_\_\_sel\_\_\_, heirs, executors, administrators, successors and assigns, hereinafter called the Contractor.

#### WITNESSETH:

That in consideration of the payments, covenants and agreements hereinafter mentioned to be made and performed by the parties hereto, the parties hereto covenant and agree as follows:

#### DESCRIPTION OF WORK:

1. The Contractor shall do all work and furnish all material necessary to improve Pigeon Springs Road by planning bituminous pavement, and paving roadway with HMA, and other work, all in Lewis County Washington, in accordance with and as described in the attached plans and specifications, and in full compliance with the terms, conditions and stipulations herein set forth and attached, now referred to and by such reference incorporated herein and made a part hereof as fully for all purposes as if here set forth at length, and shall perform any alterations in or additions to the work covered by this contract and every part thereof and any extra work which may be ordered as provided in this contract and every part thereof.

The Contractor shall provide and be at the expense of all materials, labor, carriage, tools, implements and conveniences and things of every description that may be requisite for the transfer of materials and for constructing and completing the work provided for in this contract and every part thereof.

2. The County hereby promises and agrees with the Contractor to hire and does hire the Contractor to provide the materials and to do and cause to be done the above described work and to complete and furnish the same according to the attached plans and specifications and the terms and conditions herein contained, and hereby contracts to pay for the same according to the schedule of unit or itemized prices at the time and in the manner and upon the conditions provided for in this contract and every part thereof. The County further agrees to hire the contractor to perform any alterations in or conditions to the work covered by this contract and every part thereof and any force account work that may be ordered and to pay for the same under the terms of this contract and the attached plans and specifications.

3. The Contractor for himself, and for his heirs, executors, administrators, successors and assigns, does hereby agree to the full performance of all the covenants herein contained upon the part of the Contractor.

4. It is further provided that no liability shall attach to the County be reason of entering into this contract, except as expressly provided herein.

#### Contract - 1

#### 5. <u>CANCELLATION OF CONTRACT FOR VIOLATION OF STATE POLICY</u>

This contract, pursuant to RCW 49.28.040 to RCW 49.28.060, may be canceled by the officers or agents of the Owner authorized to contract for or supervise the execution of such work, in case such work is not performed in accordance with the policy of the State of Washington.

#### 6. DOCUMENTS COMPRISING CONTRACT

All documents hereto attached, including but not being limited to the advertisement for bids, information for bidders, bid proposal form, general conditions (if any), special conditions (if any), complete specifications and the complete plans, are hereby made a part of this contract.

IN WITNESS WHEREOF, the said Contractor has executed this instrument, and the said Board of County Commissioners of aforesaid County, pursuant to resolution duly adopted, has caused this instrument to be executed by and in the name of said Board by its Chairman, duly attested by its Clerk, the day and year first above written, and the seal of said Board to be hereunto affixed on the date in this instrument first above written.

	Ву:		
	Contractor		
APPROVED AS TO FORM:	Performance of foregoing contract assured in accordance with the terms of the accompanying bond.		
JONATHAN MEYER Prosecuting Attorney	Dated:, 2023 By: Surety		
By: Civil Deputy	By: Attorney-in-fact		
	APPROVED:		
	County Engineer		

#### Contract – 2

#### **CONTRACT BOND FOR** LEWIS COUNTY, WASHINGTON

Bond No.

WE.	d/b/a		
(Insert legal name of Contractor)	(Insert trade name of Contractor, if any)		
United States of America) equal to the total compens	(hereinafter "Surety"), are held and firmly ereinafter "County"), as Obligee, in an amount (in lawful money of the ation and expense reimbursement payable to Principal for satisfactory		
	<u><b>RP 2200C</b></u> between Principal and County, which total is <i>initially</i>		
themselves, their executors, administrators, legal repr presents Said contract (hereinafter referred to as "th part hereof by this reference. The Contract includes	resentatives, successors and assigns, jointly and severally, firmly by these he Contract") is for the <b>Pigeon Springs Road HMA Project</b> and is made a the original agreement as well as all documents attached thereto or made a rother document modifying, adding to or deleting from said Contract any		

This Bond is executed in accordance with the laws of the State of Washington, and is subject to all provisions thereof and the ordinances of County insofar as they are not in conflict therewith, and is entered into for the use and benefit of County, and all laborers, mechanics, subcontractors, and materialmen, and all persons who supply such person or persons, or subcontractors, with provisions or supplies for the carrying on of the work covered by Contract No. <u>CRP 2200C</u> between the below-named Contractor and County for the <u>Pigeon Springs Road HMA Project</u>, a copy of which Contract, by this reference is made a part hereof and is hereinafter referred to as "the Contract." (The Contract as defined herein includes the aforesaid agreement together with all of the Contract documents including addenda, exhibits, attachments, modifications, alterations, and additions thereto, deletions therefrom, amendments and any other document or provision attached to or incorporated into the Contract)

**THE CONDITION OF THIS OBLIGATION** is such that if Contractor shall promptly and faithfully perform the Contract, then this obligation shall be null and void; otherwise it shall remain in full force and effect.

#### THE PARTIES FURTHER ACKNOWLEDGE & AGREE AS FOLLOWS:

(1) Surety hereby consents to, and waives notice of, any alteration, change order, or other modification of the Contract and any extension of time made by County, except that any single or cumulative change order amounting to more than twenty-five percent (25%) of the penal sum of this bond shall require Surety's written consent.

(2) Surety recognizes that the Contract includes provisions for additions, deletions, and modifications to the work or Contract Time and the amounts payable to Contractor. Subject to the limitations contained in paragraph (1) above, no such change or any combination thereof, shall void or impair Surety's obligation hereunder.

(3) Surety is subject to the provisions contained in Section 1-03.4, "Contract Bond," of the Washington State Department of Transportation (WSDOT) Standard Specifications for Road, Bridge, and Municipal Construction. And such provisions are incorporated by reference. A copy may be viewed at WSDOT's website www.wsdot.wa.gov/fasc/EngineeringPublications/Manuals/.

(4) Whenever County has declared Contractor to be in default and County has given Surety written notice of such declaration, Surety shall promptly (in no event more than thirty [30] days following receipt of such notice), specify, in written notice to County, which of the following actions Surety intends to take to remedy such default, and thereafter shall:

(a) Remedy the default within fifteen (15) days after its notice to County, as stated in such notice; or

(b) Assume within fifteen (15) days following its notice to County, full responsibility for the completion of the Contract in accordance with all of its provisions, as stated in such notice, and become entitled to payment of the balance of the Contract sum as provided in the Contract; or

(c) Pay County upon completion of the Contract, in cash, the cost of completion together with all other reasonable costs and expenses incurred by County as a result of Contractor's default, including but not limited to those incurred by County to mitigate its losses, which may include but are not limited to attorneys' fees and the cost of efforts to complete the work prior to Surety's exercising any option available to it under this Bond; or

(d) Obtain a bid or bids for completing the Contract in accordance with its terms and conditions, and upon a determination by County and Surety jointly of the lowest responsible bidder, arrange for one or more agreements between such bidder and County, and make available as work progresses (even though there is a default or a succession of defaults under such agreement(s) for completion arranged for under this paragraph) sufficient funds to pay the cost of completion less the balance of the Contract price, but not exceeding, including other costs and damages for which Surety may be liable hereunder, the penal sum of this Bond. The term "balance of the Contract price," as used in this paragraph, shall mean the total amount payable by County to Contractor under the Contract, less the amount properly paid by County to Contractor.

(5) If County commences suit and obtains judgment against Surety for recovery hereunder, then Surety, in addition to such judgment, shall pay all costs and attorneys' fees incurred by County in enforcement of County's rights hereunder. The venue for any action arising out of or in connection with this bond shall be in Lewis County. Washington.

(6) No right or action shall accrue on this Bond to or for the use of any person or corporation other than Lewis County, except as herein provided.

(7) No rider, amendment or other document modifies this Bond except as follows, which by this reference is incorporated herein:

**SURETY'S QUALIFICATIONS:** Every Surety named on this bond must appear on the United States Treasury Department's most current list (Circular 570 as amended or superseded) and be authorized by the Washington State Insurance Commissioner to transact business as a surety in the State of Washington. In addition, the Surety must have a current rating of at least A-:VII in A. M. Best's <u>Key Rating Guide</u>.

**INSTRUCTIONS FOR SIGNATURES:** This bond must be signed by the president or a vice-president of a corporation; the managing general partner of a partnership; managing joint venturer of a joint venture; manager of a limited liability company or, if no manager has been designated, a member of such LLC; a general partner of a limited liability partnership; or the owner(s) of a sole proprietorship. If the bond is signed by any other representative, the Principal must attach <u>currently-dated</u>, written proof of that signer's authority to bind the Principal, identifying and quoting the provision in the corporate articles of incorporation, bylaws, Board resolution, partnership agreement, certificate of formation, or other document authorizing delegation of signature authority to such signer, and confirmation acceptable to the County that such delegation was in effect on the date the bond was signed. A NOTARY PUBLIC MUST ACKNOWLEDGE EACH SIGNATURE BELOW.

#### FOR THE SURETY:

#### FOR THE PRINCIPAL:

By	By:
(Signature of Attorney-in-Fact)	(Signature of authorized signer for Contractor)
(Type or print name of Attorney-in-Fact)	(Type or print name of signer for Contractor)
(Type or print telephone number for Attorney-in-Fact)	(Type or print title of signer for Contractor)
STATE OF)	
) ss: COUNTY OF)	ACKNOWLEDGMENT FOR CONTRACTOR
personally appeared, the that signed and sealed said bond as the free and v	y public in and for the State of, duly commissioned and sworn, person described in and who executed the foregoing bond, and acknowledged to me oluntary act and deed of the Contractor so identified in the foregoing bond for the tt is authorized to execute said bond for the Contractor named therein. and year in this certificate first above written.
(Signature of Notary Public)	(Print or type name of Notary Public)
(Signature of Notary Public) Notary Public in and for the State of My commission expires	residing at SEAL >
STATE OF) ) ss: COUNTY OF)	ACKNOWLEDGMENT FOR SURETY
personally appeared, Attor bond to be the free and voluntary act and deed of the Surety authorized to execute said bond on behalf of the Surety, and	tary public in and for the State of, duly commissioned and sworn, mey-in-Fact for the Surety that executed the foregoing bond, and acknowledged said of the uses and purposes therein mentioned, and on oath stated that is I that the seal affixed on said bond or the annexed Power of Attorney is the corporate reto affixed the day and year in this certificate first above written.
(Signature of Notary Public)	(Print or type name of Notary Public)
Notary Public in and for the State of	residing at
My commission expires	SEAL →

#### POWER EQUIPMENT LIST

The undersigned furthermore certifies that he/she is thoroughly aware that time is of the essence for the completion of this contract within the time specified in the special provisions, and hereby agrees to provide the Engineer a list of his power equipment to be used on this project.

This equipment list will be used in computing any Force Account that may be performed within this contract.

#### The Contractor must complete this form in its entirety.


#### **POWER EQUIPMENT**

Type of Equipment	Make	Model Number	Serial Number	* Capacity	Year Built

## **APPENDIX D**


**CONTRACT PLANS** 

# PIGEON SPRINGS ROAD HMA PROJECT



LENGIF	
SUMMARY C	
ITEM	ITEM
DESCRIPTION	NO.
PREP	
MOBILIZATION	1
SUR	
SHOULDER FINISHING	2
HOT MI	
PLANING BITUMINOUS PAVEMENT	3
HMA FOR PRELEVEL CL. 3/8 IN. PG 58H-22 FIBER REINFOR	4
HMA CL. 3/8 IN. PG 58H-22 FIBER REINFORCED	5
TR	
PROJECT TEMPORARY TRAFFIC CONTROL	6
<b>TEMPORARY PAVEMENT MARKING - SHORT DURATION</b>	7
EROSIO	
WATTLES	8
0	
TRIMMING AND CLEANUP	9
SPILL PREVENTION CONTROL AND CONTERMEASURE PLA	10

## VICINITY MAP



#### M.P. 0.00 - M.P. 0.55 LENGTH 2907 L.F.

DF QUANTITIES				
	TOTAL	UNIT		
	QUANTITY			
PARATION				
	LUMP SUM	LUMP SUM		
RFACING	•			
	1.10	MILE		
IX ASPHALT		-		
	138	S.Y.		
CED	1135	TON		
	695	TON		
RAFFIC		-		
	LUMP SUM	LUMP SUM		
	2900	L.F.		
N CONTROL				
	2900	L.F.		
THER	•	•		
	LUMP SUM	LUMP SUM		
AN .	LUMP SUM	LUMP SUM		